

IRAQ AERONAUTICAL INFORMATION PUBLICATION (AIP)

ARRANGEMENTS AND PROCEDURES FOR FLIGHT OPERATIONS IN IRAQ AIRSPACE

1. The Combined Forces Air Component Commander (CFACC) is the Airspace Control Authority (ACA) for Iraq and the Baghdad FIR. Although the transition to transferring the approval process to the Iraq Civil Aviation Authority (ICAA) is underway, all aircraft require ACA approval to land at or depart from an aerodrome within, or to overfly, the Baghdad FIR. Such approval is to be obtained by contacting the Regional Air Movement Control Center (RAMCC) Iraq via the procedures described in AIP GEN 1.2.

2. The Iraq AIP is formatted in accordance with Annex 14 to the Convention on International Civil Aviation. The procedures contained in this AIP are designed for the safety of all aircraft flying in the Baghdad FIR, particularly humanitarian aid (HA) flights carried out by the United Nations, Non-Governmental Organizations (NGOs), other International Organizations (IOs), military flights and authorized civilian and State flights. Operators must review Notice to Airmen (NOTAMs) regularly for changes affecting the information in this document.

3. Operators organizing and/or conducting flights in the Baghdad FIR must comply with all regulations specified in Iraq AIP. Particular attention should be paid to the following AIP entries:

Baghdad Flight Information Region (FIR) Control Authority.....	GEN 1.2
Emergencies and Search and Rescue (SAR).....	GEN 3.6
Risks to Flight and Compliance with These Procedures.....	GEN 1.2.1.5
	ENR 5.3
Restrictions to Civil Aircraft Operations.....	ENR 1.1.4.5
Slot Time Allocation Procedures.....	GEN 1.2.1.3
	GEN 1.2.1.13
Required Navigation Performance Criteria.....	GEN 1.5.2
	ENR 1.3.2
Transponder Codes.....	GEN 1.2.1.2
NOTAM Information.....	GEN 3.1.3.5.1
Meteorological Information.....	GEN 3.5.3
International Agreements.....	ENR 1.8.3
Flight Rules	ENR 1.1.4
	ENR 1.2
	ENR 1.3
Altimeter Setting Procedures.....	ENR 1.7
Airspace Classification.....	ENR 1.4
Flight Planning.....	ENR 1.10
	ENR 1.11
Route Descriptions.....	ENR 3.3
Mandatory Routing.....	ENR 3.5.1
Enroute Holding Procedures.....	ENR 3.6
Radio and Radar Failure procedures.....	ENR 1.6.3
Separation.....	ENR 1.8.2
Intercept Procedures.....	ENR 1.12
Air Traffic Incidents.....	ENR 1.14
Terminal Air Traffic Control.....	ENR 1.1.5
	ENR 1.1.6
Airport Information	AD 2.1

IRAQ AERONAUTICAL INFORMATION PUBLICATION (AIP)

SUMMARY OF CHANGES

1. The following table provides a summary of notable or significant changes. Changes correcting spelling mistakes, syntax errors and formatting errors are not listed.

2. This Summary of Changes is made with all due care but should not be used exclusively or without reference to the AIP. Moreover, this Summary of Changes is provided only to assist with the effective use and maintenance of the Iraq AIP and is not an authoritative document in its own right.

Paragraph / Page	Description of Change
GEN 1.2.1.3	Baghdad FIR Approving Authority
GEN 1.2.1.7.1.2 and 3	Overflight of Baghdad FIR
GEN 1.2.1.8.5.1	Customs and Immigration requirements
GEN 2.1.22	Summer and Winter period timings Baghdad FIR
GEN 3.1.3.2	AIP publishing and amendment
GEN 3.1.4.1	AIP full edition amendment dates
ENR 1.4.1.3 - 5	Baghdad FIR Class D, E and G airspace. Established CTAF VHF 122.0
ENR 1.8.3.3	Agreement with Syria
ENR 2.1.2	Terminal Control Areas (TMA). Baghdada TMA established. Balad TMA modified.
ENR 3.3.1.3	Area Navigation Route description. ATS route L200 included. Additional waypoints added to existing routes.
AD ORBI 2.12	PCN change
AD ORBD	RWY dimension change
AD ORSU and ORTF	Numerous changes to airfield facilities



جمهورية العراق

دليل الطيران العراقي

**REPUBLIC OF IRAQ
AERONAUTICAL INFORMATION PUBLICATION
(AIP)**

EIGHTEENTH EDITION

Effective 11 May 2006

CONSULT NOTAMs FOR LATEST INFORMATION

IRAQ CIVIL AVIATION AUTHORITY

**PART 1
GENERAL (GEN)**

PART 1 – GENERAL (GEN)

GEN 0.1 PREFACE

0.1.1 Name of publishing authority. The Iraq AIP is published by authority of the Iraq Civil Aviation Authority

0.1.2 Applicable ICAO documents. The AIP is prepared in accordance with the Standards and Recommended Practices (SARPS) of Annex 15 to the Convention on International Civil Aviation and the Aeronautical Information Services Manual (ICAO Doc 8126) and Annex 14 to the Convention on International Civil Aviation. Charts contained in the AIP are produced in accordance with Annex 4 to the Convention on International Civil Aviation and the Aeronautical Chart Manual (ICAO Doc 8697). Differences from ICAO Standards, Recommended Practices and Procedures are detailed in subsection GEN 1.7.

0.1.3 The AIP structure and established regular amendment interval

0.1.3.1 The AIP forms part of the Integrated Aeronautical Information Package, details of which are given in Subsection GEN 3.1. The principal AIP structure is shown in graphic form on page GEN 0.1-4. The AIP consists of three parts; General (GEN), En-route (ENR) and Aerodromes (AD). Each part is divided into sections and subsections, as applicable.

Part 1 – General (GEN)

Part 1 consists of five sections containing information as briefly described below.

GEN 0	Preface; Record of AIP Amendments; Record of AIP Supplements; Checklist of AIP Pages; List of Hand Amendments to the AIP; and Table of Contents to Part 1.
GEN 1	National Regulations and Requirements - Designated authorities; Entry; Transit and Departure of Aircraft; Transit and Departure of Passengers and Crew; Entry, Transit and Departure of Cargo; Aircraft Instruments, Equipment and Flight Documents; Summary of National Regulations and International Agreements/Conventions; and Differences from ICAO Standards, Recommended Practices and Procedures.
GEN 2	Tables and Codes - Measuring System, Aircraft Markings and Holidays; Abbreviations used in AIP; Chart Symbols; Location Indicators; List of Radio Navigation Aids; Conversion Tables; and Sunrise/Sunset Tables.
GEN 3	Services – Aeronautical Information Services; Aeronautical Charts; Air Traffic Services; Communication Services; Meteorological Services; and Search and Rescue.
GEN 4	Fees and Charges.

Part 2 – En-route (ENR)

Part 2 consists of seven sections containing information as briefly describe below.

- ENR 0 Preface; Record of AIP Amendment; Record of AIP Supplements; Checklist of AIP Pages; List of Hand Amendments to the AIP; and the Table of Contents to Part 2.
- ENR 1 General Rules and Procedures - General Rules; Instrument Flight Rules; ATS Airspace Classification; Holding; Approach and Departure Procedures; Radar Services and Procedures; Altimeter Setting Procedure; Regional Supplementary Procedures; Air Traffic Flow Management; Flight Planning; Addressing Of Flight Plan Message; Interception Of Civil Aircraft; Unlawful Interference and Air Traffic Incidents.
- ENR 2 Air Traffic Services (ATS) Airspace - Detailed Description of Flight Information Regions (FIR) and Terminal Control Areas (TMA).
- ENR 3 ATS Routes.
- ENR 4 Radio Navigation Routes Aids/Systems - Radio Navigation Aids - En-Route; Name-Code Designators for Significant Points; and Aeronautical Ground Lights - En-Route.
- ENR 5 Navigation Warnings - Prohibited, Restricted and Danger Areas.
- ENR 6 En-Route Charts - En-route Chart – ICAO and Index Charts.

Part 3 - Aerodromes (AD)

Part 3 consists of three sections containing information as briefly described below.

- AD 0 Preface; Record of AIP Amendments; Record of AIP Supplements; Checklist of AIP Pages; List of Hand Amendments to the AIP; and the Table of Contents to Part 3.
- AD 1 Introduction - Aerodrome Availability; Rescue and Fire Fighting Services; and Index to Aerodromes.
- AD 2 Detailed Information about Aerodromes.

0.1.3.2 Regular Amendment Interval. Amendments to the AIP will be promulgated each 28 days by way of either a complete AIP amendment, i.e. a full edition issue, or by way of an AIP Amendment bulletin. Immediate advice of errors and their correction will be made by way of a Baghdad FIR NOTAM.

4. Service to contact in case of detected AIP errors or omissions. In the compilation of the AIP, care has been taken to ensure that the information contained therein is accurate and complete. Any errors and omissions, which may nevertheless be detected, as well as any correspondence concerning the publications mentioned in this preface, should be referred to the following agencies:


IRAQ CIVIL AVIATION AUTHORITY

Telephone: + 964 7901418903

E-mail: ibiap1@yahoo.com

**IRAQ AIP DEVELOPER
ON BEHALF OF AIRSPACE CONTROL AUTHORITY**

E-mail: iraq.aip.dev@auab.centaf.af.mil



GEN 0.2 RECORD OF AIP AMENDMENTS

[illegible][illegible]

GEN 0.3 RECORD OF AIP SUPPLEMENTS

Serial No.	Subject	Section(s) affected	Period of validity	Cancellation record
A01/06	ICAO location indicators and weather codes	GEN 2.4.2	16Feb-16Mar	AIP Ed 17
A02/06	Iraq Airways route data	ENR 3.3.1	16Feb-19Feb	AIP Sup A04/06
A03/06	Aerodrome Information	Various	16Feb-16Mar	AIP Ed 17
A04/06	Iraq Airways route data	ENR 3.3.1	19Feb-16Mar	AIP Ed 17

GEN 0.4 AIP IRAQ		PAGE CHECKLIST			
PAGE	DATE	PAGE	DATE	1.2-1	11 MAY 06
PART 1 - GENERAL (GEN)		2.3-2	11 MAY 06	1.2-2	11 MAY 06
		2.4-1	11 MAY 06	1.2-3	11 MAY 06
		2.4-2	11 MAY 06	PAGE	DATE
GEN 0		2.5-1	11 MAY 06	1.3-1	11 MAY 06
0.1-1	11 MAY 06	2.6-1	11 MAY 06	1.3-2	11 MAY 06
0.1-2	11 MAY 06	2.7-1	11 MAY 06	1.4-1	11 MAY 06
0.1-3	11 MAY 06	2.7-2	11 MAY 06	1.4-2	11 MAY 06
0.1-4	11 MAY 06	2.7-3	11 MAY 06	1.4-3	11 MAY 06
0.1-5	11 MAY 06	2.7-4	11 MAY 06	1.4-4	11 MAY 06
0.2-1	11 MAY 06			1.4-5	11 MAY 06
0.3-1	11 MAY 06	GEN 3		1.5-1	11 MAY 06
0.4-1	11 MAY 06	3.1-1	11 MAY 06	1.5-2	11 MAY 06
0.4-2	11 MAY 06	3.1-2	11 MAY 06	1.5-3	11 MAY 06
0.4-3	11 MAY 06	3.1-3	11 MAY 06	1.5-4	11 MAY 06
0.5-1	11 MAY 06	3.1-4	11 MAY 06	1.6-1	11 MAY 06
0.6-1	11 MAY 06	3.2-1	11 MAY 06	1.6-2	11 MAY 06
0.6-2	11 MAY 06	3.2-2	11 MAY 06	1.6-3	11 MAY 06
		3.2-3	11 MAY 06	1.7-1	11 MAY 06
GEN 1		3.3-1	11 MAY 06	1.7-2	11 MAY 06
1.1-1	11 MAY 06	3.3-2	11 MAY 06	1.8-1	11 MAY 06
1.2-1	11 MAY 06	3.3-3	11 MAY 06	1.8-2	11 MAY 06
1.2-2	11 MAY 06	3.4-1	11 MAY 06	1.8-3	11 MAY 06
1.2-3	11 MAY 06	3.4-2	11 MAY 06	1.8-4	11 MAY 06
1.2-4	11 MAY 06	3.4-3	11 MAY 06	1.9-1	11 MAY 06
1.2-5	11 MAY 06	3.4-4	11 MAY 06	1.10-1	11 MAY 06
1.2-6	11 MAY 06	3.5-1	11 MAY 06	1.10-2	11 MAY 06
1.2-7	11 MAY 06	3.5-2	11 MAY 06	1.11-1	11 MAY 06
1.2-8	11 MAY 06	3.6-1	11 MAY 06	1.12-1	11 MAY 06
1.2-9	11 MAY 06	3.6-2	11 MAY 06	1.12-2	11 MAY 06
1.2-10	11 MAY 06	3.6-3	11 MAY 06	1.12-3	11 MAY 06
1.3-1	11 MAY 06	3.6-4	11 MAY 06	1.12-4	11 MAY 06
1.4-1	11 MAY 06			1.13-1	11 MAY 06
1.4-2	11 MAY 06	GEN 4		1.14-1	11 MAY 06
1.5-1	11 MAY 06	4.1-1	11 MAY 06	1.14-2	11 MAY 06
1.6-1	11 MAY 06	4.1-2	11 MAY 06	1.14-3	11 MAY 06
1.7-1	11 MAY 06	4.2-1	11 MAY 06		
1.7-2	11 MAY 06			ENR 2	
		PART 2 – ENROUTE		2.1-1	11 MAY 06
GEN 2		(ENR)		2.1-2	11 MAY 06
2.1-1	11 MAY 06			2.1-3	11 MAY 06
2.1-2	11 MAY 06	ENR 0		2.1-4	11 MAY 06
2.2-1	11 MAY 06	0.6-1	11 MAY 06	2.1-5	11 MAY 06
2.2-2	11 MAY 06	0.6-2	11 MAY 06	2.1-6	11 MAY 06
2.2-3	11 MAY 06	0.6-3	11 MAY 06		
2.2-4	11 MAY 06			ENR 3	
2.2-5	11 MAY 06	ENR 1		3.1-1	11 MAY 06
2.2-6	11 MAY 06	1.1-1	11 MAY 06	3.2-1	11 MAY 06
2.3-1	11 MAY 06	1.1-2	11 MAY 06	3.3-1	11 MAY 06

3.3-2	11 MAY 06	2.1-3	11 MAY 06	2.1-54	11 MAY 06
3.3-3	11 MAY 06	2.1-4	11 MAY 06	2.1-55	11 MAY 06
3.3-4	11 MAY 06	2.1-5	11 MAY 06	2.1-56	11 MAY 06
3.3-5	11 MAY 06	2.1-6	11 MAY 06	2.1-57	11 MAY 06
3.4-1	11 MAY 06	2.1-7	11 MAY 06	2.1-58	11 MAY 06
3.5-1	11 MAY 06	2.1-8	11 MAY 06	2.1-59	11 MAY 06
3.5-2	11 MAY 06	2.1-9	11 MAY 06	2.1-60	11 MAY 06
3.5-3	11 MAY 06	2.1-10	11 MAY 06	2.1-61	11 MAY 06
3.5-4	11 MAY 06	2.1-11	11 MAY 06	2.1-62	11 MAY 06
3.5-5	11 MAY 06	2.1-12	11 MAY 06	2.1-63	11 MAY 06
3.5-6	11 MAY 06	2.1-13	11 MAY 06	2.1-64	11 MAY 06
3.6-1	11 MAY 06	2.1-14	11 MAY 06	2.1-65	11 MAY 06
		2.1-15	11 MAY 06	2.1-66	11 MAY 06
ENR 4		2.1-16	11 MAY 06	2.1-67	11 MAY 06
4.1-1	11 MAY 06	2.1-17	11 MAY 06	2.1-68	11 MAY 06
4.2-1	11 MAY 06	2.1-18	11 MAY 06	2.1-69	11 MAY 06
4.3-1	11 MAY 06	2.1-19	11 MAY 06	2.1-70	11 MAY 06
4.4-1	11 MAY 06	2.1-20	11 MAY 06	2.1-71	11 MAY 06
		2.1-21	11 MAY 06	2.1-72	11 MAY 06
ENR 5		2.1-22	11 MAY 06	2.1-73	11 MAY 06
5.1-1	11 MAY 06	2.1-23	11 MAY 06	2.1-74	11 MAY 06
5.2-1	11 MAY 06	2.1-24	11 MAY 06	2.1-75	11 MAY 06
5.3-1	11 MAY 06	2.1-25	11 MAY 06	2.1-76	11 MAY 06
5.4-1	11 MAY 06	2.1-26	11 MAY 06	2.1-77	11 MAY 06
5.5-1	11 MAY 06	2.1-27	11 MAY 06	2.1-78	11 MAY 06
5.6-1	11 MAY 06	2.1-28	11 MAY 06	2.1-79	11 MAY 06
		2.1-29	11 MAY 06	2.1-80	11 MAY 06
ENR 6		2.1-30	11 MAY 06	2.1-81	11 MAY 06
6.1-1	11 MAY 06	2.1-31	11 MAY 06	2.1-82	11 MAY 06
		2.1-32	11 MAY 06	2.1-83	11 MAY 06
PART3 AERODROMES		2.1-33	11 MAY 06	2.1-84	11 MAY 06
(AD)		2.1-34	11 MAY 06	2.1-85	11 MAY 06
		2.1-35	11 MAY 06	2.1-86	11 MAY 06
AD 0		2.1-36	11 MAY 06	2.1-87	11 MAY 06
0.6-1	11 MAY 06	2.1-37	11 MAY 06	2.1-88	11 MAY 06
0.6-2	11 MAY 06	2.1-38	11 MAY 06	2.1-89	11 MAY 06
0.6-3	11 MAY 06	2.1-39	11 MAY 06	2.1-90	11 MAY 06
0.6-4	11 MAY 06	2.1-40	11 MAY 06	2.1-91	11 MAY 06
0.6-5	11 MAY 06	2.1-41	11 MAY 06	2.1-92	11 MAY 06
0.6-6	11 MAY 06	2.1-42	11 MAY 06	2.1-93	11 MAY 06
0.6-7	11 MAY 06	2.1-43	11 MAY 06	2.1-94	11 MAY 06
0.6-8	11 MAY 06	2.1-44	11 MAY 06	2.1-95	11 MAY 06
0.6-9	11 MAY 06	2.1-45	11 MAY 06	2.1-96	11 MAY 06
		2.1-46	11 MAY 06	2.1-97	11 MAY 06
AD 1		2.1-47	11 MAY 06	2.1-98	11 MAY 06
1.1-1	11 MAY 06	2.1-48	11 MAY 06	2.1-99	11 MAY 06
1.2-1	11 MAY 06	2.1-49	11 MAY 06	2.1-100	11 MAY 06
		2.1-50	11 MAY 06	2.1-101	11 MAY 06
AD 2		2.1-51	11 MAY 06	2.1-102	11 MAY 06
2.1-1	11 MAY 06	2.1-52	11 MAY 06	2.1-103	11 MAY 06
2.1-2	11 MAY 06	2.1-53	11 MAY 06	2.1-104	11 MAY 06

2.1-105	11 MAY 06
2.1-106	11 MAY 06
2.1-107	11 MAY 06
2.1-108	11 MAY 06
2.1-109	11 MAY 06
2.1-110	11 MAY 06
2.1-111	11 MAY 06
2.1-112	11 MAY 06
2.1-113	11 MAY 06

AD 3

3.1-1	11 MAY 06
3.1-2	11 MAY 06
3.1-3	11 MAY 06
3.1-4	11 MAY 06
3.1-5	11 MAY 06
3.1-6	11 MAY 06

GEN 0.5 LIST OF HAND AMENDMENTS TO THE AIP

Section or page affected	Amendment Text	Introduced by AIP AMDT Serial No.

GEN 0.6 TABLE OF CONTENTS TO PART 1**GEN 1 NATIONAL REGULATIONS AND REQUIREMENTS**

	Page
GEN 1.1 Designated authorities	GEN 1.1-1
GEN 1.2 Entry, transit and departure of aircraft	GEN 1.2-1
GEN 1.3 Entry, transit and departure of passenger and crew	GEN 1.3-1
GEN 1.4 Entry, transit and departure of cargo	GEN 1.4-1
GEN 1.5 Aircraft instruments, equipment and flight documents	GEN 1.5-1
GEN 1.6 Summary of national regulation and international agreements/conventions	GEN 1.6-1
GEN 1.7 Differences from ICAO Standards, Recommended Practices and Procedures	GEN 1.7-1

GEN 2 TABLES AND CODES

GEN 2.1 Measuring system, aircraft marking, public holidays	GEN 2.1-1
GEN 2.1.1 Units of measurement	GEN 2.1-1
GEN 2.1.2 Time system	GEN 2.1-1
GEN 2.1.3 Geodetic reference datum	GEN 2.1-1
GEN 2.1.4 Aircraft nationality and registration marks	GEN 2.1-1
GEN 2.1.5 Public holidays	GEN 2.1-2
GEN 2.2 Abbreviations used in AIS publications	GEN 2.2-1
GEN 2.3 Chart symbols	GEN 2.3-1
GEN 2.4 Location indicators	GEN 2.4-1
GEN 2.4.1 Location indicators Encode	
GEN 2.4.2 Location indicators Decode	GEN 2.4-2
GEN 2.5 List of radio navigation aids	GEN 2.5-1
GEN 2.6 Conversion tables	GEN 2.6-1
GEN 2.7 Sunrise/sunset tables	GEN 2.7-1

GEN 3 SERVICES

GEN 3.1 Aeronautical Information Services	GEN 3.1-1
GEN 3.1.1 Responsible service	GEN 3.1-1
GEN 3.1.2 Area of responsibility	GEN 3.1-1
GEN 3.1.3 Aeronautical publications	GEN 3.1-1
GEN 3.1.4 AIRAC System	GEN 3.1-3
GEN 3.1.5 Pre-flight information service at aerodrome	GEN 3.1-4
GEN 3.2 Aeronautical charts	GEN 3.2-1
GEN 3.2.1 Responsible services	GEN 3.2-1
GEN 3.2.2 Maintenance of charts	GEN 3.2-1
GEN 3.2.3 Purchase arrangements	GEN 3.2-1
GEN 3.2.4 Aeronautical chart series available	GEN 3.2-1
GEN 3.2.5 List of aeronautical charts available	GEN 3.2-3
GEN 3.2.6 Index to the World Aeronautical Chart (WAC) - ICAO 1:1 000 000	GEN 3.2-3
GEN 3.2.7 Topographical charts	GEN 3.2-3

	Page
GEN 3.3 Air traffic services	GEN 3.3-1
GEN 3.3.1 Responsible service	GEN 3.3-1
GEN 3.3.2 Area of responsibility	GEN 3.3-1
GEN 3.3.3 Types of services	GEN 3.3-1
GEN 3.3.4 Co-ordination between the operator and ATS	GEN 3.3-3
GEN 3.3.5 Minimum flight altitude	GEN 3.3-3
GEN 3.3.6 ATS units address list	GEN 3.3-3
GEN 3.4 Communication services	GEN 3.4-1
GEN 3.4.1 Responsible service	GEN 3.4-1
GEN 3.4.2 Area of responsibility	GEN 3.4-1
GEN 3.4.3 Types of service	GEN 3.4-1
Aeronautical fixed services: Telegraph	GEN 3.4-3
Aeronautical fixed services: Telephone	GEN 3.4-4
GEN 3.5 Meteorological services	GEN 3.5-1
GEN 3.5.1 Responsible service	GEN 3.5-1
GEN 3.5.2 Area of responsibility	GEN 3.5-1
GEN 3.5.3 Meteorological observations and reports	GEN 3.5-1
GEN 3.5.4 Types of services	GEN 3.5-1
GEN 3.5.5 Notification required from operators	GEN 3.5-1
GEN 3.5.6 Aircraft reports	GEN 3.5-1
GEN 3.5.7 VOLMET service	GEN 3.5-2
GEN 3.5.8 SIGMET service	GEN 3.5-2
GEN 3.5.9 Other automated meteorological services	GEN 3.5-2
GEN 3.6 Search and rescue	GEN 3.6-1
GEN 3.6.1 Responsible service	GEN 3.6-1
GEN 3.6.2 Area of responsibility	GEN 3.6-1
GEN 3.6.3 Types of service	GEN 3.6-1
GEN 3.6.4 SAR agreements	GEN 3.6-1
GEN 3.6.5 Search and rescue facilities	GEN 3.6-2
GEN 3.6.6 Procedures and/or signals employed by rescue aircraft	GEN 3.6-3

GEN 4 FEES AND CHARGES

GEN 4.1 Aerodrome charges	GEN 4.1-1
GEN 4.1.1 General	GEN 4.1-1
GEN 4.1.2 Landing charges	GEN 4.1-1
GEN 4.1.3 Fees for additional ground handling	GEN 4.1-1
GEN 4.1.4 Miscellaneous charges	GEN 4.1-2
GEN 4.1.5 Exemptions and reductions	GEN 4.1-2
GEN 4.1.6 Payment of fees and charges	GEN 4.1-2
GEN4.2 Air navigation charges	GEN 4.2-1

GEN 1 NATIONAL REGULATIONS AND REQUIREMENTS

GEN 1.1 DESIGNATED AUTHORITIES

1.1.1 INTRODUCTION

1.1.1.1 The requirement for entry, transit and departure of aircraft engaged in international flights and the procedures for clearance of these aircraft at designated airports in Iraq are given for the information and guidance of operators conducting international flights.

1.1.1.2 The Iraq Civil Aviation Authority (ICAA) is the agency responsible for Iraq's obligations under the provisions of Annex 9 (Facilitation) of the Chicago Convention. The ICAA is responsible for coordinating with other Iraq agencies for the development and implementation of policy and coordination of ICAO matters.

1.1.1.3 The addresses of the designated authorities concerned with facilitation of international air navigation are as follows:

a. **Iraq Civil Aviation Authority:**

Director General
Iraq Civil Aviation Authority
Baghdad International Airport
Baghdad – Republic of IRAQ

AFTN address: ORBIYAYX or ORBIZGZX

Telephone, Telex and P.O. Box will be advised by NOTAM once available

b. **Meteorology:**

The Iraqi Meteorological Organization
Meteorological Office Section
Baghdad International Airport
Baghdad - Republic of IRAQ

Telephone, Telex and P.O. Box will be advised by NOTAM once available

c. **Agricultural and Quarantine:**

Ministry of Agriculture
ANDULUS Square
Near ALSADER HOTEL
Baghdad – Republic of IRAQ

Telephone, Telex and P.O. Box will be advised by NOTAM once available

Note: Addresses, phone numbers, and contact information of related authorities within AIP are yet to be determined. All aviation related enquiries should be addressed to ICAA staff at Baghdad International Airport until further notice.

GEN 1.2 ENTRY, TRANSIT AND DEPARTURE OF AIRCRAFT

1.2.1 General

1.2.1.1 On behalf of the Republic of Iraq the Combined Forces Air Component Commander (CFACC) is the Airspace Control Authority (ACA) for Iraq and the Baghdad FIR, effective from 19 March 2003 until further notice. The procedures for flight operations detailed here are mandatory for all aircraft operators authorized to fly in the Baghdad FIR.

1.2.1.2 The ICAA has responsibility for all operational and safety matters relating to civil aviation into, within and from Iraqi territory. International flights into, from or over Iraqi territory shall be subject to the current Iraqi regulations relating to civil aviation. These regulations correspond in all essentials to the Standards and Recommended Practices (SARP) contained in Annex 9 to the Convention on International Civil Aviation. Under no circumstances should an aircraft attempt to overfly or enter Iraq without first having obtained the necessary permission.

1.2.1.3 The approving authority for flights intending to overfly, land, or depart from an aerodrome within the Baghdad FIR, is the Iraq Civil Aviation Authority (ICAA). All aircraft require ICAA approval as well as deconfliction by the ACA to land, depart, and overfly Iraq. To accomplish this, all carriers will either contact the ICAA directly or coordinate with the RAMCC for contact information. The carrier will then provide any documentation required by the ICAA to obtain approval. All company information shall be submitted to the ICAA at least seven days prior to the commencement of the first intended flight, or at least 15 days when such a request is submitted through diplomatic channels. Once carriers are approved by the ICAA, RAMCC is responsible for slotting overflights as well as takeoff and landings at ICAA approved aerodromes. Requests for civil flights in the Baghdad FIR shall be submitted to RAMCC giving details of the proposed flight as described in the Overflight or Landing Slot Request Form. RAMCC operating hours are 0300 - 2100 UTC daily. Slot request forms and after hours contact information may be found on the RAMCC website at <http://ramcc.dtic.mil>. Changes in slot times will be coordinated through the RAMCC. Once requests are approved, RAMCC will assign a Mode 3/A transponder code and slot times to aircraft operators and/or aircraft dispatchers. For slot times, RAMCC Iraq can be contacted via:

RAMCC Iraq Mobile Phone:	+974 589 2695
RAMCC Iraq Landing Slots Commercial Phone:	+974 (QATAR) 458 9555
DSN Phone:	436 5184 or 5187
NIPRNET (non-secure e-mail):	ramcc.iraq@auab.aorcentaf.af.mil
RAMCC Iraq Overflights Commercial Phone:	+974 (QATAR) 458 9555
DSN Phone:	436 2671
NIPRNET (non-secure e-mail):	ramcc.overfly.iraq@auab.aorcentaf.af.mil
RAMCC Iraq Commercial Fax:	+974 (QATAR) 432 7382
RAMCC Web address:	http://ramcc.dtic.mil

1.2.1.4 Should discrepancies arise as to whether or not an operator is approved to operate in the Baghdad FIR the issue is to be resolved directly between the operator and ICAA. The contact numbers for ICAA representatives are:

ICAA Aviation Adviser Work Phone
Mobile Phone

0 + 1 + 703 343 7906
0 + 1 + 914 360 7755

Risks to Flight and Compliance with These Procedures

1.2.1.5 All operators are advised that non-military operations could be at significant risk because of terrorist and criminal activities and ongoing military operations countering those activities in Iraq. There are continuing reports of indiscriminate small arms and missile attacks on aircraft operating in Iraq, primarily at low altitudes. Therefore, operators that undertake flights within the Baghdad FIR shall do so at their own risk. Compliance with AIP procedures is mandatory; safety of aircraft operating in the Baghdad FIR requires strict adherence to AIP procedures. Operators should review NOTAMs, using their appropriate system and methods, regularly for any changes that may affect the information contained within this document.

1.2.1.6 All aircraft operators shall comply strictly with the provisions of the permission granted for their aircraft and shall adhere to the international designated air routes. Failure to comply with the procedures in this AIP may result in interception by armed coalition fighter aircraft. Aircraft operators must be familiar with, and follow, international intercept procedures contained in Annex 2, Rules of the Air, to the Chicago Convention, paragraph 3.8 and Appendix 2, Sections 2 and 3. Pilots are to continuously monitor the VHF emergency FREQ (121.5 MHz) and operate their transponder at all times during flight, ensuring that the transponder is set on the correct code assigned by RAMCC. ACA reserves the right to deny aircraft with inoperable transponders access to the Baghdad FIR. Aircraft operating within the Baghdad FIR may also be instructed to deviate from their flight planned route due to temporary flight restrictions imposed by ACA.

1.2.1.7 GENERAL CIVIL SLOT PROCEDURES

1.2.1.7.1 Overflights

1.2.1.7.1.1 All Iraqi airports are closed to civil overflight aircraft except in an emergency situation. Only civil operators and state flights approved by the ICAA are authorized to overfly Iraqi airspace. Coalition military flights are authorized by the CFACC via the Air Tasking Order. A RAMCC assigned Mode 3/A transponder code indicates ICAA and RAMCC approval. An ATO assigned Mode 3/A transponder code indicates CFACC approval.

1.2.1.7.1.2 The overflight request form can be found on the RAMCC website at <http://ramcc.dtic.mil/>. All companies must have ICAA approval to operate within Iraqi airspace prior to submitting an overflight request (See Iraq AIP 1.2.2-1.2.5.) All overflight slot requests must be submitted by 1900Z the day prior to the planned flight. Additionally, carriers operating under the scheduled flight procedures outlined in Iraq AIP 1.2.2, will submit summer/winter schedules no later than 7 days prior to the first month of scheduled operation. In all cases, requests should not be submitted any earlier than 30 days prior to the planned overflight.

1.2.1.7.1.3 Overflights of Baghdad FIR must be conducted above FL200; except for flights departing from adjacent countries whose climb performance will not permit operation above FL200 prior to entering the Baghdad FIR. RAMCC will assign a Mode 3/A transponder code valid for the 24 hour period from 0000 - 2359 UTC of the approved date of entry to the Baghdad FIR boundary. If an approved overflight will deviate from the assigned UTC date of

entry, the operator must contact RAMCC as soon as possible by e-mail, phone, or fax with the new FIR entry time/date. At that time, RAMCC will either advise that the original Mode 3/A transponder code remains valid or assign a new code. If an approved overflight is cancelled or will not need to enter the Baghdad FIR, operators will notify RAMCC of the overflight cancellation as soon as possible. To make changes after hours contact information may be found on the RAMCC website at <http://ramcc.dtic.mil>.

1.2.1.7.1.4 Changes to overflight slot time requests. To make changes before a slot time has been issued by RAMCC, coordinate all changes by submitting an updated request form. To make changes after a slot time has been issued by RAMCC, coordinate significant changes by submitting an updated request form and contacting RAMCC by any means available. A significant change is defined as any changes to the following:

1. UTC date of flight
2. Aircraft type
3. Call Sign
4. Aircraft Registration
5. Departure and/or Arrival locations

1.2.1.7.2 Landings and Departures

1.2.1.7.2.1 Civil aircraft must receive a RAMCC approved slot time and Mode 3/A transponder code to arrive and depart from each Iraq airfield. Slot times are used to deconflict ramp space at BIAP (no PPR system) as well as arrivals and departures at all Iraq airfields. Operators must plan to arrive and depart on their RAMCC approved slot times. Failure to meet approved slot times may result in holding and/or delays. Landing slot requests must be submitted no later than 0800 UTC the day prior to the flight. Late requests will not be accepted. The Landing Slot Request Form can be found on the RAMCC website at <http://ramcc.dtic.mil>. Upon approval, RAMCC will assign a Mode 3/A transponder code valid only for the 24 hour period from 0000 - 2359 UTC of the approved date of entry to the Baghdad FIR boundary.

ICAA guidelines currently limit flight operations in Iraq to the following categories:

1. Non-military humanitarian assistance flights,
2. Flights contracted by the military (e.g., DHL and FedEx),
3. International Committee for the Red Cross (ICRC),
4. Humanitarian passenger flights (e.g., UNHAS, Air Serv, etc),
5. Medical evacuation flights,
6. ICAA charter flights (i.e., Royal Jordanian), and
7. Iraq Reconstruction Flights.

Operators requesting landing slots in Iraq *must* specify a category on the request form. ICAA will not approve requests submitted without specifying a category.

1.2.1.7.2.2 Changes to landing slot time requests. To make changes before a slot time has been issued by RAMCC, coordinate all changes by submitting an updated request form. To make changes after a slot time has been issued by RAMCC, coordinate significant changes by submitting an updated request form and contacting RAMCC by any means available. A significant change is defined as any changes to the following:

1. UTC date of flight
2. Aircraft type
3. Call Sign
4. Aircraft Registration
5. Departure and/or Arrival locations

1.2.1.7.2.3 The RAMCC approved slot time and Mode 3/A transponder code is authorization to enter the Baghdad FIR and fly to the requested airport. Assignment of a slot time does not encompass any aircraft servicing, ground handling, or other aircrew requirements, nor does it imply air traffic control separation, weather conditions or threat assessment. All flights must have sufficient fuel and maintenance support to meet their assigned arrival and departure times. Aircrews should be prepared for minimum ground times. Aircrews need to consider adequate fuel for potential ground or air delays, due to unforeseen events. An earlier takeoff than the assigned slot time is authorized if approved by air traffic control. Any schedule changes must be coordinated with the destination airport manager to ensure servicing and security concerns are addressed.

1.2.1.8 PPR (Prior Permission Required) Procedures

1.2.1.8.1 In general, PPRs are required for transient military and civil aircraft including those on ATO's operating at designated airfields. Aircraft that land without an approved PPR may be turned away or met by security forces.

1.2.1.8.2 PPR times must be met +/- 30 minutes from the approved time. Any changes to an arrival or departure time at an airfield that requires a PPR must be coordinated with the Senior Airfield Authority. Operators that do not coordinate changes to their PPR times may face delays and/or be prohibited from downloading their cargo or passengers.

1.2.1.8.3. RAMCC issues slot times for civil aircraft. An approved RAMCC slot time does not constitute an approved PPR. At PPR designated airfields, operators must contact the Senior Airfield Authority and receive a PPR before requesting a slot time from RAMCC. Requirements for PPR are defined with the relevant airfield entry in PART 3 AERODROMES (AD). Carriers are also required to check current NOTAMS for changes in PPR requirements. Civil aircraft are to conform to the requirements of section 1.2.1.8.

1.2.1.8.4 RAMCC does not issue slot times for military aircraft. PPR's issued will serve as slot times. Arrivals/Departures outside the valid PPR window will need to contact the Senior Airfield Authority listed below or in AD 2.3 for the specific aerodrome. PPR's issued with less than 6 hours notification, will not be guaranteed priority handling and may be delayed. The Senior Airfield Authority is the arbiter for final approval of PPR's.

1.2.1.8.5 Civilian aircraft flying into or departing from Iraqi territory shall:

1.2.1.8.5.1 Only be permitted to make their first landing and final departure from an approved International Airport in order to complete required Customs and Immigration clearance. The

current ICAA approved International Airports are Baghdad International, Erbil International, Sulaymaniyah International, and Basrah International. Note: Cargo flights and military coalition passengers may be exempt from “international aerodrome” requirements subject to ICAA approval.

1.2.1.8.5.2 Restrict landings to Baghdad International or Basrah International Airports between 0300–1500 UTC during the Summer period and 0400–1600 UTC during the Winter period, if ferrying passengers. Note this restriction applies to ground services availability, such as Customs and Immigration, and does not negate nor vary the restrictions specified in ENR 1.1.4.5.

1.2.1.8.5.3 Conduct flights to aerodromes specified in ENR 3.5, subject to further approval by ICAA, if an approved humanitarian aid or United Nations flight.

1.2.1.8.5.4 Submit a slot time change request to RAMCC if a significant change occurs as defined in section 1.2.1.7.1.4 for overflights and 1.2.1.7.2.2 for landings.

1.2.1.8.5.5 Fly mandatory routings and altitudes as described in sections ENR 1.8 and ENR 3.5. If authorization has been obtained to land at airfields where no mandatory routing has been specified, aircraft are to comply with the mandatory routing of the nearest airport (where the routing is provided) and then indicate the airport of intended landing. In such cases, expect air traffic control to amend routings as required.

1.2.1.9 Fuel and other services may not be available at most airports. If fuel, ground handling or other services are required it must be coordinated through the prime contractor. The military accepts no responsibility to provide aid in cargo handling in any manner unless it is coordinated prior to arrival and specifically agreed upon. To obtain fuel from the US government, you must have a pre-existing contract. Current rates and payment methods can be found at the following web addresses:

(ORBI) http://www.skylink-usa.net/airport_operations/baghdad_international_airport/airfield_information.html

(ORMM) http://www.skylink-usa.net/airport_operations/basrah_international_airport/aircraft_fueling_fees.html

1.2.1.10 All operators are to consult PART 3 AERODROMES (AD), for the specific airfield, and NOTAMS for updated information and contact numbers.

Contact information:

AL ASAD (ORAA)

Email: alasadppr@acemnf-wiraq.usmc.mil

DSN # for Airfield Manager is 318-341-2700

ALI (ORTL)

Email: 407AEG/EOSS/AMOP2@tlab.aorcentaf.af.mil

DSN# for Airfield Manager is 318-459-0058 or 318-459-0482

AL SAHRA (ORSH)

Email: alsahra.operations@us.army.mil

DSN # for Airfield Manager is 302-242-1120

AL TAQADDUM (ORAT)

Email: tqfc@acemnf-wiraq.usmc.mil

DSN # for Airfield Manager is 318-342-2344 or 318-342-2341

BAGHDAD Military (ORBI)

Email: 447AEG/OSAA@bdab.aorcentaf.af.mil

DSN# for Airfield Manager is 318-446-2900

BALAD (ORBD)

Email: 332EOSS.OSAM@blab.centaf.af.mil

DSN # for Airfield Manager is 318-443-6065/6675

BASRAH (ORMM)

Email: basrahairops@hotmail.com

Contact # for Airfield Manager is 011-965-911-4553

ERBIL (ORER)

Email: arbilgc@yahoo.com

Phone# 003248459767 or 008821667700111

KIRKUK (ORKK)

Email: 506EOSS/OSAM@krab.centaf.af.mil

DSN # for Airfield Manager is 318-444-2456/2457

MOSUL (ORBM)

Email: orbmppr@yahoo.com

DSN # for Airfield Manager 302-587-7409

QAYYARAH WEST (ORQW)

Email: andrew.fairfax@us.army.mil

DNVT# for Airfield Manager is 302-530-0718 or 302-530-0522

SULAYMANIYAH (ORSU)

E-mail: tahirjul55@yahoo.com

Phone#+96407701530273 or 96407701505186

TALL AFAR (ORTF)

Email: john.parker1@usarmy.smil.mil

DNVT# for Airfield Manager is 302-539-5406

1.2.1.11 HA/NGO flights are allowed to land/depart from the following airports with proper approval authority:

1.2.1.11.1 Baghdad International Airport - ORBI

1.2.1.11.2 Basrah International Airport - ORMM (PPR from Basrah Air Operations prior to contacting RAMCC for a slot time. See ORMM AD 2.1 Airport Information for contact number).

1.2.1.11.3 Al Asaad - ORAA

1.2.1.11.4 Al Kut - ORUB

1.2.1.11.5 Ali Base - ORTL

1.2.1.11.6 Al Sahra - ORSH

1.2.1.11.7 Al Taqaddum - ORAT

1.2.1.11.8 Balad SE airport - ORBD

1.2.1.11.9 Erbil International Airport - ORER

1.2.1.11.10 Kirkuk - ORKK

1.2.1.11.11 Mosul - ORBM

1.2.1.11.12 Qayyarah West - ORQW

1.2.1.11.13 Sulaymaniyah - ORSU

1.2.1.11.14 Tall Afar - ORTF

1.2.1.12 Aircraft operations at other airports may be permitted with ICAA approval and RAMCC coordination. If approval is granted, operators shall comply with the mandatory routings and procedures contained in ENR 3. Changes to an airport's status will be disseminated by NOTAM, as will the notification of any additional airports cleared by ACA for slot time operations.

1.2.2 Scheduled flights

1.2.2.1 Regular international scheduled flights, operated by foreign airlines, into or transiting the Baghdad FIR, must comply with the following:

1.2.2.1.1 The State of the airline must be a party to the International Air Services Transit Agreement and/or the International Air Transport Agreement to which both the State of the airline and Iraq are contracting parties.

1.2.2.1.2 The airline must be eligible to make the flights under the provisions of a bilateral or multilateral agreement, provided that the State of the airline and Iraq are contracting parties, and must have a permit to operate into or in transit across Iraq. Applications for such permits shall be submitted to ICAA until further notice.

1.2.2.1.3 Applications for permission for aircraft engaged in scheduled International Air Services requesting to overfly Iraqi territory or land for non-traffic purposes shall be submitted with full details to ICAA at least seven days prior to the commencement of the flight.

1.2.2.1.4 Applications for timetable approval of scheduled International Air Services to operate into Iraq for commercial purposes, shall be submitted at least two months prior to the

proposed date of the commencement of operation. For additional and non-scheduled flights, see GEN 1.2.3.

1.2.2.2 Documentary Requirements for Clearance of Aircraft. It is necessary that the under mentioned aircraft documents be submitted by airline operators for clearance on entry and departure of their aircraft to and from Iraq. All documents listed below must follow the ICAO standard format as set in the relevant appendices to ICAO Annex 9, completed in English and completed in legible handwriting. Visas are not required to accompany these documents.

1.2.2.3 Aircraft documents required (arrival/departure)

Required By	General Declaration	Passenger Manifest	Cargo Manifest
Airport Authority	1	1	1
Customs	1	1	1
Immigration	1	1	1
Public Health	1	1	1

1.2.3 Non-scheduled flights

1.2.3.1 Aircraft registered in States that are parties to Chicago International Civil Aviation Convention (1944) and not engaged in scheduled International Air Services are permitted to overfly Iraqi territory or make stops for non-traffic purposes, provided that applications for clearance are forwarded at least 48 hours prior to the commencement of the flight, incorporating the following details:

1.2.3.1.1 Name and address of aircraft operator;

1.2.3.1.2 Type of aircraft and registration mark;

1.2.3.1.3 Date of overflying or date and estimated time of arrival at and departure from Iraqi territory;

1.2.3.1.4 Route of flight; and

1.2.3.1.5 Purpose of flight and nature of freight on-board.

1.2.3.2 The ICAA will not consider any request without the above information.

1.2.3.3 Aircraft registered in other foreign countries require special permission to exercise the above rights after submitting applications to ICAA at least 72 hours prior to the commencement of flights incorporating the details mentioned in 1.2.3.1.

1.2.3.4 Applications for permission to transport passengers and cargo to and from Iraq for commercial purposes shall be submitted directly to ICAA seven days before the commencement of the first intended flight, or at least 15 days when such a request is submitted through diplomatic channels, incorporating the following:

1.2.3.4.1 Cargo flights:

1.2.3.4.2 Name and address of the carrier and operator;

1.2.3.4.3 Type of aircraft and registration marks;

1.2.3.4.4 Name and address of the consigner and consignee;

1.2.3.4.5 Type and amount of cargo, with specific indication of any material subject to special restrictions or authorization such as explosives, arms, and munitions, nuclear objects and radioactive materials and any other objects related thereto, poisonous gases, germs and dangerous objects and any other objects the carriage of which is prohibited by the competent authority;

1.2.3.4.6 Name and address of the designated agent in Iraq through whom landing and air navigation facilities charges are to be paid in respect of airlines which do not have offices or accredited agents in Iraq.

1.2.3.4.7 Place of embarkation or disembarkation aboard, with date and estimated time of arrival at and departure from Iraqi aerodromes.

1.2.3.4.8 Passenger flights:

1.2.3.4.8.1 As mentioned in 1.2.3.4 sub-sub-paragraphs 2, 3, 6 and 7 above; and

1.2.3.4.8.2 Purpose of the flight.

1.2.3.5 Application for permission for aircraft equipped with air photographic apparatus to fly over or land within Iraqi territory should be submitted with full details at least 10 days before the intended day of operation.

1.2.3.6 Application for permission for foreign military aircraft to operate over or into Iraqi territory should be submitted through diplomatic channels at least 15 days prior to the commencement of flight. The application must include the items mentioned in paragraph 1.2.3.1.1.

1.2.3.7 Any delay in non-scheduled flights must be notified to ICAA in order that the permission originally obtained is not invalidated.

1.2.3.8 **Documentary Requirements for Clearance of Aircraft.** Those requirements defined at GEN 1.2.2.2 and 1.2.2.3 apply to Non-scheduled flights.

1.2.4 Private flights

1.2.4.1 Advance Notification of Arrival or Entry

1.2.4.1.1 Prior permission shall be obtained for private aircraft overflying or landing at Iraqi aerodromes and must be submitted to ICAA at least 48 hours prior to the departure of the aircraft, or far enough in advance to ensure that the request can be processed and a reply received before departure. The application must contain information as stated in paragraph 1.2.3.1.

1.2.4.1.2 Private flights must submit a flight plan sufficiently early to ensure that the information will be received at least two hours in advance of the aircraft entering the Baghdad FIR. If landing in Iraq, the landing must be carried out at a designated international aerodrome.

1.2.4.1.3 Any delay in Private flights must be notified to ICAA in order that the permission originally obtained is not invalidated.

1.2.4.2 **Documentary Requirements for Clearance of Aircraft.** Those requirements defined at GEN 1.2.2.2 and 1.2.2.3 apply to Private flights.

1.2.5 Public health measures applied to all aircraft

1.2.5.1 Evidence of protection against cholera, yellow fever or smallpox is required from crew and passengers coming from infected countries.

1.2.5.2 Airline operators, or the pilot for Non-scheduled and Private flights, must ascertain whether the point of departure of any flight to Iraq is contained in an area that has been declared an epidemic area for the purpose of the Iraqi Health Regulation and Orders. The airline or pilot, as applicable, should similarly acquaint themselves as to the status of any area through which the aircraft may transit prior to entering Iraq.

1.2.5.3 No health formalities are required on departure.

GEN 1.3 ENTRY, TRANSIT AND DEPARTURE OF PASSENGERS AND CREW

1.3.1 Customs requirements

1.3.1.1 Baggage or articles belonging to disembarking passengers and crew are immediately released except for those selected by the customs authorities for inspection. Such baggage will be cleared on the basis of oral declaration.

1.3.1.2 For customs inspection, presentation of baggage is required from passengers departing Iraq.

1.3.2 Immigration requirements

1.3.2.1 All foreign passengers must be in possession of a valid passport.

1.3.2.2 All foreign passengers entering Iraq must possess an entry visa, except the nationals of Arab countries.

1.3.2.3 All passengers remaining in Iraq for longer than 30 days and embarking to any point outside Iraq must be in possession of an exit visa.

1.3.2.4 All foreign transit passengers embarking in Iraq for 30 days or less, other than those proceeding on the same flight, must be in possession of a transit visa. No foreign passenger will be permitted to leave the confines of the airport without such a visa.

1.3.2.5 Entry visa is valid for three months from the date of issue, with the understanding that the duration of stay in Iraq is for a maximum of 30 days only.

1.3.2.6 A crew member traveling by service route must be in possession of a valid passport and obtain the necessary authorization.

1.3.3 Public health requirements

1.3.3.1 Disembarking passengers are not required to present vaccination certificates unless arriving from an area infected with cholera, yellow fever or smallpox.

1.3.3.2 For crew and passengers intending to enter Iraq or in transit, see GEN 1.2.5.

GEN 1.4 ENTRY, TRANSIT AND DEPARTURE OF CARGO

1.4.1 Customs requirements concerning cargo and other articles

1.4.1.1 Application for permission to transport cargo to and from Iraq for commercial purposes shall be submitted directly to ICAA at least 7 days before commencement of the first intended flight, or at least 15 days when such request is submitted through diplomatic channels. Requests shall incorporate the following:

1.4.1.1.1 Name and address of the carrier and operator;

1.4.1.1.2 Type of aircraft and registration marks;

1.4.1.1.3 Name and address of consigner and consignee;

1.4.1.1.4 Type and amount of cargo, with specific indication of any material subject to special restrictions or authorization, such as explosives, arms and munitions, nuclear objects and radioactive materials, poisonous gases, germs and dangerous goods;

1.4.1.1.5 Name and address of the designated agent in Iraq through which landing and air navigation facilities charges are to be paid in respect of airlines which do not have offices or accredited agents in Iraq;

1.4.1.1.6 Place of embarkation or disembarkation abroad with date and estimated time of arrival at, and departure from, Iraqi aerodromes.

1.4.2 Agricultural quarantine requirements

1.4.2.1 Agricultural quarantine requirements are comprised of the following:

1.4.2.1.1 Passenger Inspection

1.4.2.1.1.1 Certain plants and plant materials are prohibited by law from entering Iraq such as:

1.4.2.1.1.1.1 Fruits: Mangoes, citrus, etc.

1.4.2.1.1.1.2 Plants: Palm, all green plants, plant cuttings, etc.

1.4.2.1.1.1.3 Others: Culture of bacteria and fungi.

1.4.2.1.1.1.4 Seeds: A permit must be obtained in advance from the Ministry of Agriculture in Iraq. A photo-sanitary certificate from the country of origin is also required. Seeds must pass laboratory inspection before they are released.

1.4.2.1.2 Imports

1.4.2.1.2.1 All regulations mentioned above must be observed. All airlines or representatives must present the required documentations and prepare the shipment for inspection.

1.4.2.1.3 Exports

1.4.2.1.3.1 The shipment must be examined by an official from the Agricultural Quarantine Administration. A certificate will be granted if the shipment passes inspection. The certificate must accompany the shipment. Detailed information and the required forms are available from the Ministry of Agriculture at the address below.

MINISTRY OF AGRICULTURE
ANDULUS Square
Near ALSADER HOTEL
Baghdad – Republic of IRAQ

Fax and telephone numbers will be advised by NOTAM when available.

GEN 1.5 AIRCRAFT INSTRUMENTS, EQUIPMENT AND FLIGHT DOCUMENTS

1.5.1 General: Commercial air transport aircraft operating in Iraq must adhere to the provisions of ICAO Annex 6 – Operation of Aircraft, Part 1 – International Commercial Air Transport – Aeroplanes, Chapter 6 (Aeroplanes Instruments, Equipment and Flight Documents) and Chapter 7 (Aeroplane Communication and Navigation Equipment).

1.5.2 Special equipment to be carried

1.5.2.1 All civil and State overflight aircraft operating within the Baghdad FIR must be approved by the State of the operator or the State of Registry for Basic Area Navigation (B-RNAV) or Required Navigation Performance 5 (RNP5). B-RNAV/RNP5 approved aircraft shall have the capability to maintain enroute lateral navigation accuracy along track position fixing of +/- 5NM or better, for 95% of the flight time in Iraqi airspace. Any aircraft unable to meet the navigation criteria will not be authorized to fly within Iraqi airspace.

1.5.2.2 Pilots of aircraft meeting B-RNAV/RNP5 standards must indicate R in field 10 of the ICAO flight plan. Operators are to ensure that all relevant procedures, publications and training are in accordance with B-RNAV/RNP 5 standards. Pilots must advise ATC of any deterioration or failure of their navigation system by stating “Unable RNAV due to equipment”. ATC will then attempt to provide alternative separation standards and/or routings.

1.5.2.3 There may be insufficient ground-based navigation aids (NAVAIDs) suitable for RNAV or Inertial Navigation System updating along the Iraqi air routes. Therefore, operators whose aircraft navigation systems depend upon ground-based NAVAID updating to meet RNP5 criteria shall conduct an analysis of the routes to be flown to ensure suitable NAVAID reception.

1.5.2.3 All aircraft operating in the Baghdad FIR shall be equipped with a serviceable Mode 3/A transponder.

1.5.3 Miscellaneous Information

1.5.3.1 Subject to the observance of the applicable rules, conditions and limitations set forth in this document and in legislation listed in GEN 1.6 and GEN 1.7, foreign civil aircraft registered in any foreign country that is a member of the ICAO may be navigated over Iraq.

1.5.3.2 Aircraft registered under the laws of foreign countries, that are not members of the ICAO, and which grant reciprocal treatment to Iraqi aircraft and airmen, may be navigated over Iraq subject to the observance of the same rules, conditions and limitations applicable as in the case of aircraft of ICAO member States.

1.5.3.3 Radiotelephony procedures and phraseology shall be in accordance with the ICAO Manual of Radiotelephony, Doc 9432 AN/925 and supporting sections of the current ICAO Doc 4444 ATM /501 Procedures for Air Navigation Services – Air Traffic Management.

**GEN 1.6 SUMMARY OF NATIONAL REGULATIONS AND INTERNATIONAL
AGREEMENTS/CONVENTIONS**

1.6.1 It is essential that personnel engaged in air operations comply with the relevant laws and regulations. Copies of the relevant documents may be obtained from the Ministry of Justice, the address of which is stated below. The following is a list of civil aviation legislation and air navigation regulations, etc. in force in Iraq:

1.6.1.1 Civil Aviation Law No.148 of 1974 (modified issue), (attention is drawn to section 15 of the law, concerning the executive actions taken against persons and airline companies deviating from the articles of the law and incorporated instructions).

1.6.1.2 Regulation No.4 of 1975 concerning the Rules of the Air.

1.6.1.3 Regulation No.27 of 1940 for the control of aerial navigation.

1.6.1.4 Regulation No.26 of 1987 governing the fees and charges for using Iraqi Airports.

1.6.1.5 Laws of Agricultural Quarantine and Instructions 1973/1974.

MINISTRY OF JUSTICE
Salihiya
Baghdad – Republic of IRAQ

Telephone numbers and P.O. Box to be advised by NOTAM once available

**GEN 1.7 DIFFERENCES FROM ICAO STANDARDS RECOMMENDED
PRACTICES AND PROCEDURES**

ANNEX 1	- PERSONNEL LICENSING, 8th edition:	Nil
ANNEX 2	- RULES OF THE AIR, 9th edition:	Nil
ANNEX 3	- METEOROLOGY, 13th edition: The Iraq AIP is at variance with Chapter 8, Section 8.3., airport climatological summaries for Iraq are not available	
ANNEX 4	- AERONAUTICAL CHARTS, 9th ^{edition} : The Iraq AIP is at variance with Chapter 4 Section 4.2. Aerodrome Obstacle Chart – ICAO Type B is not available for airports in Iraq.	
ANNEX 5	- UNITS OF MEASUREMENT TO BE USED IN AIR AND GROUND OPERATIONS, 4th edition:	Nil
ANNEX 6	- OPERATION OF AIRCRAFT, 7th edition:	Nil
ANNEX 7	- AIRCRAFT NATIONALITY AND REGISTRATION MARKS, 4th edition:	Nil
ANNEX 8	- AIRWORTHINESS OF AIRCRAFT, 8th edition:	Nil
ANNEX 9	- FACILITATION, 10th edition:	Nil
ANNEX 10	- AERONAUTICAL TELECOMMUNICATIONS, 5th edition:	Nil
ANNEX 11	- AIR TRAFFIC SERVICES, 12th edition: Air traffic services within Iraq are being primarily provided by coalition air traffic controllers. Whilst services are in accordance with ICAO classifications of airspace, certain phraseology or procedures may vary at different locations.	
ANNEX 12	- SEARCH AND RESCUE, 6th edition:	Nil
ANNEX 13	- AIRCRAFT ACCIDENT INVESTIGATION, 8th edition:	Nil
ANNEX 14	- AERODROMES, 3rd edition: Some of the facilities and procedures described in AD 2 may not comply with Annex 14.	
ANNEX 15	- AERONAUTICAL INFORMATION SERVICES, 10th edition: The Iraq AIP is at variance with Chapter 4, paragraph 4.1.3. Precision Approach Terrain Charts are not produced yet. Additionally, Iraq AIP is at a variance with Chapter 6 in that a mature Aeronautical Information Regulation and Control system has not been implemented in Iraq.	
ANNEX 16	- ENVIRONMENTAL PROTECTION, 3rd edition:	Nil
ANNEX 17	- SECURITY – SAFEGUARDING INTERNATIONAL CIVIL AVIATION AGAINST ACTS OF UNLAWFUL INTERFERENCE, 6th	Nil

edition:

ANNEX
18

- THE SAFE TRANSPORT OF DANGEROUS GOODS BY AIR, 2nd
edition:

Nil

GEN 2 TABLES AND CODES

GEN 2.1 MEASURING SYSTEM, AIRCRAFT MARKINGS, HOLIDAYS

2.1.1 Units of Measurement. Aeronautical stations within Baghdad FIR shall use the following table of units of measurement.

For Measurement of	Units Used
Distance used in navigation, position reporting, etc. generally in excess of 2 nautical miles.....	Nautical Miles and tenths
Relatively short distances such as those relating to aerodromes (e.g. RWY lengths).....	Meters
Altitudes, Elevations and Heights.....	Feet
Horizontal speed including wind speed.....	Knots
Vertical speed.....	Feet per minute
Wind direction for LDG and TKOF.....	Degrees Magnetic
Wind direction except for LDG and TKOF.....	Degrees True
Visibility including RWY visual range.....	Kilometers or Meters
Altimeter setting (barometric pressure).....	Hectopascals
Temperature.....	Degrees Celsius
Weight.....	Metric Tonnes or Kilograms
Time.....	Hours and Minutes beginning at midnight UTC

2.1.2 Time system

2.1.2.1 Coordinated Universal Time (UTC) is used by air navigation services and in publications issued by the Aeronautical Information Service. Reporting of time is expressed to the nearest minute, e.g. 12:40:35: is reported as 1241.

2.1.2.2 The expression 'Summer Period' indicates that part of the year in which daylight savings time is in force (UTC +4). The other part of the year is the 'Winter Period' (UTC+3). The Summer Period will begin every year on 31st March at 2300 UTC and will cease on the 30th September at 2300 UTC.

2.1.3 Geodetic Reference Datum. All published geographical coordinates indicating latitude and longitude are expressed in World Geodetic System 1984 (WGS84). WGS84 is applicable within the area of responsibility of the Aeronautical Information Service; i.e. the entire territory of Iraq as well as the airspace over the high seas encompassed by the Baghdad Flight Information Region in accordance with the regional agreement.

2.1.4 Aircraft Nationality and Registration Marks. The nationality mark for aircraft registered in Iraq is the letters 'YI'. The nationality mark is followed by a hyphen and a registration mark consisting of three letters, e.g. YI-ABC.

2.1.5 Public Holidays

2.1.5.1 The following is a list of the national public holidays for 2005 (1426) with dates corresponding to the Gregorian Calendar. Public holidays for Islamic events, which are marked with an asterisk, are based upon the Hijra Calendar which does not correspond or coincide with the Gregorian Calendar commonly used in aviation.

Name	Gregorian Date	Hijri Date	Duration Days
New Year's Day	1 January		1
Eid Al-Adh'ha Al-Mubarak (Greater Bairam)*	21 January	10 Thw Al-Hijjah	1
Spring Day	21 March		1
Hijri New Year's Day*	10 February	1 Muharram	1
Ashuraa' Day	19 February	10 Muharram	1
Prophet Mohammed's Birthday *	10 April	1 Rabie Awwal	1
14 th July Revolution Anniversary Day	14 July		1
Eid Al-Fitr Al-Mubarak (Lesser Bairam)*	3 November	1 Shawwal	1

2.1.5.2 The Hijra Year is approximately 10 days shorter than the Gregorian Year; therefore, the dates marked by asterisk will be moved forward by approximately 10 days per year. Additionally, the start of each month depends on moon sightings and cannot be accurately predicted.

2.1.5.3 Iraq applies a five working day week, with Fridays and Saturdays as official days off. Working hours commence at 0800 (local) and end at 1400, except on Thursdays, which end at 1300.

GEN 2.2 ABBREVIATIONS USED IN AIS PUBLICATIONS

Abbreviations marked by an asterisk (*) are either different from or not contained in ICAO Doc 8400.

(A)			
A(A0-A5)*	Amplitude modulation (AM)	APU	Auxiliary power unit
A/A	Air – to – Air	APV	Approve (approved)
AAL	Above aerodrome level	ARO	Air traffic services reporting office
ABM	Abeam	ARP	Aerodrome reference point
ABN	Aerodrome beacon	ARR	Arrive or arrival
ACC	Area control center or area control	ASDA	Accelerate-stop distance
ACFT	Aircraft	ASPH	Asphalt
ACL	Altimeter check location	ATA	Actual time of arrival
ACN	Aircraft classification number	ATC	Air traffic control (in general)
ACT	Active (activated, activity)	ATD	Actual time of departure
ADF	Automatic direction-finding equipment	ATIS	Automatic terminal information service
AFIS	Aerodrome flight information service	ATS	Air traffic services
AFS	Aeronautical fixed service	ATTN	Attention
AFTN	Aeronautical fixed telecommunication network	ATZ	Aerodrome traffic zone
A/G	Air – to – ground	AUG	August
AGA	Aerodrome, air routes and ground aids	AUW	All up weight
AGL	Above ground level	AVASIS	Abbreviated VASIS
AIC	Aeronautical information circular	AVBL	Available
AIP	Aeronautical information publication	AVGAS	Aviation gasoline
AIRAC	Aeronautical information regulation and control	(B)	
AIS	Aeronautical information service	BA	Braking action
ALT	Altitude	BCN	Beacon (Aeronautical ground light)
ALTN	Alternate (aerodrome)	BCST	Broadcast
AMD	Amendment (amend, amended)	BDRY	Boundary
AMDT	Amendment (AIP AMDT)	BLDG	Building
AMSL	Above mean sea level	BLW	Below
ANC*	Aeronautical chart 1:500, 000	BRG	Bearing
AOC	Aerodrome obstacle chart	BTN	Between
ANP	Air navigation plan	(C)	
APCH	Approach	C	Degrees Celsius (Centigrade)
APP	Approach control office or Approach control or approach control services	CAT	Category
APR	April	CH	Channel
APRX	Approximate	CHG*	Change or changed
		CIV	Civil
		CLSD	Closed

CM	Centimeter	ETA	Estimated time of arrival or
CNL	Cancel or cancelled		Estimating arrival
COM	Communication	ETD	Estimated time of departure
CONC	Concrete		identification or estimating
COP	Change/over point		departure
COR	Correct, corrected or correction	ETO	Estimated time over
CS*	Callsign		significant point
CTA	Control area	EXC	Except
CTR	Control zone		
CUST	Customs		(F)
CWY	Clearway		
	(D)	F	Fix/fixed
		FAC	Facilities
		FAF	Final approach fix
D...	Danger area (followed by	FAL	Facilitation of international
DB*	Decibel (noise level)		air transport
DCA*	Director or Department of	FAX	Facsimile transmission
	Civil Aviation	FCST	Forecast
DCT	Direct	FG	Fog
DEC	December	FIC	Flight information center
DEG	Degrees	FIR	Flight information region
DEP	Depart or departure	FIS	Flight information service
DEST	Destination	FL	Flight level
DIST	Distance	FLD	Field
DME	Distance measuring equipment	FLG	Flashing
DOC*	Document (ICAO)	FLR	Flares
DP	Due point	FLT	Flight
DST*	Day light saving time (Summer	FLTCK	Flight check
	time)	FLW	Follow(s) or following
DTG	Date – time group	FM	From
DUR	Duration	FMU	Flow management unit
DVOR	Doppler VOR	FNA	Final approach
DX	Duplex operation	FPL	Filed flight plan (message
			type designator)
	(E)	FREQ	Frequency
E	East or eastern longitude	FRI	Friday
EAT	Expected approach time	FRNG	Firing
EET	Estimated elapsed time	FRONT	Front (relating to weather)
ELBA	Emergency location beacon	FT	Feet (dimensional unit)
	aircraft		(G)
ELEV	Elevation	G	Green
EM	Emission	GEN	General
EMERG	Emergency	GND	Ground
EOBT	Estimated off - block time	GNDCK	Ground check
EQPT	Equipment	GP	Glide path
EST	Estimate or estimated or		
	estimate (message type		
	designator)		

(H)		(L)	
H24	Continuous day and night service	LAT	Latitude
HA	Humanitarian Assistance	LDA	Landing distance available
HDG	Heading	LDG	Landing
HEL	Helicopter	LGT	Light or lighting or lighted
HJ	Sunrise to sunset	LLZ	Localizer
HLDG	Holding	LON	Longitude
HN	Sunset to sunrise	LTD	Limited
HPA	Hectopascal	LTT	Landline teletypewriter
HR	Hours	LVL	Level
HVY	Heavy	(M)	
(I)		MAG	Magnetic
IAC	Instrument approach chart	MAINT	Maintenance
IAF	Initial approach fix	MAP	Aeronautical maps and charts
IAS	Indicated air speed	MAR	March
ICAA	Iraq Civil Aviation Authority	MAX	Maximum
ICE	Icing	MAY	May
IDENT	Identification	MET	Meteorological or meteorology
IF	Intermediate approach fix	METAR	Aviation routine weather report (in aeronautical meteorological code)
IFR	Instrument flight rules	MF	Medium frequency (300-3000KHz)
ILS	Instrument landing system	MHZ	Megahertz
INBD	Inbound	MIN	Minutes
INCERFA	Uncertainty phase	MNTN	Maintain
INFO	Information	MON	Monday
INOP	Inoperative	MOTNE	Meteorological operational telecommunications network Europe
INS	Inches (dimensional unit)	MOV	Move or moving or movement
INSTL	Install or installed	MRP	ATS/MET reporting point
INSTR	Instrument	MRU	Mountain rescue unit landing forecasts)
INT	Intersection	MSA	Minimum Safe Altitude
INTL	International	MSG	Message
I/V	Instrument/visual	MSL	Mean sea level
IWI	Illuminated wind indicator	MT	Mountain
(J)			
JAN	January		
JUL	July		
JUN	June		
(K)			
KG	Kilograms		
KHZ	Kilohertz		
KM	Kilometers		
KT	Knots		

(N)		OCT	October
N	North or northern latitude	OPMET	Operational meteorological (information)
N/A	Not applicable	OPN	Open or opening or opened
NAV	Navigation	OPR	Operator or operate or operative or operating or operational
NB	Northbound	OBS	Operations
NDB	Non-directional radio beacon	O/R	On request
NE	Northeast	OUBD	Outbound
NEG	No or negative or permission not Granted or that is not correct	(P)	
NGO	Non-governmental organizations	P	Prohibited area (followed by identification)
NGT	Night	PANS	Procedure for air navigation services
NIL	None or I have nothing to send to you	PAPI	Precision approach path indicator
NM	Nautical miles	PAR	Precision approach radar
NML	Normal	PARL	Parallel
NNE	North northeast	PAX	Passenger(s)
NNW	North northwest	PCN	Pavement classification number
NOF	International NOTAM office	PERM	Permanent
NOSIG	No significant change (used in trend-type)	PJE	Parachute jumping exercises
NOTAM	A notice containing information concerning the establishment, condition or change in any aeronautical facility, service, procedure or hazard, the timely knowledge of which is essential to personnel concerned with flight operations	PMI	Preventive Maintenance Interval
NOV	November	PN	Prior notice required
NR	Number	POB	Persons on board
NW	North-west	PPR	Prior permission required
NWB	North-westbound	PRI	Primary
NXT	Next	PRKG	Parking
(O)		PROB	Probability
OBS	Observe or observation	PS	Plus
OBSC	Obscure	PSN	Position
OBST	Obstacle	PWR	Power
OCA	Obstacle clearance altitude	(Q)	
OCA	Oceanic control area	QFE	Atmospheric pressure at aerodrome elevation (or at RWY threshold)
OCH	Obstacle clearance height	QNH	Altimeter sub-scale setting to obtain elevation when on the ground
OCL	Obstacle clearance limit		
OCNL	Occasional or occasionally		










(R)		SECT	Sector
R	Red	SEP	September
R	Restricted area (followed by identification)	SER	Service or servicing or served
RA	Rain	SFC	Surface
RAC	Rules of the air and air traffic services	SGL	Signal
RCC	Rescue co-ordination center	SID	Standard instrument departure
RCL	Runway center line	SIGMET	Information concerning en-route weather phenomena which may effect the safety of aircraft operations
RCLL	Runway center line light(s)	SITA	Societe International
RDH	Reference datum height (for ILS)	SKC	Sky clear
RDL	Radial	SKED	Schedule or scheduled
RDO	Radio	SNOWTAM	A special series NOTAM notifying the presence or removal or hazardous conditions due to snow, ice, or slush on the movement area, by means of a specific format
REC	Receive or receiver identification)	SPL	Supplementary flight plan (message type designator)
REF	Reference to or refer to	SR	Sunrise
REG	Registration	SRY	Secondary
REP	Report or reporting or reporting point	SS	Sunset
REQ	Request or requested	SSB	Single side band
RLCE	Request level change enroute	SSR	Secondary surveillance radar
RMK	Remark	STD	Standard
RNAV	Area navigation (pronounced AR NAV)	STAR	Standard instrument arrival
RNG	Radio range	STN	Station
RNP	Required Navigation Performance	SUB	Subject to
RPL	Representative flight plan	SUN	Sunday
RPT	Regular Public Transport	SUP	Supplement (AIP Supplement)
RTE	Route	SUPPS	Regional supplementary procedures
RTF	Radio telephone	SVC	Service message
RTT	Radio teletypewriter	SVCBL	Serviceable
RVR	Runway visual range	SWY	Stopway
RWY	Runway	SX*	Simplex operations
(S)			
S	South or southern latitude		
SAA	Senior Airfield Authority		
SAR	Search and rescue		
SARPS	Standards and recommended practices (ICAO)		
SAT	Saturday		
SC	Stratocumulus		
SCT	Scattered		
SDBY	Standby		
SEC	Seconds		
(T)			

T	Temperature	VOLMET	Meteorological information for aircraft in flight
TAF	Terminal area forecast	VOR	VHF Omni-directional radio range
TAS	True airspeed		
TBD	To be determined		
TEL	Telephone		(W)
TEM	Temporary or temporarily	W	West
TFC	Traffic	W	White
THR	Through	WAFC	World area forecast center
THU	Thursday	WDI	Wind direction indicator
TIL	Until	WED	Wednesday
TKOF	Take-off	WEF	With effect from or effective from
TMA	Terminal control area	WI	Within
TODA	Take-off distance available	WIE	With immediate effect or effective immediately
TOP	Cloud top	WILCO	I understand and will comply
TORA	Take-off run available	WPT	Waypoint
TT	Teletypewriter	WRNG	Warning
TTF	Trend type forecast	WT*	Wireless telegraphy
TUE	Tuesday	WX	Weather
TUR	Turbulence		(X)
TWR	Aerodrome control tower or aerodrome control		
TWY	Taxiway		
	(U)		
UFN	Until further notice	XBAR	Crossbar (or approach lighting system)
UHF	Ultra high frequency (300-3000 MHz)		(Y)
UIR	Upper flight information region		
UNL	Unlimited	Y	Yellow
U/S	Unserviceable	YR	Your
UTC	Universal coordinated time		(Z)
	(V)		
VAR	Magnetic variation	Z	Zulu (universal coordinated universal time)
VASIS	Visual approach slope indicator system		
VCY	Vicinity		
VDF	Very high frequency direction-finding station		
VFR	Visual flight rules		
VHF	Very high frequency (30-300 MHz)		
VIS	Visibility		



GEN 2.3 CHART SYMBOLS

See ICAO Annex 4 Appendix 2 for full list of symbols.




2.3.1 Aerodromes**2.3.1.1 Charts other than approach charts**

Civil (land)	
Civil (water)	
Joint civil and military (land)	
Joint civil and military (water)	
Military (land)	
Military (water)	
Emergency aerodrome or aerodrome with no facilities	
Sheltered anchorage	
Heliport	







2.3.1.2 Approach Charts

The aerodrome on which the procedure is based	
Aerodrome affecting the traffic pattern on the aerodrome on which the procedure is based	







2.3.2 Aerodrome Charts

Hard surface runway	
Unpaved runway	
Stop way	

2.3.3 Aerodrome installations and lights

Aerodrome reference point (ARP)	
Taxiways and parking areas	
Control Tower	TBD
Point light	
Barrette	TBD
Marine light	<div> <div>Alt B F</div> <div>Alternating Blue Fixed</div> </div> <div> <div>Fl G Gp</div> <div>Flashing Green Group</div> </div> <div> <div>Occ R SEC</div> <div>Occulting Red Sector</div> </div> <div> <div>sec (U) W</div> <div>Second Unwatched White</div> </div> <div>F ●</div>
Obstacle light	
Aeronautical ground light	
Wind direction indicator (lighted)	TBD
Wind direction indicator (unlighted)	TBD
Landing direction indicator (lighted)	
Landing direction indicator (unlighted)	T

2.3.4 Miscellaneous

Highest elevation on chart	<div> <div>Alternative</div> <div>17456</div> <div>.17456</div> </div>
Obstacle	
Group obstacles Note A: Numerals in italics indicate elevation of top obstacle above sea level. Note B: Upright numerals in parentheses indicate height above specified datum.	 <div> <div>A → 52</div> <div>(15) ← B</div> </div>
Restricted airspace (prohibited, restricted or danger areas)	
Common boundary of two areas	
Transmission line or overhead cable	
Isogonal	

GEN 2.4 LOCATION INDICATORS

2.4.1 Code Allocation. Iraq follows international conventions in the allocation of codes. The first letter is an ‘O’ to designate Middle East region. The second letter is ‘R’ designating locations in Iraq. The remaining two letters designate the landing area/location, and may not necessarily correlate with the English name of the location. Locations other than those given the ‘OR’ prefix are designated by three, four or five letter codes. To avoid confusion with location indicators, waypoints do not begin with the letters ‘OR’. The following table summarizes code allocation:

Type	Code	Example
Licensed aerodrome, aircraft landing area, helicopter landing site	Four letters (OR??)	Kirkuk – (ORKK)
Navigation Aid	Two or three letters	Basrah VOR (BSR)
Visual Waypoint	Four letters	<i>Not yet allocated</i>
IFR Waypoint	Five letters	MODIK

2.4.2 List of Location Codes**2.4.2.1 Encode**

Location	ICAO Indicator	Weather Code
Al Asad	ORAA	KQAJ
Al Iskandarariyah	ORAI	
Al Kut/ Ubaydah Bin Al Jarrah	ORUB	
Al Qaim	ORAQ	KQVO
Al Sahra	ORSH	KQSL
Al Taji	ORTI	KQAA
Al Taqaddum	ORAT	KQEZ
Ali Base/Talil	ORTL	KQXJ
An Numaniyah	ORAN	
Baghdad/Baghdad FIR	ORBB	
Baghdad INTL Airport	ORBI	KQTZ
Balad Southeast	ORBD	KQTO
Bashur	ORBR	
Basrah INTL Airport	ORMM	
Erbil INTL Airport	ORER	
Jalibah Southeast	ORJA	
Kirkuk	ORKK	KQTX
Korean Village	ORRW	
Mosul	ORBM	KQTU
Qasr Tall Mihil	ORQT	
Qayyarah West	ORQW	KQCO
Sulaymaniyah INTL Airport	ORSU	
Tall Afar	ORTF	KQTI
Talil/Ali Base	ORTL	KQXJ
Tikrit East	ORTK	
Tikrit South	ORTS	
Ubaydah Bin Al Jarrah/Al Kut	ORUB	
Umm Qasr	ORUQ	

2.4.2.2 Decode

ICAO Indicator	Location	Weather Code
ORAA	Al Asad	KQAJ
ORAI	Al Iskandarariyah	
ORAN	An Numaniyah	
ORAQ	Al Qaim	KQVO
ORAT	Al Taqaddum	KQEZ
ORBB	Baghdad/Baghdad FIR	
ORBD	Balad Southeast	KQTO
ORBI	Baghdad INTL Airport	KQTZ
ORBM	Mosul	KQTU
ORBR	Bashur	
ORER	Erbil INTL Airport	
ORJA	Jalibah Southeast	
ORKK	Kirkuk	KQTX
ORMM	Basrah INTL Airport	
ORQT	Qasr Tall Mihil	
ORQW	Qayyarah West	KQCO
ORRW	Korean Village	
ORSH	Al Sahra	KQSL
ORSU	Sulaymaniyah INTL Airport	
ORTF	Tall Afar	KQTI
ORTI	Al Taji	KQAX
ORTK	Tikrit East	
ORTL	Ali Base/Talil	KQXJ
ORTS	Tikrit South	
ORUB	Al Kut/ Ubaydah Bin Al Jarrah	
ORUQ	Umm Qasr	

GEN 2.5 LIST OF RADIO NAVIGATION AIDS

2.5.1 The security situation is such that the only radio navigational aid in Iraq that has been flight inspected for civil use is the Baghdad VOR. All current radio navigational aids are temporary military assets. Apart from the VOR DME to RWY 33R at BIAP, all other instrument procedures built utilizing these navigational aids are restricted for military use only.

Aid	Ident	FREQ	Lat/Long	Remarks
Al Asad TACAN	MAA	CH 57X	N33°47'14.37" E042°26'36.13"	VAR 4°E
Al Taqaddum TACAN	MAT	CH70X	N33°20'22.09" E043°35'38.16"	VAR 4°E
Baghdad TACAN	BGD	CH43X	N33°15'36.60" E044°14'58.10"	VAR 4°E
Baghdad VORW	BGD	110.600MHz	N33°15'38.60" E044°14'57.29"	VAR 4°E
Balad VORTAC	BLD	CH93X/114.6	N33°56'09.28" E044°22'05.01"	VAR 4°E
Basrah TACAN	BAR	CH20X/108.3	N30°31'32.40' E047°41'12.00'	VAR 3°02.9'E
Basrah VORW-DME	BSR	112.300MHz	N30°31.54' E047°41.20'	VAR 3°0.0'E
Kirkuk TACAN	KRK	CH86X	N35°28'16.42" E044°20'52.45"	VAR 4°01.4'E
Ali Base TACAN	TAL	CH84X	N30°56'06.94" E046°05'26.15"	VAR 3°E

GEN 2.6 CONVERSION TABLES

NM to KM 1 NM = 1.852KM		KM to NM 1 KM = 0.54 NM		FT to M 1 FT = 0.3048 M		M to FT 1 M = 3.281FT	
NM	KM	KM	NM	FT	M	M	FT
0.1	0.185	0.1	0.05	1	0.305	1	3.28
0.2	0.370	0.2	0.11	2	0.610	2	6.56
0.3	0.556	0.3	0.16	3	0.914	3	9.84
0.4	0.741	0.4	0.22	4	1.219	4	13.12
0.5	0.926	0.5	0.27	5	1.524	5	16.40
0.6	1.111	0.6	0.32	6	1.829	6	19.69
0.7	1.296	0.7	0.38	7	2.134	7	22.97
0.8	1.482	0.8	0.43	8	2.438	8	26.25
0.9	1.667	0.9	0.49	9	2.743	9	29.53
1	1.852	1	0.54	10	3.048	10	32.81
2	3.704	2	1.08	20	6.096	20	65.62
3	5.556	3	1.62	30	9.144	30	98.43
4	7.408	4	2.16	40	12.192	40	131.23
5	9.260	5	2.70	50	15.240	50	164.04
6	11.112	6	3.24	60	18.288	60	196.85
7	12.964	7	3.78	70	21.336	70	229.66
8	14.816	8	4.32	80	24.384	80	262.47
9	16.668	9	4.86	90	27.432	90	295.28
10	18.520	10	5.40	100	30.480	100	328.08
20	37.040	20	10.80	200	60.960	200	656.17
30	55.560	30	16.20	300	91.440	300	984.25
40	74.080	40	21.60	400	121.920	400	1312.34
50	92.600	50	27.00	500	152.400	500	1640.48
60	111.120	60	32.40	600	182.880	600	1968.50
70	129.640	70	37.80	700	213.360	700	2296.59
80	148.160	80	43.20	800	243.840	800	2624.67
90	166.680	90	48.60	900	274.320	900	2952.76
100	185.200	100	54.00	1000	304.800	1000	3280.84
200	370.400	200	107.99	2000	609.600	2000	6561.68
300	555.600	300	161.99	3000	914.400	3000	9842.52
400	740.800	400	215.98	4000	1219.200	4000	13123.36
500	926.000	500	269.98	5000	1524.000	5000	16404.20
				6000	1828.800		
				7000	2133.600		
				8000	2438.400		
				9000	2743.200		
				10000	3048.000		

GEN 2.7 SUNRISE/SUNSET TABLES

2.7.1 The tables on the following pages have been prepared using data from the United States Naval Observatory website. The tables provide data for selected airports. Data on other locations, or accurate times for dates falling between those listed below, may be obtained from: <http://aa.usno.navy.mil/>

Select 'Data Services' and enter appropriate year, latitude and longitude.

2.7.2 The times in the tables below are given in UTC for the beginning of the civil morning twilight (TWIL FM), sunrise (SR), sunset (SS), and the end of the civil evening twilight (TWIL TO).

2.7.3 2006 Sunrise-Sunset Table for Baghdad International Airport (ORBI). Based on approximation of ARP (N33° 15' E044° 14') the official times are as follows:

MTH	Day	TWIL FM	SR	SS	TWIL TO	MTH	Day	TWIL FM	SR	SS	TWIL TO
Jan	5	0340	0407	1410	1437	Jul	5	0130	0159	1616	1645
	10	0340	0407	1414	1441		10	0133	0202	1615	1643
	15	0340	0407	1418	1445		15	0136	0205	1613	1641
	20	0339	0405	1423	1450		20	0140	0208	1611	1639
	25	0337	0403	1428	1454		25	0143	0211	1608	1635
	30	0334	0400	1433	1459		30	0147	0214	1604	1632
Feb	5	0330	0356	1438	1504	Aug	5	0152	0219	1559	1626
	10	0326	0352	1443	1509		10	0156	0222	1554	1621
	15	0322	0347	1448	1513		15	0159	0226	1549	1615
	20	0317	0342	1452	1517		20	0203	0229	1544	1609
	25	0311	0336	1456	1521		25	0207	0232	1538	1603
							30	0210	0236	1531	1557
Mar	1	0307	0332	1500	1525						
	5	0302	0327	1503	1528	Sep	5	0215	0240	1523	1549
	10	0255	0321	1507	1532		10	0218	0243	1517	1541
	15	0249	0314	1511	1535		15	0221	0246	1510	1535
	20	0243	0307	1514	1539		20	0225	0250	1503	1528
	25	0236	0301	1518	1543		25	0228	0253	1456	1521
	30	0229	0254	1522	1547		30	0232	0256	1449	1514
Apr	5	0221	0246	1526	1551	Oct	5	0235	0300	1443	1508
	10	0214	0239	1530	1555		10	0239	0303	1436	1501
	15	0208	0234	1533	1559		15	0242	0307	1430	1455
	20	0202	0228	1537	1603		20	0246	0311	1424	1449
	25	0156	0222	1541	1607		25	0250	0315	1419	1444
	30	0150	0217	1545	1611		30	0254	0319	1414	1439
May	5	0145	0212	1548	1615	Nov	5	0259	0325	1408	1434
	10	0140	0207	1552	1619		10	0303	0329	1404	1430
	15	0136	0204	1556	1623		15	0307	0334	1401	1427
	20	0133	0200	1559	1627		20	0312	0338	1359	1425
	25	0130	0158	1603	1631		25	0316	0343	1357	1424
	30	0127	0156	1606	1634		30	0320	0347	1356	1423
Jun	5	0125	0154	1609	1638	Dec	5	0324	0352	1355	1423
	10	0125	0153	1612	1641		10	0328	0355	1356	1423
	15	0124	0153	1614	1643		15	0332	0359	1357	1425
	20	0125	0154	1615	1644		20	0334	0402	1359	1427
	25	0126	0155	1616	1645		25	0337	0404	1402	1429
	30	0128	0157	1616	1645		30	0339	0406	1405	1432

2.7.4 2006 Sunrise – Sunset Table for Basrah International Airport (ORMM). Based on approximation of ARP (N30° 33' E047° 40') the official times are as follows:

MTH	Day	TWIL FM	SR	SS	TWIL TO	MTH	Day	TWIL FM	SR	SS	TWIL TO
Jan	5	0321	0347	1402	1429	Jul	5	0124	0152	1556	1623
	10	0321	0348	1406	1432		10	0127	0154	1555	1622
	15	0321	0347	1410	1436		15	0130	0157	1553	1620
	20	0320	0346	1415	1441		20	0133	0200	1551	1618
	25	0319	0344	1419	1445		25	0136	0203	1549	1615
	30	0317	0342	1424	1449		30	0140	0206	1545	1612
Feb	5	0313	0338	1429	1454	Aug	5	0144	0210	1541	1607
	10	0310	0334	1433	1458		10	0147	0213	1536	1602
	15	0306	0330	1437	1502		15	0150	0216	1532	1557
	20	0301	0325	1441	1506		20	0154	0219	1526	1551
	25	0256	0320	1445	1509		25	0157	0222	1521	1546
							30	0200	0225	1515	1540
Mar	1	0252	0316	1448	1512						
	5	0248	0312	1451	1515	Sep	5	0203	0228	1508	1532
	10	0242	0306	1454	1518		10	0206	0231	1502	1526
	15	0236	0300	1457	1521		15	0209	0233	1455	1519
	20	0230	0254	1501	1525		20	0212	0236	1449	1513
	25	0223	0248	1504	1528		25	0215	0239	1443	1507
	30	0217	0241	1507	1531		30	0218	0242	1436	1500
Apr	5	0210	0234	1511	1535	Oct	5	0221	0245	1430	1454
	10	0204	0228	1514	1538		10	0224	0248	1424	1448
	15	0158	0222	1517	1542		15	0227	0251	1419	1443
	20	0152	0217	1520	1545		20	0230	0255	1413	1438
	25	0147	0212	1523	1549		25	0234	0258	1408	1433
	30	0142	0207	1527	1552		30	0237	0302	1404	1428
May	5	0137	0203	1530	1556	Nov	5	0242	0307	1359	1424
	10	0133	0159	1533	1559		10	0246	0311	1355	1420
	15	0129	0155	1537	1603		15	0250	0315	1352	1418
	20	0126	0152	1540	1606		20	0254	0319	1350	1416
	25	0123	0150	1543	1610		25	0258	0323	1349	1415
	30	0121	0148	1546	1613		30	0302	0328	1348	1414
Jun	5	0119	0147	1549	1616	Dec	5	0305	0332	1348	1414
	10	0119	0146	1551	1619		10	0309	0335	1349	1415
	15	0119	0146	1553	1621		15	0312	0339	1350	1416
	20	0119	0147	1555	1622		20	0315	0342	1352	1419
	25	0121	0148	1555	1623		25	0317	0344	1355	1421
	30	0122	0150	1556	1623		30	0319	0346	1358	1424

2.7.5 2006 Sunrise – Sunset Table for Kirkuk Airport (ORKK). Based on approximation of ARP (N35° 28' E044° 21') the official times are as follows:

MTH	Day	TWIL FM	SR	SS	TWIL TO	MTH	Day	TWIL FM	SR	SS	TWIL TO
Jan	5	0344	0412	1404	1432	Jul	5	0123	0153	1621	1651
	10	0344	0412	1408	1436		10	0126	0155	1620	1650
	15	0344	0411	1413	1441		15	0129	0159	1618	1647
	20	0342	0410	1418	1445		20	0133	0202	1616	1645
	25	0340	0407	1423	1450		25	0137	0205	1612	1641
	30	0337	0404	1428	1455		30	0141	0209	1608	1637
Feb	5	0333	0359	1434	1501	Aug	5	0146	0214	1603	1631
	10	0328	0355	1439	1506		10	0150	0218	1558	1625
	15	0324	0350	1444	1510		15	0155	0222	1552	1619
	20	0318	0344	1449	1515		20	0159	0225	1546	1613
	25	0312	0338	1454	1520		25	0203	0229	1540	1606
							30	0207	0233	1533	1559
Mar	1	0307	0333	1458	1523						
	5	0302	0328	1501	1527	Sep	5	0212	0238	1525	1550
	10	0256	0321	1506	1531		10	0216	0241	1517	1543
	15	0249	0314	1510	1535		15	0219	0245	1510	1536
	20	0241	0307	1514	1539		20	0223	0249	1503	1528
	25	0234	0300	1518	1544		25	0227	0253	1456	1521
	30	0227	0253	1522	1548		30	0231	0256	1448	1514
Apr	5	0218	0244	1527	1553	Oct	5	0235	0300	1441	1507
	10	0211	0237	1531	1557		10	0239	0304	1434	1500
	15	0204	0231	1535	1602		15	0243	0309	1428	1453
	20	0158	0224	1539	1606		20	0247	0313	1421	1447
	25	0151	0218	1544	1610		25	0251	0317	1416	1442
	30	0145	0213	1548	1615		30	0256	0322	1410	1436
May	5	0140	0207	1552	1619	Nov	5	0301	0328	1404	1431
	10	0135	0203	1556	1624		10	0306	0333	1400	1427
	15	0130	0158	1600	1628		15	0311	0338	1356	1423
	20	0126	0155	1604	1633		20	0315	0343	1353	1421
	25	0123	0152	1608	1637		25	0320	0347	1351	1419
	30	0120	0150	1611	1640		30	0324	0352	1350	1418
Jun	5	0118	0148	1615	1644	Dec	5	0328	0357	1350	1418
	10	0117	0148	1615	1647		10	0332	0401	1350	1418
	15	0117	0147	1617	1649		15	0336	0404	1351	1419
	20	0117	0147	1621	1651		20	0339	0407	1353	1421
	25	0119	0149	1622	1652		25	0341	0410	1356	1424
	30	0120	0150	1622	1652		30	0343	0411	1359	1427

GEN 3 SERVICES

GEN 3.1 AERONAUTICAL INFORMATION SERVICES

3.1.1 Responsible service

3.1.1.1 The Aeronautical Information Service, which forms part of the Iraq Civil Aviation Authority, ensures the flow of information necessary for the safety and regularity of international and domestic air navigation within the area of its responsibility as indicated under GEN 3.1.2 below. It consists of AIS Headquarters, International NOTAM Office (NOF) and AIS units established at the aerodromes as listed under GEN 3.1.5 below. The service is provided in accordance with the provisions contained in ICAO Annex 15 – Aeronautical Information Services.

3.1.1.2 Due to a lack of technical infrastructure, ICAA does not currently have the capability to maintain efficient AIS. All FIR and airfield NOTAMs are currently being promulgated through the ACA.

3.1.1.3 Addresses and contact details for the ICAA AIS Headquarters and International NOTAM Office will be confirmed by NOTAM once established.

3.1.2 Area of responsibility. The Aeronautical Information Service is responsible for the collection and dissemination of information for Iraq and for the airspace over the high seas encompassed by the Baghdad FIR.

3.1.3 Aeronautical publications

3.1.3.1 The aeronautical information is provided in the form of the Integrated Information Package consisting of the following elements:

3.1.3.1.1 Aeronautical Information Publication (AIP)

3.1.3.1.2 Supplement to the AIP (AIP SUP);

3.1.3.1.3 Aeronautical Information Circular (AIC):

3.1.3.1.4 NOTAM and Pre-flight Information Bulletin (PIB); and

3.1.3.1.5 Checklists and summaries.

3.1.3.2 Aeronautical Information Publication (AIP)

3.1.3.2.1 The AIP is the overarching aviation document intended primarily to satisfy international requirements for the exchange of permanent aeronautical information and long duration temporary changes essential for safe and efficient air navigation. The Iraq AIP is published in one volume. **The AIP is published in an electronic format as a Microsoft Word document**, in English only, for use in international and domestic operation, whether the flight is a commercial or private one.

3.1.3.2.2 The AIP is amended by the publication of a full edition AIP in accordance with a 56 day AIRAC cycle. A brief description of the references affected by the publication of a full

edition AIP will be provided in the form of a Summary of Changes. Changes of note or significance are included; correction of editorial errors will not be included. A checklist of AIP pages containing page number/chart title and the publication or effective date (day, month by name, and year) of the information is reissued with each edition.

3.1.3.3 Supplement to the AIP (AIP SUP)

3.1.3.3.1 Temporary changes of long duration and information of short duration that consists of extensive text and/or text supplementing the permanent information contained in the AIP are published as AIP Supplements (AIP SUP). Due to the newly established AIP and AIP AMDT cycle it is unlikely that the use of AIP SUP will be common. However, the following paragraph describes their use.

3.1.3.3.2 AIP SUP are separated by information subject (General – GEN, En-route – ENR and Aerodromes – AD) and, when issued, are to be placed at the beginning of each relevant AIP part. Each AIP Supplement is allocated a consecutive serial number, based on the calendar year, e.g. AIP SUP 01/06. Each AIP SUP is to remain in the AIP as long as all or some of its contents remain valid. The period of validity of the information contained in the AIP SUP will normally be given in the supplement itself. Alternatively, a NOTAM may be used to indicate changes to the period of validity or cancellation of the AIP SUP. Any AIP SUP will, for the short term, be published on the RAMCC Iraq webpage co-located with the full edition AIP. Notification of AIP SUP release will be via a Baghdad FIR NOTAM.

3.1.3.4 Aeronautical Information Circular (AIC)

3.1.3.4.1 Aeronautical Information Circulars (AIC) contain information on the long-term forecast of any major change in legislation, regulation, procedures or facilities. The information contained within the AIC is to be considered advance notice. While unlikely to change significantly information within the AIC is provided as advisory only until formally promulgated within the AIP, AIP AMDT, and AIP SUP or via NOTAM. Information likely to be contained in an AIC may include:

3.1.3.4.1.1 Information of a purely explanatory or advisory nature liable to affect flight safety; and,

3.1.3.4.1.2 Information or notification of an explanatory or advisory nature concerning technical, legislative or purely administrative matters.

3.1.3.4.2 Each AIC is allocated a consecutive serial number, based on the calendar year, e.g. AIC 01/06. Any AIC released will be published on the RAMCC Iraq webpage co-located with the full edition AIP. Notification of AIC release will be via a Baghdad FIR NOTAM. Notification of AIC cancellation will be via NOTAM.

3.1.3.5 NOTAM and Pre-flight Information Bulletins (PIB)

3.1.3.5.1 NOTAMs contain information concerning the establishment, condition or change in any aeronautical facility, service, procedure or hazard, the timely knowledge of which is essential for personnel concerned with flight operations. The text of each NOTAM contains the information in the order shown in the ICAO NOTAM Format and is composed of the significations/uniform abbreviated phraseology assigned to the ICAO NOTAM Code. This is complemented by ICAO abbreviations, indicators, identifiers, designators, callsigns,

frequencies, figures and plain language. NOTAMs are issued and published via several means. Each pilot in command, Civil Air Carrier/Operator is responsible for ensuring current NOTAMs are reviewed.

3.1.3.6 Sale of Publications. Publications may be obtained from the Aeronautical Information Service (see GEN 0.1.4 for AIS address). Purchase prices are as follows:

Publication	Price for a complete copy	
	In Iraq	Outside Iraq
AIP – IRAQ	<i>No charge</i>	
ANNUAL subscription including NOTAM/AIC services	<i>No charge</i>	
AIP ring binder	<i>Not currently available</i>	

3.1.4 Aeronautical Information Regulation and Control (AIRAC) system. A complete AIRAC system is partially implemented in Iraq. However, in order to publish the operationally significant changes requiring amendments to charts, routes manuals, etc. such changes, whenever possible, will be issued as a NOTAM to allow early delivered to recipients before the date(s) of applicability. If possible the effective date of operationally significant changes will be set such to allow timely advice.

3.1.4.1 The following table describes the full edition AIP effective dates:

Publication Name & Edition / Serial Number	Effective date	AIP submission close date
AIP Edition 17	16 Mar 06	06 Mar 06
AIP Edition 18	11 May 06	01 May 06
AIP Edition 19	06 Jul 06	26 Jun 06
AIP Edition 20	31 Aug 06	21 Aug 06
AIP Edition 21	26 Oct 06	16 Oct 06
AIP Edition 22	21 Dec 06	11 Dec 06

3.1.5 Pre-flight Information Service at aerodromes. Pre-flight Information Service is provided at both Baghdad and Basrah International aerodromes through self-briefing at the AIS units (Briefing Office) which is located at the terminal building and connected to the AIS Headquarters.

GEN 3.2 AERONAUTICAL CHARTS

3.2.1 Responsible Services. The Civil Aviation Authority of Iraq, Aeronautical Information Service, provides aeronautical charts which as part of the AIP. Charts suitable for pre-flight planning and briefing, selected from those listed in the ICAO aeronautical chart catalogue (Doc 7101), are available for reference at aerodrome AIS units, or purchase from AIS Headquarters. The AIS Headquarters address is listed at GEN 3.1. The charts are produced in accordance with the provisions contained in ICAO Annex 4 - Aeronautical Charts. Differences to these provisions are detailed in subsection GEN 1.7.

3.2.2 Maintenance of Charts

3.2.2.1 The aeronautical charts included in the AIP are kept up to date by amendments to the AIP. Information concerning the planning for or issuance of new maps and charts is notified by Aeronautical Information Circular.

3.2.2.2 If incorrect information detected on published charts is of operational significance, it is corrected by NOTAM.

3.2.3 Purchase arrangements

3.2.3.1 The charts as listed under GEN 3.2.5 may be obtained from AIS Headquarters, the address of which is at GEN 3.1. During the reconstruction of Iraq's air navigation system, charts are available from the following website:

<http://164.214.2.62/products/digitalaero/index.html>

Follow links for Enroute or Terminal charts as applicable.

3.2.3.2 The Civil Aviation Authority and the Aeronautical Information Service have copies of the ICAO Aeronautical Charts Catalogue (Doc 7101) where all aeronautical charts or chart series produced by this and other countries are listed and known to be available to civil aviation.

3.2.4 Aeronautical chart series

3.2.4.1 The following aeronautical charts are produced:

3.2.4.1.1 Aerodrome Chart – ICAO. This chart contains detailed aerodrome data to provide flight crew with information that will facilitate the ground movement of aircraft between the aircraft stand(s) to, and from, the RWY(s).

3.2.4.1.2 Aerodrome Ground Movement Chart – ICAO. This chart is produced for both Baghdad and Basrah International aerodromes where, due to the congestion of information, details necessary for the ground movement of aircraft along the TWYs to and from the aircraft stands and for the parking/docking of aircraft cannot be shown with sufficient clarity on the Aerodrome Chart – ICAO.

3.2.4.1.3 Aircraft Parking/Docking Chart – ICAO. This chart is produced for both Baghdad and Basrah international aerodromes where, due to the complexity of the terminal facilities, the information to facilitate the ground movement of aircraft between the TWYs and the aircraft stands and the parking/docking of aircraft cannot be shown with sufficient clarity on the Aerodrome Chart – ICAO or on the Aerodrome Ground Movement Chart- ICAO.

3.2.4.1.4 Aerodrome Obstacle Chart – ICAO – Type A (Operating Limitations). This chart contains detailed information on obstacles in take-off flight path areas of aerodromes. It is shown in plan and profile view. This obstacle information provides the data necessary to enable an operator to comply with the operating limitations of ICAO Annex 6, Part I and II, Chapter 5.

3.2.4.1.5 Instrument Approach Chart – ICAO. This chart is produced for all aerodromes used by civil aviation where instrument approach procedures are established. A separate Instrument Approach Chart ICAO is provided for each procedure. The aeronautical data shown includes information on aerodromes, prohibited, restricted, and danger areas, radio communication facilities and navigation aids, minimum sector altitudes, procedure track portrayed in plan and profile view, aerodrome operating minima, etc. This chart provides the flight crew with information that will enable them to perform an approved instrument approach procedure to the RWY of intended landing including the missed approach procedure and when applicable, associated holding patterns.

3.2.4.1.6 En-route Chart – ICAO. This chart is produced for the entire Baghdad FIR. The aeronautical data includes aerodromes, prohibited, restricted, and danger areas and the air traffic services system in detail. This chart provides the flight crew with information that will facilitate navigation along ATS routes in compliance with air traffic service procedures.

3.2.4.1.7 Standard Departure Chart – Instrument (SID) – ICAO. This chart is produced whenever a standard departure route – instrument is established and cannot be shown with sufficient clarity on the terminal area chart. The aeronautical data shown includes the aerodrome of departure, aerodrome(s) which affect the designated standard departure route-instrument, prohibited, restricted and danger areas and the air traffic services system. This chart provides the flight crew with information that will enable them to comply with the designated standard departure route – instrument from the take-off phase to the en-route phase.

3.2.4.1.8 Standard Arrival Chart – Instrument (STAR) – ICAO. This chart is produced whenever a standard arrival route –instrument has been established and cannot be shown with sufficient clarity on the terminal area chart. The aeronautical data shown includes the aerodrome of landing, aerodrome(s) which affect the designated standard arrival route – instrument, prohibited, restricted and danger areas and the air traffic service system. This chart provides the flight crew with information that will enable them to comply with the designated standard arrival route –instrument from the en-route phase to the approach phase.

3.2.5 List of Aeronautical Charts Available

Those chart series marked by an asterisk form part of the AIP.

Title of series	Scale	Name/number	Price
Aerodrome Chart-ICAO* (AC)	1:10 000	Baghdad/Basrah Intl	<i>No Charge</i>
Aerodrome Ground Movement Chart - ICAO (AGMC)	not to scale	Baghdad/Basrah Intl	<i>No Charge</i>
Aircraft Parking/ Docking Chart-ICAO (APDC)	not to scale	Baghdad/Basrah Intl	<i>No Charge</i>
Aerodrome Obstacle Chart ICAO-Type A (AOC)	1:20 000	Baghdad/Basrah Intl	<i>No Charge</i>
Instrument Approach Chart-ICAO (IAC)	not to scale	Baghdad/Basrah Intl	<i>No Charge</i>
En-route Chart-ICAO		Baghdad/Basrah Intl	<i>No Charge</i>

3.2.6 Index to the World Aeronautical Chart (WAC) – ICAO. The production of World Aeronautical Chart 1 000 000 is suspended at the present time.

3.2.7 Topographical Charts. Topographical charts may be available, on request, from AIS Headquarters (see GEN 0.1.4).

GEN 3.3 AIR TRAFFIC SERVICES

3.3.1 Responsible Service

3.3.1.1 The Department of Air Traffic Services with the Iraqi Civil Aviation Authority is the responsible authority for the provision of air traffic services within the area indicated under GEN 3.3.2. Contact details are at GEN 0.1.4.

3.3.1.2 Air traffic services are provided in accordance with the provision contained in the following ICAO documents:

Annex 2	Rules of the Air
Annex 11	Air Traffic Services
Doc 4444	Procedures for Air Navigation Services – Air Traffic Management
Doc 8168	Procedures for Air Navigation Services – Aircraft Operations (PANS-OPS)
Doc 7030	Regional Supplementary Procedures

3.3.1.3 Differences to these provisions are detailed at GEN 1.7.

3.3.1.4 Air Traffic Services are provided H24 at Baghdad and Basrah International Airports and for enroute traffic overflying the Baghdad FIR.

3.3.2 Area of responsibility. Air traffic services are provided for the entire Baghdad FIR. This includes the territory of Iraq and its territorial waters.

3.3.3 Types of air traffic services

3.3.3.1 A combined military and civilian air traffic service workforce provides the following types of air traffic services in Iraq:

3.3.3.1.1 **Aerodrome Control Service** is provided to aerodrome traffic within 5NM below approximately 3000FT AGL at aerodromes at which a control tower is operating, unless otherwise specified. The control function in respect of aerodrome and other traffic operating on the surface outside the landing area in use may be provided separately and is termed Surface Movement Control.

3.3.3.1.2 **Apron Service** is provided to aircraft (under tow or power) operating on the apron area of an airport by air traffic control or another agency.

3.3.3.1.3 **Approach/Departure Control Service** is provided to flights within 55NM of Balad South East and Basrah and within 30NM of Mosul, while within controlled airspace. Services to flights operating to or from Baghdad International are currently provided from Balad within the Balad Class E airspace. For military aircraft approach/departure control service is provided within 55NM of Ali Base and Kirkuk, while within controlled airspace. Approach/departure control service is provided until the arriving flights become aerodrome traffic and to departing flights from the time they cease to be aerodrome traffic until they climb independently of approaching flights or aircraft departing on other routes. The control function concerned with departing traffic when separately established is termed Departure Control, the remaining function then being termed Approach Control. Approach/Departure

control service will be provided jointly with aerodrome control service, unless specified otherwise in Enroute Supplement.

3.3.3.1.4 **Area Control Service** is provided to flights operating in control area when not provided with aerodrome or approach control service.

3.3.3.1.5 **Air Traffic Control Radar Service** is the predominant means of control at Baghdad, Basrah and, when activated by military authorities, Balad, Kirkuk, Mosul and Ali Base. Radar service may include the following:

3.3.3.1.5.1 The **Radar Control Service** provides positive traffic separation (except between VFR flights in VMC in Class D and E airspace) and the monitoring of aircraft navigation, to radar identified traffic in controlled airspace.

3.3.3.1.5.2 The **Radar Information Service** (RIS) is a service provided by ATC within radar coverage. It provides traffic, position and navigation information to flights not receiving a separation service and is available to improve situational awareness and assist pilots in avoiding collisions with other aircraft. At pilot request, and, if possible, a controller providing radar services will suggest a course of action to avoid other aircraft. Ultimate responsibility for aircraft and terrain avoidance rests with the pilot in command. This service may be provided in Class G airspace to IFR flights in relation to other IFR flights and, unless impracticable, in relation to observed VFR flights. It may also be provided to VFR flights in Class E and G airspace.

3.3.3.1.5.3 The **Final Approach Service** provides a precision or surveillance radar service for final approach.

3.3.3.1.5.4 The **Emergency Service** provides navigation assistance to aircraft in distress or experiencing navigational difficulties.

3.3.3.1.6 **Flight Information and SAR Alerting Services** are provided concurrently with the services shown above. In areas where air traffic control services are not provided, flight information and SAR alerting services are not provided by ATS units.

3.3.3.2 In some circumstances a number of services may operate under a common callsign and can be on a common or separate frequency:

3.3.3.2.1 **Clearance Delivery:** used by the Airways Clearance Delivery (ACD) service when established on a discrete frequency.

3.3.3.2.2 **Ground:** used by Surface Movement Control and Apron Service (if provided by ATC) when established on a discrete frequency. At some locations, this service also provides the Airways Clearance Delivery service on the same frequency.

3.3.3.2.3 **Tower:** used by Aerodrome Control and occasionally Aerodrome/Approach Control when these services are combined and provided by one agency.

3.3.3.2.4 **Approach:** used by Approach Control (APP) service when established on a discrete frequency and Approach/Departure Control when combined on the same frequency.

3.3.3.2.5 **Departure:** used by Departure Control (DEP) service when established on a discrete frequency.

3.3.3.2.6 **Center:** used for Area Control (ACC) service.

3.3.4 Coordination between the operator and air traffic services. Coordination between the operator and traffic services is affected in accordance with 2.15 of ICAO Annex 11 and 11.2.1.1.4 and 11.2.1.1.5 of Chapter 11 of the Procedures for Air Navigation Services - Air Traffic Management (Doc 4444 ATM/501).

3.3.5 Minimum Flight Altitude. The minimum flight altitudes on the ATS routes published for the Baghdad FIR have been determined so as to ensure at least 1000 FT (300 M) vertical clearance above the highest obstacle within 5 NM either side of the centerline of the route.

3.3.6 ATS Units Address List

Unit name	Postal address	Telephone NR	Telefax NR	Telex NR	AFS/AFTN Address
BASRAH APP (or TWR)	Department of Air Traffic Services, Basrah Int'l Airport, Basrah, Iraq	TBD	TBD	207023 BIA IK	ORMMZQZX
BAGHDAD ACC (or APP, TWR or RADIO)	Department of Air Traffic Services, BAGHDAD Int'l Airport, Baghdad, Iraq	TBD	TBD	212500 YIA IK	ORBIZGZX

GEN 3.4 COMMUNICATION SERVICES

3.4.1 Responsible Service

3.4.1.1 The responsible service for the provision of telecommunication and navigation facility services in Iraq is The Iraq Civil Aviation Authority. The address and contact details are listed at GEN 0.1.4.

3.4.1.2 The service is provided in accordance with provisions contained in the following ICAO documents:

Annex 10 -	Aeronautical Telecommunications
Doc 8400-	Procedures for Air Navigation Services-ICAO Abbreviations and Codes (PANS-ABC)
Doc 8585-	Designators for Aircraft Operating Agencies, Aeronautical Authorities and Services
Doc 7030-	Regional Supplementary Procedures
Doc 7910-	Location Indicators

3.4.2 **Area of Responsibility.** Communication services are provided for the entire Baghdad FIR. Arrangements for such services on a continuing basis should be made with the Director of Communication Services. Responsibility for the day-to-day operation of these services is vested in Station Communication Officers located at Basrah and Baghdad International Aerodromes. Inquiries, suggestions or complaints regarding any telecommunication service should be referred to the relevant communication officer or to the Director of Communication Services, as appropriate.

3.4.3 Types of Services

3.4.3.1 Radio Navigation Services.

The following types of radio aids to navigation are available:

VHF Omni-directional Radio Range	(VOR)
Distance Measuring Equipment	(DME)
Tactical Air Navigation	(TACAN)

3.4.3.2 **Mobile Service.** The aeronautical stations maintain a continuous watch on their stated frequencies during the published hours of service unless otherwise notified. An aircraft should normally communicate with the air-ground agency that exercises control in the area in which the aircraft is flying. Aircraft should maintain a continuous watch on the appropriate frequency of the control station and should not abandon watch, except in an emergency, without informing the control station.

3.4.3.3 **Fixed Service.** The messages to be transmitted over the Aeronautical Fixed Service/Aeronautical Fixed Telecommunication Network (AFS/AFTN) are accepted only if they satisfy the requirements of ICAO Annex 10, Vol. II Chapter 3.3; they are prepared in the form specified in ICAO Annex 10; and the text on an individual message does not exceed 200 groups. General aircraft operating agency messages are only accepted for transmission to countries that have agreed to accept Class B traffic.

3.4.3.4 Broadcasting Services

3.4.3.4.1 Sub-area meteorological broadcasts (VOLMET radio telegraphy broadcasts) are available for the use by aircraft in flight. Full details are given at GEN 3.5.

3.4.3.4.2 **Automatic Broadcast Services** in the form of Automatic Terminal Information Service (ATIS) is established at Baghdad and Basrah International Aerodromes. The normal operational information required by aircraft prior to take-off or landing is broadcast automatically and continuously either on a discrete frequency or on the voice channel of one or more radio-navigation aids. The broadcast may be pre-recorded or computerized.

3.4.3.4.3 The following information is transmitted on the ATIS:

(aerodrome) TERMINAL INFORMATION (code letter ALPHA, BRAVO, etc., as assigned to each separately prepared transmission. “ZULU” is not used)
TIME (hh mm UTC) time of observations, if appropriate
“EXPECT ... [e.g.TACAN, ASR or VISUAL] APPROACH”

One RWY in Use:

RWY (number), [DAMP] [WET] [WATER PATCHES] [FLOODED] (if applicable)
or

More Than One RWY in Use:

RWY/S (number/s) AND (number/s) FOR ARRIVALS,
RWY/S (number/s) AND (number/s) FOR DEPARTURES, [DAMP] [WET]
[WATER PATCHES] [FLOODED] (if applicable)


Significant RWY surface conditions and, if appropriate, braking action
... MINUTES HOLDING MAY BE EXPECTED (if appropriate)
WIND ... DEGREES ... KNOTS (include significant variations)
VISIBILITY ... KILOMETRES or METERS as applicable or RVR, when applicable
CLOUD [FEW] [SCATTERED] [BROKEN] or [OVERCAST] below 1 500 m (5 000 ft) or below the highest minimum sector altitude, whichever is greater and any Cumulonimbus;
TEMPERATURE ...
DEW POINT ...
QNH ...
Any available information on significant meteorological phenomena in the approach and climb-out areas including wind shear, and information on recent weather of operational significance;
ON FIRST CONTACT WITH [Baghdad or Basrah] [GROUND, TOWER OR APPROACH], NOTIFY RECEIPT OF ...

3.4.3.5 Language used is **English**.

3.4.3.6 Communication facilities are under reconstruction. Details of the various communication agencies available for enroute traffic can be found at ENR 2.1 and ENR 3.3.1. Details of the facilities available at individual aerodromes can be found in the relevant sections of Part 3 (AD). In the case where a facility is serving both the enroute traffic and the aerodromes, details are given in the relevant sections of Part 2 (ENR) and Part 3 (AD).


3.4.4 **Requirements and conditions.** No specific requirements or conditions exist.

AERONAUTICAL FIXED SERVICES: TELEGRAPH/AFTN



LEGEND	
LANDLINE TELETYPEWRITER CIRCUIT (LTT)	————
RADIO TELETYPEWRITER CIRCUIT (RTT)	-----
DUPLEX CIRCUIT	II
INTERNATIONAL CIRCUIT	✕

AERONAUTICAL FIXED SERVICES: TELEPHONE



GEN 3.5 METEOROLOGICAL SERVICES

3.5.1 Responsible Service. The meteorological services for civil aviation are temporarily suspended. Civil aircraft are responsible for obtaining limited meteorological information from available commercial services as specified by the operating company or individual. Site specific weather information is available to civil operators from the following website: <http://adds.aviationweather.noaa.gov/>. Military organizations may derive information from the following websites: <https://afwin.afwa.af.mil/> or <https://28ows.shaw.af.mil/>. The appropriate weather station identifier/designator is listed in the relevant AERODROME entry at AD 2.1. Once established, the meteorological service will be provided by the meteorological office section of Baghdad International Airport.

3.5.2 Area of Responsibility. Meteorological Service obtained from United States military sources is provided for the entire Baghdad FIR and may be obtained by those organizations authorized military access to electronic media, those operators with access to the World Wide Web or at airports where limited meteorological services are provided.

3.5.3 Meteorological Observations and Reports. Terminal Area Forecasts will be available to aircraft operators at selected airports, see the relevant AERODROME entry at AD 2.1 for details.

Name of station/ Location indicator	Type / frequency observations / Automatic Observing equipment	Type of reports & supplementary information	Observation system site(s)	Hours of operation	Climatological information
Baghdad Int'l Airport ORBI	Hourly observation	Metar, Speci, TAFS	Complete surface observation equipment	24 Hrs	Climatological Tables AVBL.
Basrah Int'l Airport ORMM	Hourly observation	Metar, Speci, TAFS	Complete surface observation equipment	24 Hrs	Climatological Tables AVBL.

3.5.4 Types of Services: Personal briefing and consultation for flight crews are provided at Baghdad International Airport, Meteorological Briefing Office. Consultation is also available at these offices for flights to other aerodromes. Limited flight documentation is provided for domestic flights. For international flights, the flight documentation comprises a significant weather chart and the latest available aerodrome forecast for the destination and its alternate aerodromes.

3.5.5 Notification Required from Operators. Notification from operators in respect of briefing, consultation, flight documentation and other meteorological information needed (ref. ICAO Annex 3, 2.3) is normally required for intercontinental flights of more than 1900NM. Such consultation should be received at least 6 hours before the estimated time of departure.

3.5.6 Aircraft Reports. Pursuant to ICAO Annex 3, 5.3.1 the making and transmission of aircraft reports (AIREP) are required at the following ATS reporting points:

RAMPI
MURIB
TASMI

Wind sheer within 200 meters above ground is required.

3.5.7 VOLMET Service

Name of station	Callsign or IDENT and emission	FREQ	Broadcast Period	Hours of service	Aerodromes included	Contents and format of report and forecast and remarks
Baghdad Int'l Airport	Baghdad Int'l Airport Volmet Report	126.8MHz	0500 1500	H24	Baghdad Int'l Airport	METAR, TREND

3.5.8 SIGMET service

Name of MWO /location indicators	Hours	FIR or CTA Served	Type of SIGMET/validity	Specific procedures	ATS unit Served	Additional Information
Baghdad Int'l Airport Met Office, ORBI	H24	Baghdad FIR	SIGMET/ 4 HRS	NIL	Baghdad Int'l Airport ATS/ACC	NIL

3.5.9 Other Automated Meteorological Services

Service Name	Information available	Area, route and aerodrome coverage	Telephone, telex and Telefax numbers remarks
Aeronautical Meteorological Division Baghdad Int'l Airport	The prognostic General Aviation Weather Chart (GWC) The European Significant Weather Chart	All of Europe including British Isles, Asia	Tel: TBD
Meteorological Information Self-briefing Terminal (MIST) Obtainable for any flight by the crew	TAF; METAR; Satellite Imagery	Europe; Asia, etc.	Aeronautical Meteorological Division ORBI Int'l Tel:8863999-24368

GEN 3.6 SEARCH AND RESCUE (SAR)

3.6.1 Responsible Authority. The Search and Rescue service in Iraq is, with the exception of the difference given below, organized in accordance with the standards and recommended practices of ICAO Annex 12 by the Iraq Civil Aviation Authority, in collaboration with Defense authorities, which has responsibility for making the necessary facilities available. Postal and Telegraphic addresses of Search and Rescue coordinator are as follows:

Search and Rescue Coordinator
Air Traffic Services
Baghdad International Airport
P.O. Box:
Baghdad, Iraq
Tel:
Telegraphic address: ORBIZQZX
Telex:
Telefax:

3.6.2 Area of responsibility. The Search and Rescue service is responsible for SAR operations for the entire Baghdad FIR.

3.6.3 Types of service

3.6.3.1 Details of the rescue coordination center and related rescue units are given in GEN.

3.6.3.2. Various additional elements of the state police organization, State Civil Service and Armed Forces are available for search and rescue missions when required. The aeronautical, military and public telecommunication services are available to the search and rescue organization. All aircraft carry survival equipment, capable of being air-dropped, consisting of medical supplies, blankets, and emergency rations. Aircraft are equipped for communication on 121.5 MHz.

3.6.4 SAR agreements

3.6.4.1 An agreement is established between the Search and Rescue service of Iraq and the search and rescue services of neighboring Arabian States regarding the provision of assistance upon receipt by the former of letter requesting aid. This agreement provides for facilitation of the overflight and landing of search and rescue aircraft on prior permission and after dispatch of a flight plan (with the exception of the prohibited areas), for similar facilitation of the entry of SAR surface vessels and their operation in border areas, for notification of entry to the authorities controlling entry, for defraying the costs of stop-overs, accommodation and transportation of crew members, and for direct communication between the various SAR services on all common search and rescue matters.

3.6.4.2 Requests for the entry of aircraft, equipment and personnel from other States to engage in search for aircraft in distress or to rescue survivors of aircraft accidents should be transmitted to the Rescue Coordination Center. Instructions as to the control which will be exercised on entry of such aircraft and/or personnel will be given by the Rescue Coordination Center in accordance with a standing plan for the conduct of search and rescue in its area.

3.6.5 Search and rescue facilities and units

RESCUE COORDINATION CENTER(S)				
1.	NAME	Rescue Coordination Center, Air Traffic Service		
a)	Postal Address	Rescue Coordination Center, Directorate of Air Traffic Services, Baghdad International Airport P.O. Box: 23006 Baghdad, Iraq		
b)	Telegraphic address	Aeronautical: AFTN ORBIYCYX Commercial: Baghdad International Airport – Baghdad		
c)	Telephone number:	8134775 – 8134723		
2.	SEARCH AND RESCUE AREA: Baghdad FIR			
3.	RESPONSIBLE AGENCY: Iraq Civil Aviation Authority in collaboration with Defense Authorities			
4	NAME AND LOCATION OF RESCUE SUB-CENTER <u>Remarks:</u> Direct telephone circuits between RCC, RSC and related ATS units.			
5	RESCUE UNITS			
	NAME	LOCATION	FACILITIES	REMARKS
	Baghdad Int'l Airport	At all of the Iraqi Governorates <i>What?</i>	MRG, SRG-HEL	Other military units
	Basrah Int'l Airport			In conjunction with the main Search and Rescue Coordination Center at Baghdad Int'l Airport.

3.6.5.1 Conditions of availability. The SAR service and facilities in Iraq are available without charge to neighboring States upon request to Iraq Civil Aviation Authority at all times when they are not engaged in search and rescue operations in Iraq.

3.6.6 Procedures and/or signals employed by rescue aircraft

3.6.6.1 Procedures. Procedures for pilots-in-command observing an accident or intercepting a distress call/and or message are outlined in Annex 12, chapter 5 to the Convention on International Civil Aviation.

3.6.6.2 Communications

3.6.6.2.1 Transmission and reception of distress message within the Baghdad FIR are handled in accordance with 5.3 chapter 5, volume II of Annex 10 to the Convention on International Civil Aviation.

3.6.6.2.2 For communication during search and rescue operation, use the codes and abbreviations in ICAO codes and abbreviation (Doc 8400).

3.6.6.2.3 Information concerning positions, callsigns, frequencies and hours of operation of Iraqi aeronautical stations and navigation aids is published in GEN 3.4.

3.6.6.2.4 Aeronautical stations will, on request, guard the international emergency frequency 121.5 MHz. All coast stations will guard the international distress frequencies.





3.6.6.2.5 Rescue aircraft belonging to permanent Search and Rescue units use the callsign RESCUE and additional identification marks (ALFA, BRAVO, CHARLE, etc.).

3.6.6.3 Search and rescue signals

3.6.7 The search and rescue signals to be used are those prescribed in ICAO Annex 12, chapter 6, paragraph 5.10. The following table provides common examples:



GROUND-TO-AIR EMERGENCY SIGNALLING CODES

GROUND-TO-AIR VISUAL SIGNAL CODE FOR USE BY SURVIVORS

Nr	Message	Code Symbol	Nr	Message	Code Symbol
1	Require doctor-serious injuries		10	Will attempt take-off	N/A
2	Require medical supplies	N/A	11	Aircraft seriously damaged	N/A
3	Unable to proceed	N/A	12	Probably safe to land here	N/A
4	Require food and water	N/A	13	Require fuel and oil	N/A
5	Require firearms and ammunition	N/A	14	All well	N/A
6	Require map and compass	N/A	15	No	
7	Require signal lamp with battery and radio	N/A	16	Yes	
8	Indicate direction to proceed	N/A	17	Not understood	N/A
9	Proceeding in this direction		18	Require engineer	N/A

Note: Symbols shall be at least 2.5 meters (8 FT) long and shall be made as conspicuous as possible. Any of these code symbols may be used in combination.

**GROUND–TO–AIR VISUAL SIGNAL CODE FOR USE BY GROUND SEARCH
PARTIES**

Nr	Message	Code Symbol	Nr	Message	Code Symbol
1	Operation completed	LLL	5	Have divided into two groups each proceeding in direction indicated	
2	We have found all Personnel	<u>LL</u>	6	Information received that aircraft is in this direction	
3	We have found only some Personnel	++	7	Nothing found, will continue to search	NN
4	We are not able to continue, returning to base	XX			
Note: Symbols shall be at least 2.5 meters (8 FT) long and shall be made as conspicuous as possible. Any of these code symbols may be used in combination.					

GEN 4 FEES AND CHARGES

4.1 AERODROME CHARGES

4.1.1 General. The charges set out hereunder apply to all government aerodromes administrated by the Iraq Civil Aviation Authority. Unless an alternative arrangement has been made, all charges for use of the aerodrome are payable by the pilot of the aircraft before the aircraft departs from the aerodrome. Currently, there are no commercial cargo handling services available at the airports.

4.1.2 Landing fees and charges

4.1.2.1 Landing fees and charges are based on aircraft types grouped according to GEN 4.1.2.2 below. Fees shall be paid to the Department of Accountancy through the ICAA.

4.1.2.2 Fees are structured as follows (all fees are expressed in US dollars):

4.1.2.2.1 C560, Learjet, Jetstream, DH6 will be levied \$350;

4.1.2.2.2 CL60, C750, F50, F27, AN24, ATR42, HS748, HS125, DA90, and YAK40 will be levied \$450;

4.1.2.2.3 G2, G3, G4, G5, BE2, TU124, TU134, F28, CRJ, EM4, CV580, ATR72, and BAC111 will be levied \$500;

4.1.2.2.4 AN8, AN12, B717, B737 (series 100, 200, 500, 600), DC9, IL18, MD82, F70, F100, YAK42 will be levied \$900;

4.1.2.2.5 A320, A321, B727, B737 (series 300, 400, 700, 800), C130, MD83/87/88/90, TU104, TU154 will be levied \$1150;

4.1.2.2.6 B757, TU204 will be levied \$1500;

4.1.2.2.7 B707, C160 will be levied \$1900;

4.1.2.2.8 A310, B767, IL62, IL76, DC8 will be levied \$2200;

4.1.2.2.9 A300, A330, A340, B777, DC10, IL86, IL96, MD11, and L1011 will be levied \$2500;

4.1.2.2.10 AN124, B747 will be levied \$3150.

4.1.3 Fees for additional ground handling. Additional fees for services will be levied as follows:

4.1.3.1 Wheelchair service will be levied at \$35 per wheelchair passenger;

4.1.3.2 Meet and assist service will be levied \$28 per passenger per hour or part thereof;

4.1.3.3 Ground power (100KVA) service will be levied at \$155 per hour of part thereof;

4.1.3.4 Air starter unit service will be levied at \$190 per start cycle per unit;

4.1.3.5 Pushback service will be levied at \$160 per service;

4.1.3.6 Towing service will be levied at \$310 per hour;

4.1.3.7 Air-conditioning unit (106 cooling tons) service will be levied at \$150 per hour or part thereof.

4.1.4 Miscellaneous charges. Charges for security checks, guarding, use of boarding bridges, use of air navigation facilities, electrical lighting and housing have been temporarily suspended until otherwise notified by NOTAM or an amendment to this AIP.

4.1.5 Exemptions/reductions. According to Regulation No. 26 of 1987, the following aircraft are exempt from the levy of the fees and charges:

4.1.5.1 Aircraft belonging to the United Nations and its specialized agencies and the aircraft belonging to the Red Crescent and Red Cross societies.

4.1.5.2 Non-commercial Iraqi government aircraft including aircraft belonging to the Youth Training Organizations.

4.1.5.3 Aircraft belonging to the Arab League and its specialized agencies.

4.1.5.4 Aircraft on official delegations to Iraq provided that the exemption is made either on a reciprocal basis, or by prior approval/recommendation of the Ministry of Foreign Affairs or concerned Iraqi Minister.

4.1.5.5 Aircraft engaged in search and rescue operations free of charge.

4.1.5.6 Aircraft on test flights will be exempted, provided that the relevant air traffic control agency is informed in advance.

4.1.5.7 Aircraft conducting an emergency landing at the aerodrome of departure provided that it will not land thereafter at an aerodrome other than the planned destination aerodrome.

4.1.5.8 Aircraft transporting, free of charge, catering materials for disaster relief and/or humanitarian aid.

4.1.6 Payment of fees and charges. Landing fees and charges will be levied directly to the pilot in command of the aircraft or whoever represents him/her (in the case of airlines with offices in Iraq). Operators without representatives in Iraq must pay all fees and charges prior to departure of each flight. Where operators are invoiced, the payment for charges, services and landing fees should be made within 30 days of the date the fees and charges were incurred. Otherwise, an additional fee for 'delay interest' shall be charged at the rate of 7% of the total invoice per day until the entire debt is paid.

4.2 AIR NAVIGATION SERVICES CHARGES

Aircraft that transit the Baghdad FIR without landing will be levied \$375. All air navigation charges of Iraq will be billed and collected by the International Air Transport Association (IATA) on behalf of the State of Iraq as represented by the MOT. IATA can be contacted via:

International Air Transport Association
Route De L'Aéroport 33
P.O. Box 416
CH-1215 Geneva 15 Airport
Switzerland

AFTN address: LSGGIATA
SITA address: GVALDXB

Commercial Fax:	+41 (22) 770 2654
Commercial Phone (Mr. Bo Bleeg)	+41 (22) 770 2644

Overflight requests must be obtained by contacting the Regional Air Movement Control Center (RAMCC). RAMCC overflight section can be contacted via:

RAMCC Iraq Mobile Phone:	+974 589 2695
Commercial Phone:	+974 (QATAR) 458 9555 Ext 436 2671
Commercial Fax:	+974 (QATAR) 432 7382 Ext 436 2669
DSN Phone:	(318) 436 2671
DSN Fax:	(318) 436 2669
NIPRNET (non-secure e-mail):	ramcc.overfly.iraq@auab.aorcentaf.af.mil
Web address:	http://ramcc.dtic.mil

Approvals are managed by the MoT on behalf of ICAA.

**PART 2
EN- ROUTE (ENR)**

PART 2 – EN-ROUTE (ENR)**ENR 0****ENR 0.1** PREFACE - Not applicable**ENR 0.2** RECORD OF AIP AMENDMENT – Not applicable**ENR 0.3** RECORD OF AIP SUPPLEMENTS – Not applicable**ENR 0.4** CHECKLIST OF AIP – Not applicable**ENR 0.5** LIST OF HAND AMENDMENT TO THE AIP – Not applicable**ENR 0.6 TABLE OF CONTENTS TO PART 2****ENR 1 GENERAL RULES AND PROCEDURES**

	Page
ENR 1.1 General rules	ENR 1.1-1
ENR 1.1.1 Minimum safe height	ENR 1.1-1
ENR 1.1.2 Prohibited areas and flight restrictions	ENR 1.1-1
ENR 1.1.3 Take-offs and landings at other airfields	ENR 1.1-1
ENR 1.1.4 Flight rules – general	ENR 1.1-1
ENR 1.1.5 Terminal areas and non-controlled aerodromes	ENR 1.1-2
ENR 1.1.6 Clearances to operate in class D airspace	ENR 1.1-2
ENR 1.2 Visual flight rules	ENR 1.2-1
ENR 1.2.1 Visual meteorological conditions	ENR 1.2-1
ENR 1.2.2 Altitude and airspace restrictions	ENR 1.2-1
ENR 1.2.3 Air traffic services	ENR 1.2-2
ENR 1.2.4 VFR flights at night	ENR 1.2-2
ENR 1.2.5 Special VFR	ENR 1.2-2
ENR 1.2.6 Change to instrument flight rules	ENR 1.2-3
ENR 1.3 Instrument flight rules	ENR 1.3-1
ENR 1.3.1 IFR departure	ENR 1.3-1
ENR 1.3.2 Rules applicable to all IFR flights	ENR 1.3-1
ENR 1.3.3 Rules applicable to IFR flights in controlled airspace	ENR 1.3-1
ENR 1.3.4 Rules applicable to IFR flights outside controlled airspace	ENR 1.3-1
ENR 1.3.5 Change from IFR flight to VFR flight	ENR 1.3-2
ENR 1.4 ATS airspace classification	ENR 1.4-1
ENR 1.4.1 Description of airspace in Baghdad FIR	ENR 1.4-1
ENR 1.4.2 ATS airspace classes, services provided and flight requirements	ENR 1.4-2
Diagram of Airspace structure within Baghdad FIR	ENR 1.4-3
Diagram of division of responsibility between ATS units	ENR 1.4-4
Diagram of Class E TMA	ENR 1.4-5
ENR 1.5 Holding, approach and departure procedures	ENR 1.5-1
ENR 1.5.1 General	ENR 1.5-1
ENR 1.5.2 Arriving flights	ENR 1.5-1
ENR 1.5.3 Departing flights	ENR 1.5-3
ENR 1.5.4 Signals to aircraft	ENR 1.5-4
ENR 1.6 Radar services and procedures	ENR 1.6-1
ENR 1.6.1 Services and coverage	ENR 1.6-1
ENR 1.6.2 Application of radar control service	ENR 1.6-1
ENR 1.6.3 Radar and radio failure procedures	ENR 1.6-1
ENR 1.6.4 Diagram of radar coverage	ENR 1.6-3
ENR 1.7 Altimeter setting procedures	ENR 1.7-1

ENR 1.7.1	General	ENR 1.7-1
ENR 1.7.2	Provision of Altimeter Setting Information.....	ENR 1.7-1
ENR 1.7.3	Cruising levels within the Baghdad FIR	ENR 1.7-2
ENR 1.8	Regional supplementary procedures (Doc 7030)	ENR 1.8-1
ENR 1.8.1	Overflights	ENR 1.8-1
ENR 1.8.2	Separation	ENR 1.8-1
ENR 1.8.3	International Agreements	ENR 1.8-1
	ENR 1.8.3.1 Agreement with Turkey	ENR 1.8-1
	ENR 1.8.3.2 Agreement with Jordan	ENR 1.8-2
	ENR 1.8.3.3 Agreement with Syria	ENR 1.8-2
	ENR 1.8.3.4 Agreement with Kuwait	ENR 1.8-3
	ENR 1.8.3.5 Agreement with Saudi Arabia	ENR 1.8-4
ENR 1.9	Air traffic flow management (ATFM)	ENR 1.9-1
ENR 1.10	Flight planning	ENR1.10-1
ENR 1.11	Addressing of flight plan messages	ENR1.11-1
ENR 1.12	Interception of civil aircraft	ENR1.12-1
ENR 1.13	Unlawful interference	ENR1.13-1
ENR 1.14	Air traffic incidents	ENR1.14-1

ENR 2 AIR TRAFFIC SERVICES AIRSPACE

ENR 2.1	FIR, TMA	ENR 2.1-1
---------	----------------	-----------

ENR 3 ATS ROUTES

ENR 3.1	Lower ATS routes	ENR 3.1-1
ENR 3.2	Upper ATS routes	ENR 3.2-1
ENR 3.3	Area navigation routes	ENR 3.3-1
	ENR 3.3.1 Rules applicable to air routes in Baghdad FIR	ENR 3.3-1
	ENR 3.3.2 Approved ATS routes entry/exit points for Baghdad FIR	ENR 3.3-5
ENR 3.4	Helicopter routes	ENR 3.4-1
ENR 3.5	Other routes	ENR 3.5-1
	ENR 3.5.1 Mandatory routing	ENR 3.5-1
	ENR 3.5.2 From Kuwait	ENR 3.5-1
	ENR 3.5.3 From Turkey	ENR 3.5-2
	ENR 3.5.4 From Jordan	ENR 3.5-3
	ENR 3.5.5 From Syria	ENR 3.5-4
	ENR 3.5.6 From Iran	ENR 3.5-5
	ENR 3.5.7 From Saudi Arabia	ENR 3.5-5
ENR 3.6	Enroute holding	ENR 3.6-1

ENR 4 RADIO NAVIGATION AIDS/SYSTEMS

ENR 4.1	Radio navigation aids- enroute	ENR 4.1-1
ENR 4.2	Special navigation systems	ENR 4.2-1
ENR 4.3	Name – code designators for significant points	ENR 4.3-1
ENR 4.4	Aeronautical ground lights – enroute	ENR 4.4-1

ENR 5 NAVIGATION WARNINGS

ENR 5.1	Prohibited, restricted and danger areas	ENR 5.1-1
ENR 5.2	Military exercise and training areas and ADIZ	ENR 5.2-1
ENR 5.3	Other activities of a dangerous nature and other potential hazards	ENR 5.3-1
ENR 5.4	Air navigation obstacles – enroute	ENR 5.4-1
ENR 5.5	Aerial sporting and recreational activities	ENR 5.5-1
ENR 5.6	Bird migration and areas with sensitive fauna	ENR 5.6-1

ENR 6 ENROUTE CHART - ICAO

ENR 1 GENERAL RULES AND PROCEDURES

ENR 1.1 GENERAL RULES

The rules and procedures applicable to air traffic control in the Baghdad FIR conform to Annexes 2 and 11 to the Convention on International Civil Aviation and to those portions of the ICAO Doc 4444 Procedures for Air Navigation Services – Rules of the Air and Air Traffic Services applicable to aircraft and of the Letters of Agreement.

1.1.1 Minimum safe height

1.1.1.1 Civilian aircraft shall not be flown below the minimum safe height except when necessary for take-off and landing. The minimum safe height is the height at which neither an unnecessary noise disturbance nor unnecessary hazards to persons and property in the event of an emergency landing are to be feared. However, over cities, other densely populated areas and assemblies of persons, this height shall be at least 1000FT (300 M) above the highest obstacle within a radius of 600 m of the aircraft. Elsewhere, this height shall be at least 500 FT (150 M) above ground or water.

1.1.1.2 Gliders and balloons may be operated below a height of 500FT (150 M) if necessary for the kind of operation and if danger to persons and property is not to be feared. Aircraft shall not be flown below bridges and similar constructions nor below overhead lines and antennas. For flights conducted for special purposes, the local aeronautical authority may grant exemptions.

1.1.2 **Prohibited areas and flight restrictions.** All Iraqi airspace (except ATS routes and Terminal Control Areas) is prohibited for civilian aircraft use. Aircraft are advised to strictly adhere to the route centerline. Failure to comply with the procedures in this AIP may result in interception by armed coalition fighter aircraft.

1.1.3 **Take-offs and landings at other airfields.** HA/NGO flights may land at and depart from the airfields listed at GEN 1.2.1.16, subject to approval by MoT. Flights other than HA/NGO require additional approval from the Iraq Civil Aviation Authority for all aircraft operations to and from aerodromes other than Baghdad and Basrah.

1.1.4 Flight rules - general

1.1.4.1 Within Class A airspace all civil aircraft must operate in accordance with Instrument Flight Rules (IFR) and be in two-way communication with the appropriate air traffic service unit at all times.

1.1.4.2 Civilian aircraft must plan to and operate IFR within the Baghdad FIR. Civil aircraft, below 12,000FT AMSL and in VMC, are to operate VFR. Civil aircraft must notify ATC if unable to operate VFR, i.e. VMC does not exist, when below 12,000FT using the phrase “UNABLE VFR”. The use of VFR in this manner does not negate the requirement for aircraft to carry IFR fuel reserves.

1.1.4.3 Except as specified above, in airspace where VFR operations are approved, flights should be carried out in accordance with VFR as specified in ICAO Annexes 2 and 11. Compliance with these procedures does not relieve pilots of their responsibility to see and

avoid other aircraft, or to maintain safe terrain/obstacle clearance at all times when operating VFR.

1.1.4.4 Civil aircraft are advised that military aircraft may cross and/or temporarily enter Class A airspace air routes, with an ATC clearance to do so, but may not monitor the appropriate ACC frequencies.

1.1.4.5 Restrictions to civil aircraft operations.

1.1.4.5.1 Civil aircraft are approved to operate 24 hours a day at both Erbil and Sulaymaniyah International Airports.

1.1.4.5.2 **Baghdad International Airport.** With the Senior Airfield Authority's approval, civil aircraft may operate at Baghdad International Airport between morning civil twilight and evening civil twilight. With the Senior Airfield Authority's approval and subject to local conditions, civil aircraft departures may be authorized between evening civil twilight and morning civil twilight. Requests for such approval must be made at least 1 hour in advance. Official civil twilight times are listed at GEN 2.7.

1.1.4.5.3 Civil flights are not authorized to depart from or land at any airfield (with the exception of those stated in ENR 1.1.4.5.1 and 2) in Iraq during the period from sunset to sunrise. Requests for planned exceptions are to be submitted to the RAMCC for coordination with ICAA.

1.1.5 Terminal areas and non-controlled aerodromes

1.1.5.1 Radio contact with ATC on the designated frequency is mandatory within terminal airspace. If unable to maintain contact with Approach Control, or in case of communications failure, arrivals shall attempt to contact Tower prior to entering Class D airspace. For departures, ATC should be contacted on start-up, but no later than 10 minutes before ETD. Departing aircraft shall squawk the appropriate Mode 3/A prior to departure. For airports without an approach control service, contact relevant ACC as soon as possible.

1.1.5.2 Erbil International Airport (ORER) is a non-controlled aerodrome. 24 hour civil aircraft operations are authorized. Customs and Immigration are now available for approved operators only. All operators are to check current NOTAMs for updated procedures and/or contact the Airfield Manager listed at AIP ORER AD 2.3 OPERATIONAL HOURS.

1.1.5.3 Sulaymaniyah International Airport (ORSU) is a non-controlled aerodrome. 24 hour civil aircraft operations are authorized. Customs and Immigration are now available for approved operators only. All operators are to check current NOTAMs for updated procedures and/or contact the Airfield Manager listed at AIP ORSU AD 2.3 OPERATIONAL HOURS.

1.1.6 Clearances to operate in Class D. For communications brevity and security, aircraft operating in the Class D control zones need not be issued an Air Traffic Control Clearance containing an airborne clearance limit or route of flight. Instead, aircraft shall advise the applicable tower of their preferred tracking details. Tower shall issue amended tracking and/or level instructions if required for sequencing and/or separation within Class D. The absence of amended tracking or level instructions will be an implied clearance to operate in Class D as requested. Aircraft shall advise the tower prior to deviating from the tracking details advised to, or assigned by, the tower.

ENR 1.2 VISUAL FLIGHT RULES**1.2.1 Visual Meteorological Conditions**

1.2.1.1 Limitations of weather service preclude civil VFR flight plans or flights conducted entirely in VMC. Pilots must be qualified and capable of conducting flight under IFR. Except when operating as a special VFR flight in Class D airspace, VFR flights within Terminal Control Areas shall be conducted so that the aircraft is flown in conditions of visibility and distance from cloud equal to or greater than those specified in the following table:

Airspace Classification			
	A*, D, E	G	
		Above 3000 FT AMSL or 1000FT AGL whichever is higher	At and below 3 000 FT or 1000FT AGL whichever is higher
Distance from cloud	1500M horizontal 500FT vertical		Clear of cloud and in sight of ground or water
Visibility	8 km above 10000FT AMSL 5 km at and below 10000FT AMSL		5 km

** VFR flight not permitted in Class A airspace.*

1.2.1.2 Except when a clearance for Special VFR flight is obtained from an air traffic control unit, VFR flights shall not take off or land at an aerodrome within a control zone, or enter the aerodrome traffic zone or traffic pattern:

1.2.1.2.1 When the cloud ceiling is less than 3000 FT (900 M); or

1.2.1.2.2 When the ground visibility is less than 5 KM.

1.2.1.2.3 At night, if a civil aircraft.

1.2.2 Altitude and airspace restrictions

1.2.2.1 Unless authorized by the appropriate ATS authority, VFR flights shall not be operated:

1.2.2.1.1 Within Class A airspace;

1.2.2.1.2 At transonic and supersonic speeds.

1.2.2.2 Except when necessary for take-off or landing, or by permission from the appropriate authority, a VFR flight shall not be flown:

1.2.2.2.1 Over the congested areas of cities, towns or settlements or over an open-air assembly of persons at a height less than 1,000FT (300 M) above the highest obstacle with in a radius of 600 M of the aircraft;

1.2.2.2.2 Elsewhere, at a height less than 500FT (150 M) above the ground or water.

1.2.2.3 Except when otherwise instructed in air traffic control clearances VFR flights in level cruising flight when operated above 3,000FT (900 M) from the ground or water shall be conducted at a flight level appropriate to the track as specified in the Tables of Cruising Levels in Appendix 3 to Annex 2 to the Convention on International Civil Aviation.

1.2.3 Air Traffic Services

1.2.3.1 VFR flights shall comply with the provisions of air traffic control instructions:

1.2.3.1.1 When operated within Class D airspace;

1.2.3.1.2 When forming part of aerodrome traffic at controlled aerodromes; or

1.2.3.1.3 When operated as Special VFR flights.

1.2.3.2 A VFR flight operating within or into designated controlled airspace, shall maintain continuous air-ground voice communication watch on the appropriate communication channel of, and report its position as necessary to, the air traffic services unit providing air traffic services.

1.2.3.3 In accordance with Annex 11 to the Convention on International Civil Aviation, VFR flights transiting Class E or G airspace are not compelled to maintain continuous communications with the air traffic services unit.

1.2.3.4 Instrument flight rules flights arriving at Baghdad and Basrah International Airports that have notified the air traffic services unit “*callsign* VISUAL, CANCEL IFR” in accordance with ENR 1.3.5, shall maintain continuous air-ground voice communication watch on the appropriate channels, throughout the flight.

1.2.4 VFR flights at night. In addition to previously stated rules for VFR, VFR flights at night must be conducted at or above an altitude that ensures at least 1,000FT (300 M) vertical clearance above the highest obstacle with 10 NM either side of the aircraft’s track, except:

1.2.4.1 During takeoff and landing;

1.2.4.2 When operating in the immediate vicinity of the departure or destination aerodrome while climbing to or descending from the minimum safe altitude; and

1.2.4.3 For military operations requesting low level VFR flight at night.

1.2.5 Special VFR. At pilot request, when visual meteorological conditions do not exist, ATC may issue a clearance for special VFR flights to enter a control zone for the purpose of landing, take off and departure from a control zone, to cross a control zone, or to operate locally within a control zone, provided:

1.2.5.1 The special VFR flight will not unduly delay an IFR flight;

1.2.5.2 Special VFR flight remains clear of cloud;

1.2.5.3 In-flight visibility:

a. For all aircraft is not less than 1,500 M, and

- b. Military Rotary Wing aircraft may operate with a flight and ground visibility less than 1,500 M with strict adherence to para 1.2.5.4 and 1.2.5.5.

1.2.5.4 The Special VFR flight is operated at speeds that, in the prevailing visibility, will give adequate opportunity to observe other traffic or any obstacles in time to avoid collision.

1.2.5.5 When operating Special VFR, it is the responsibility of the aircraft captain to ensure the safety of the aircraft and its occupants are not jeopardized under any circumstances. If any doubt exists, the Special VFR flight will not be undertaken.

1.2.5.6 In accordance with ICAO Doc 4444 PANS ATM Chapter 5 paragraph 5.2.1, IFR aircraft shall be separated from Special VFR aircraft, using the separation standards prescribed in Chapters 5 and 6. Radar separation may be applied between IFR and Special VFR aircraft, however, Special VFR flights shall not be radar vectored unless special circumstances, such as emergencies, dictate otherwise. Special VFR aircraft shall receive traffic information on other Special VFR aircraft in Class D airspace and, unless it is impracticable, a suggested course of avoiding action. If practicable and requested by the pilot, Special VFR may be separated from other Special VFR aircraft by the application of the standards described in ICAO Doc 4444 PANS ATM Chapter 5 and 6.

Note: Special VFR at night should only be requested by aircraft on operationally critical flights.

1.2.6 Change to instrument flight rules

1.2.6.1 An aircraft operated in accordance with the visual flight rules that wishes to change to compliance with the instrument flight rules shall:

1.2.6.1.1 If a flight plan was submitted, communicate the necessary changes to be effected to its current flight plan, or

1.2.6.1.2 Submit a flight plan to the appropriate air traffic services unit and obtain a clearance prior to proceeding IFR when in controlled airspace.

1.2.6.2 Aircraft departing satellite airports are VFR and will remain VFR until air traffic control assigns an altitude. If air traffic control is unable to issue an altitude immediately, the controller will advise the pilot when or where to expect altitude assignment.

ENR 1.3 INSTRUMENT FLIGHT RULES (IFR)

1.3.1 IFR departure: Traffic departing Baghdad and Basrah aerodromes for air route flights shall follow the normal Standard Instrument Departure (SID) procedure or, otherwise, follow ATC instructions.

1.3.2 Rules applicable to all IFR flights

1.3.2.1 All civil aircraft operating in the Baghdad FIR shall operate IFR in Class A airspace. Aircraft shall be equipped with suitable instruments and navigation equipment appropriate to the route to be flown. Aircraft intending to operate on Iraq's air routes shall be suitably equipped to comply with RNP5 as detailed at GEN 1.5.2.

1.3.2.2 Except when necessary for take-off or landing, or when specifically authorized by the appropriate authority, an IFR flight shall be flown at or above the minimum flight altitude established by the state whose territory is overflown, or, where no such minimum flight altitude is established:

1.3.2.2.1 Over high terrain or in mountainous areas, at a level which is at least 2,000FT (600 M) above the highest obstacle located within 5NM of the estimated position of the aircraft; otherwise,

1.3.2.2.2 At a level which is at least 1,000FT (300 M) above the highest obstacle located within 5NM of the estimated position of the aircraft.

1.3.2.3 An IFR flight operating in cruising flight shall be flown at a cruising level, or, if authorized to employ cruise climb techniques, between two levels or above a level, selected from the Table of Cruising Levels in Appendix C to Annex 2 to the Convention on International Civil Aviation. However, IFR flights may cruise at a level other than that described in the table of cruising levels, when otherwise instructed by air traffic control or when operating outside controlled airspace and cruising at or below 3,000FT (900 M) AMSL.

1.3.2.4 An IFR flight shall report, to the appropriate air traffic services unit, as soon as possible, the time and level of passing each designated compulsory reporting point. Position reports shall similarly be made in relation to additional points when requested by the appropriate air traffic services unit.

1.3.3 Rules applicable to IFR flights in controlled airspace. IFR flights shall comply with the provision of sub-section 3.6 of Annex 2 to the Convention of International Civil Aviation when operated in controlled airspace. This refers to the requirements for flights to submit and adhere to a flight plan, to comply with air traffic control instructions, and to maintain listening watch on the appropriate radio frequency.

1.3.4 Rules applicable to IFR flights outside controlled airspace. IFR flights operating outside controlled airspace within the Baghdad FIR shall maintain a listening watch on the appropriate radio frequency and establish two-way communication, as necessary, with the air traffic services unit providing flight information service.

1.3.5 Change from IFR flight to VFR flight

1.3.5.1 An aircraft electing to change the conduct of its flight from compliance with the instrument flight rules to compliance with the visual flight rules shall notify the appropriate air traffic services unit specifically that the IFR flight is cancelled and communicate thereto the changes to be made to its current flight plan.

1.3.5.2 When an aircraft that is operating under the instrument flight rules and arriving at Baghdad or Basrah encounters visual meteorological conditions, it shall cancel its IFR flight provided it is anticipated, and intended, that the remainder of the flight to the destination aerodrome will be conducted in uninterrupted visual meteorological conditions. In this case, the pilot shall report to the appropriate air traffic service agency “*callsign* VISUAL, CANCEL IFR”. Air traffic service agencies shall not approve such cancellation of IFR above FL290 (Class A airspace).

1.3.5.3 Military aircraft that are IFR and established on the airway or established within Class E airspace and are requesting to land at airports that are outside of these areas shall, if applicable, advise air traffic control when able to proceed tactical. Air traffic control shall acknowledge and terminate radar services. Aircraft that are tactical shall cancel IFR and comply with applicable military directives. Aircraft that cannot proceed tactical will not be descended below the airway’s minimum enroute altitude or be permitted to exit the ATS route or Class E airspace.

ENR 1.4 ATS AIRSPACE CLASSIFICATION

1.4.1 Description of airspace in Baghdad FIR

1.4.1.1 The Baghdad FIR is classified into Class A, D, E and G airspace. Class B, C and F airspace are not used in the Baghdad FIR. A diagram of the airspace structure is at ENR 1.4-3. Air traffic services are provided in all controlled airspace, by the controlling ATC facility, or MRU where authorized, based on non-radar procedures supplemented by radar where possible. A diagram of the divisions of responsibility between ATC facilities is at ENR 1.4-4.

1.4.1.2 **Class A** airspace in the Baghdad FIR is established from FL290 – FL460 over the established air route structure in Iraq. Refer to ENR 3.3 and current ORBB NOTAMs for updated airspace information.

1.4.1.3 **Class D** airspace is established in conjunction with airports that have operating control towers. Class D airspace is a normally a 5NM radius from the aerodrome reference point (ARP), from SFC to 3,000FT AMSL (4,000FT AMSL at Kirkuk and Mosul). The Class D airspace surrounding Baghdad International has been tailored to meet current military security requirements. For a full description refer AIP ENR 2.1-4

1.4.1.4 **Class E** airspace is established at Al Asad, Al Taqaddum, Baghdad International, Balad SE, Basrah International, Kirkuk, Mosul, and Ali Base TMA's. Refer to ENR 2.1-3.

1.4.1.5 **Class G** airspace is established for all areas that are not classified as A, D or E. This airspace is primarily used by military VFR aircraft. A Common Traffic Advisory Frequency (CTAF) is established for aircraft self deconfliction. Aircraft operating in Class G airspace should broadcast intentions on CTAF VHF 122.0.


1.4.2 ATS airspace classes, services provided and flight requirements

Class	Type Of Flight	Separation Provided	Service Provided	Radio Comm Requirement	Subject to ATC Clearance
A	CIV IFR only & MIL aircraft using ATS air routes	Between all aircraft	ATC	Continuous two-way	Yes
B	Not applicable in Baghdad FIR				
C	Not applicable in Baghdad FIR				
D	IFR	IFR/IFR IFR/Special VFR	ATC service, traffic information about VFR flights (and traffic avoidance advice on request)	Continuous two-way	Yes
	VFR	Nil	IFR/VFR, VFR/VFR and Special VFR/Special VFR traffic information	Continuous two-way	Yes

			(traffic avoidance advice on request)		
E	IFR	IFR/IFR	ATC service and, as far as practicable traffic information about VFR flights.	Continuous two-way	Yes
	VFR	Nil	Nil	No*	No
F	Not applicable in Baghdad FIR				
G	IFR	Nil	Flight information service	No	No
	VFR	Nil	Flight information service	No	No

* VFR arrivals and departures must remain in two-way communications with ATC whilst in Class E.


**DEPICTION OF AIRSPACE STRUCTURE WITHIN
BAGHDAD FIR**



Refer to AIP ENR 1.4.1, ENAME charts L15-18 and H13 and current Baghdad FIR NOTAMs for actual airspace descriptions.

Note: Due to equipment limitations, two-way communications may not be available in western Iraq. In the event of an emergency requiring descent in an area of poor radio coverage, pilots are to attempt to contact any air traffic agency via emergency frequencies

DIVISION OF RESPONSIBILITY BETWEEN ATS UNITS AND CLASS E TMA



ENR 1.5 HOLDING, APPROACH AND DEPARTURE PROCEDURES

1.5.1 General

1.5.1.1 The holding, approach and departure procedures at Baghdad are based on those contained in United States Terminal Instrument Procedures (TERPS). The holding, approach and departure procedures at Basrah are based on those contained in NATO – APATC-1.

1.5.1.2 The holding and approach procedures at other aerodromes in the Baghdad FIR have been based on Part III and IV of Vol. 1 of the PANS-OPS. The holding patterns shall be entered and flown as indicated below.

1.5.1.3 If necessary, such as, in case of congestion, inbound aircraft may be instructed to hold at one of the designated enroute reporting points. Additional holding points may be specified by ATC depending on traffic density and conditions. The holding procedures shall be a standard 180 degree right turn to fly outbound on the reciprocal track for one minute then conduct a standard 180 degree right turn to intercept the inbound track to overhead the holding point. ICAO Doc 8168-PAN-OPS refers.

1.5.1.4 Due to limited airspace available, it is imperative that the approaches to the holding patterns and procedures are carried out as exactly as possible. Pilots should inform ATC if the approach and/or holding procedures cannot be performed as required.

1.5.2 Arriving Flights

1.5.2.1 IFR flights entering and landing within a terminal control area shall be cleared to the specified holding point and instructed to contact approach control at a specified time, level or position. The terms of this clearance shall be adhered to until further instructions are received from approach control. If the clearance limit is reached before further instructions have been received, holding procedures shall be carried out at the level last authorized. Holding is unnecessary provided the aircraft is in receipt of onwards clearance.

1.5.2.2 Standard Instrument Arrival Routes (STAR) are established to link the significant enroute waypoints with a point from which a published instrument approach procedure can be commenced. STAR are established for Baghdad and Basrah. Arriving aircraft should normally be cleared via the appropriate STAR. Each STAR indicates by its name, the entry waypoint from the terminal area and, by its number, the RWY in use. The STAR will normally be passed to aircraft in the form of code as specified on the instrument approach/departure plate. On occasion, when ATC finds it necessary to issue clearances that do not conform with the STAR, the amended clearance/instruction shall be prefixed by the phrase "CANCEL STAR". When considered necessary by ATC, when requested by the pilot-in-command, the STAR will be decoded and described in full.

1.5.2.3 To avoid conflict with military air traffic, no maneuvers involving flight to the east of the circuit of Baghdad International Aerodrome, should be made unless specifically cleared by ATC units.

1.5.2.4 Except when complying with the requirements for a visual approach, when conforming to a published GPS arrival procedure, or when under radar control, an IFR aircraft approaching an aerodrome must not descend below the LSALT or the MSA for the route segment being flown until it has arrived over the IAF or facility.

1.5.2.5 25 NM and 10 NM MSA provide at least 1,000FT obstacle clearance. In instances where the 25 NM MSA has been divided into sectors, and the appropriate Sector MSA is lower than the 10 NM MSA, the Sector MSA may be used for tracking to the aid provided aircraft tracking can be maintained within the sector.

1.5.2.6 Visual approach

1.5.2.6.1 An arriving flight may be cleared by ATC to execute a visual approach provided:

1.5.2.6.1.1 The aircraft is within 30 NM of the destination aerodrome; and

1.5.2.6.1.2 The pilot has established, and can continue flight to the aerodrome with, continuous visual reference to the ground or water; and

1.5.2.6.1.3 At night, the pilot reports the aerodrome in sight; and

1.5.2.6.1.4 Visual meteorological conditions exist at the destination aerodrome; or

1.5.2.6.1.5 The pilot reports at the initial approach level or at any time during the instrument approach procedure that the meteorological conditions are such that a visual approach and landing can be completed.

1.5.2.6.2 Unless otherwise instructed by ATC, aircraft cleared to execute a visual approach shall maintain the assigned track until within five nautical miles of the destination aerodrome, or by night within the prescribed circling area, and then maneuver via the shortest route to base or final for the assigned RWY.

1.5.2.6.3 An aircraft executing a visual approach may descend when ready from its previously assigned level and must remain at least 500FT above the base of the control area and, by day, shall comply with ENR 1.2.2 regarding altitude restrictions above terrain and built up areas. An aircraft executing a visual approach at night shall comply with these instructions and maintain the last assigned altitude or minimum safe altitude if lower, until established within the circling area, then remain within the circling area and maneuver via the shortest route to base or final for the assigned RWY.

1.5.2.6.4 At night, international HEAVY wake turbulence category aircraft shall be processed via a straight-in instrument approach, such as ILS or VOR/DME approach. When a straight-in instrument approach is not available or is unsuitable in prevailing conditions, international HEAVY aircraft are to conduct a straight-in visual approach via 10 NM final.

1.5.2.6.5 Separation shall be provided between IFR aircraft cleared to execute a visual approach and other IFR aircraft.

1.5.2.6.6 For successive visual approaches by IFR aircraft, radar or non-radar separation shall be maintained until the pilot of a succeeding aircraft reports having the preceding aircraft in sight. The aircraft shall then be instructed to follow and maintain own separation from the preceding aircraft. When both aircraft are of a heavy wake turbulence category, or the preceding aircraft is of a heavier wake turbulence category than the following, and the distance between the aircraft is less than the appropriate wake turbulence minimum, the controller shall issue a caution of possible wake turbulence. The pilot-in-command of the aircraft concerned shall be responsible for ensuring that the spacing from a preceding aircraft

of a heavier wake turbulence category is acceptable. If it is determined that additional spacing is required, the flight crew shall inform the ATC unit accordingly, stating their requirements.

1.5.3 Departing Flights

1.5.3.1 IFR flights departing from controlled aerodromes shall receive initial ATC clearance from the local aerodrome control tower. The clearance limit will normally be the aerodrome of destination. IFR flights departing from non-controlled aerodromes must make arrangements with the area control center concerned prior to take-off.

1.5.3.2 Detailed instructions with regard to routes, turns, etc. will be issued after take-off as required.

1.5.3.3 Standard Instrument Departure (SID) Routes

1.5.3.3.1 SID routes will normally be issued in the form of a code, as detailed on the instrument departure plates, for aircraft departing from Baghdad and/or Basrah International Airports. When ATC it is necessary to issue clearances that do not conform to these standard routes, the clearances will be prefixed by the phrase "CANCEL SID". ATC shall not cancel a SID whilst the aircraft is below minimum safe altitude except, by day in visual meteorological conditions, when the aircraft is instructed to maintain visual terrain clearance by ATC appending "VISUAL" to the track/level instruction.

1.5.3.3.2 When considered necessary by ATC or when requested by the pilot-in-command the SID will be decoded and described in full.

1.5.3.3.3 Each SID indicates by its name the waypoint via which the aircraft will exit the terminal area.

1.5.3.3.4 Each SID route will be supplemented by an altitude or flight level instruction. Such altitude instructions shall not restrict an aircraft to a level below the minimum safe altitude. In that case, the SID should be cancelled and the aircraft shall be instructed to "REMAIN VISUAL UNTIL ABOVE MSA".

1.5.3.3.5 To avoid confliction with military air traffic, no maneuvers involving flight to the east of the circuit of Baghdad International Aerodrome should be made unless specifically cleared by ATC units.

1.5.4 Signals to aircraft. ATC light signals to aircraft have the following meaning and pilots of aircraft observing such light signals shall take action accordingly:

SIGNALS	MEANING	
	To Aircraft in Flight	To Aircraft on the Ground
Steady Green	Cleared to land	Cleared for take-off
Steady Red	Give way to other aircraft continue circling	Stop
Series of Green Flashes	Return for landing	Cleared to Taxi
Series of Red Flashes	Aerodrome unsafe do not land	Taxi clear of landing area in use
Series of White Flashes	Land at this aerodrome and proceed to apron	Return to starting point on aerodrome
Red Pyrotechnic	Notwithstanding any previous instructions DO NOT LAND for the time being	<i>Nil meaning</i>

ENR 1.6 RADAR SERVICES AND PROCEDURES

1.6.1 Services and coverage. Air traffic control radar units operate as integral part of the system and provide Radar Control Services for the Baghdad FIR using combined primary and secondary surveillance radar. However, due to gaps in radar coverage, particularly near the boundaries of the Baghdad FIR, air traffic control applies non-radar separation standards, supplemented by radar, to enroute aircraft. The diagram on ENR 1.6-3 depicts approximate radar coverage and the division of responsibility between air traffic control units in Iraq. Pilots are to continuously monitor the VHF emergency frequency (121.5 MHz) and operate their transponder at all times during flight, ensuring that the transponder is set on the correct discrete code assigned by Regional Air Movement Control Center. Failure to operate transponder correctly may result in interception by armed coalition fighter aircraft.

1.6.2 Application of radar control service

1.6.2.1 Radar is used for the provision of Air Traffic Services in accordance with ICAO Doc 4444 – Procedures for Air Navigation Services- Air Traffic Management, Chapter 8.

1.6.2.2 An aircraft may consider that ATC is providing a radar control service from the time ATC advises the aircraft that radar identification is established until the time when ATC advises the aircraft that identification is lost and or that radar service is terminated. Unless otherwise requested by ATC, aircraft position reporting may be omitted when receiving a radar control service.

1.6.2.3 Radar services provided by Area Control Center (ACC) or Radar Control are limited to traffic advisories, safety alerts and assisting controllers maintain the prescribed procedural horizontal and vertical separation minimums.

1.6.2.4 The minimum horizontal radar separation standard within the Baghdad FIR, prescribed for use at locations where radar services are provided is 5 NM.

1.6.2.5 Levels assigned by the radar controller shall ensure terrain clearance in accordance with minimum vector altitude, minimum safe altitude or lowest safe altitude, as appropriate to the phase of flight.

1.6.2.6 By day, in visual meteorological conditions, aircraft may be instructed to maintain terrain clearance visually, by appending the word “VISUAL” to heading or level instructions that are applicable for that portion of flight below Minimum Vector Altitude, Minimum Safe Altitude or Lowest Safe Altitude, as applicable.

1.6.3 Radar and radio failure procedures

1.6.3.1 In the event of radar failure, the radar controller shall take all steps necessary to ensure terrain clearance and establish non-radar separation standards as soon as possible. Aircraft subject to radar control services shall be advised of a radar failure as soon as possible.

1.6.3.2 If two-way communication is lost with an aircraft, the radar controller shall attempt to determine whether or not the aircraft’s receiver is functioning by:

1.6.3.2.1 instructing the aircraft to “SQUAWK IDENT” or change transponder mode/code; or

1.6.3.2.2 instructing the aircraft to acknowledge by executing a turn or series of turns and by observing the movements of the aircraft's radar track.

1.6.3.3 If the action prescribed in paragraph ENR 1.6.1.3.2 is unsuccessful, air traffic control shall attempt to contact the aircraft in the same manner on alternative frequencies and, when available, on voice monitored navigation aids.


1.6.3.4 Air traffic control shall ensure such instructions maintain terrain clearance, do not inadvertently carry the aircraft beyond radar coverage and are such that the aircraft can regain its cleared track after having complied with the instructions. Radar separation may continue to be applied provided radar identification is maintained.

1.6.3.5 Pilots shall continue to attempt to acknowledge instructions and broadcast intentions on normal air-ground radio frequencies.

1.6.3.6 **Complete Aircraft Communication Failure.** Aircraft experiencing radio failure in the departure phase within the terminal area will climb to the level specified in the clearance, or to the minimum safe altitude, whichever is higher. If no time or geographical limit was included in the clearance, maintain assigned level for three minutes then continue climb to the flight level specified in the current flight plan. If assigned a radar heading, maintain the vector for two minutes, and then proceed in accordance with the latest ATC route clearance received and acknowledged. Continue to make routine reports.

1.6.3.7 When a controlled aircraft experiencing complete communication failure is operating or expected to operate in an area and at flight levels where radar separation is applied, such separation may continue to be used. However if the aircraft experiencing radio failure is not identified, radar separation shall be applied between aircraft under radar control and the non-radar navigation tolerances of the unidentified radio fail aircraft.

1.6.4 Graphic portrayal of radar coverage. Aircraft will be advised "RADAR CONTACT" when operating in areas where sufficient radar capabilities are available. The level of services shall be in accordance with the AIP. Radar coverage in Iraq is presently provided using deployable United States military and Royal Air Force radars. These facilities exceed typical Iraqi radar coverage, but may be relocated/removed on short notice. Consequently, pilots-in-command are responsible for reviewing applicable NOTAM information on the availability of radar.



ENR 1.7 ALTIMETER SETTING PROCEDURES

1.7.1 General

1.7.1.1 The altimeter setting procedures in use generally conform to those contained in ICAO Doc 8168-OPS/611 and are given in full below. Transition altitude for all aerodromes in the Baghdad FIR is described below and detailed in the tabulation in AD 2. In addition, transition altitudes are given on instrument approach charts.

1.7.1.2 QNH reports for use in determining adequate terrain clearance is provided in meteorological broadcasts and is available on request from air traffic service units. QNH values are given in whole Hectopascals (fractions are rounded down) or, on request, in inches of mercury.

1.7.1.3 The following standard definitions shall apply in the Baghdad FIR:

1.7.1.3.1 **Transition Altitude.** The altitude at or below which the vertical position of an aircraft is controlled by reference to altitudes. The transition altitude for Baghdad FIR is 13,000FT AMSL.

1.7.1.3.2 **Transition Layer.** The airspace between the transition altitude and the transition level.

1.7.1.3.3 **Transition Level.** The lowest flight level available for use above the transition altitude. The transition level for Baghdad FIR is established at FL150.

1.7.1.4 The altimeter pressure setting at and above the transition level is the international standard altimeter pressure setting of 1013 Hectopascals or 29.92 inches. The altimeter setting at and below the transition altitude shall be the relevant QNH.

1.7.1.5 Vertical positioning of aircraft at or below the transition altitude is expressed in terms of altitude, whereas levels at or above the transition level are expressed in terms of flight levels. While passing through the transition layer, vertical position shall be expressed in terms of flight levels when climbing and in terms of altitudes when descending. Aircraft shall not cruise within the transition layer.

1.7.2 Provision of Altimeter Setting Information

1.7.2.1 ATC units shall have current QNH available for transmission to aircraft on request, both for their own and adjacent areas of responsibility. For arriving and enroute aircraft, the QNH altimeter setting shall be included in the first assignment of an altitude below the transition level. Unless the aircraft notifies receipt of the ATIS or the QNH is passed as part of a previous transmission, QNH shall be appended to the airways clearance for aircraft intending to cruise below the transition level, approach clearances or clearances to enter the traffic pattern, and with the taxi clearance for departing aircraft. ATC shall advise aircraft of subsequent QNH changes.

1.7.2.2 Pressure settings for military aircraft can be obtained from the following website:
<https://weather.afwa.af.mil/>

1.7.3 Cruising levels within the Baghdad FIR. Selected flight levels shall be compatible with Appendix 3 Annex 2 to the Convention on International Civil Aviation, Table of Cruising Levels and comply with the cruising levels specified in ENR 1.8.

ENR 1.8 REGIONAL SUPPLEMENTARY PROCEDURES

1.8.1 Overflights. Only civil operators and state flights formally approved by the MoT are authorized to overfly Iraqi airspace. The Overflight Request Form can be found on the RAMCC web site at <http://ramcc.dtic.mil>. Overflights of Iraq must be conducted above FL200, except for flights departing from adjacent countries whose climb performance will not permit operation above FL200 prior to entering the Baghdad FIR, subject to the approval of and in accordance with the conditions established in this AIP. Iraq's airway structure is described in ENR 3.3.

1.8.2 Separation. Minimum non-radar longitudinal separation between overflight aircraft operating on the same route and at the same altitude is 15 minutes. If simultaneous aircraft wish to enter the Baghdad FIR at the same flight level, ATC shall assign each aircraft a time to cross the appropriate boundary point, based on the 15 minute separation standard. At the discretion of the air traffic controller, minimum non-radar longitudinal separation between overflight aircraft may be reduced to no closer than 10 minutes if applying the Mach Number Technique. ATC retains the right to increase spacing, on an individual or temporary basis, should circumstances warrant.

1.8.3 International Agreements. There are five Letters of Agreement (LOAs) finalized between Iraq and adjacent countries – Turkey, Jordan, Syria, Kuwait, and Saudi Arabia. These LOAs authorize Regional Air Movement Control Center or Iraq Civil Aviation Authority approved aircraft to travel between said countries (through the Baghdad FIR) in accordance with agreed procedures. The pertinent points from each LOA are detailed in ENR 1.8.3.1 to ENR 1.8.3.5.

Note: Baghdad FIR is not approved for RVSM. All LOA flight levels stipulated below will be assigned by ATC to provide a minimum of 2,000FT vertical separation between aircraft operating above FL290 unless horizontal separation is established.

1.8.3.1 Agreement with Turkey

1.8.3.1.1 R784 is the only entry/exit route for aircraft between the Ankara and Baghdad FIRs.

1.8.3.1.2 All aircraft transitioning on routes that cross the Ankara/Baghdad FIR boundary shall be in level flight, at the assigned flight level, prior to KATOT for northbound flights and SIIRT for southbound flights. Altitude changes should not be anticipated between these points and the Ankara/Baghdad FIR boundary (KABAN).

1.8.3.1.3 Aircraft entering the Baghdad FIR southbound shall be in level flight at the assigned flight level prior to SIIRT at one of the following levels:

FL230, FL250, FL270, FL330, FL370, FL410

Note: FL150, FL170 and FL190 are only to be used by coalition military aircraft.

1.8.3.1.4 Aircraft entering the Ankara FIR shall be in level flight prior to KATOT at one of the following assigned levels:

FL220, FL240, FL260, FL280, FL320, FL360, FL380, FL400

Note: *FL160, FL180 and FL200 are only to be used by coalition military aircraft.*

1.8.3.1.5 Aircraft operating at the same altitude on the same route shall anticipate a minimum of 10 minutes spacing from other aircraft.

1.8.3.1.6 All aircraft should be prepared to provide their estimated time (in minutes) to KABAN upon ATC request, in either direction of flight.

1.8.3.2 Agreement with Jordan

1.8.3.2.1 L200 is the only entry/exit route for aircraft between the Amman and Baghdad FIRs.

1.8.3.2.2 All aircraft that cross the Amman/Baghdad FIR boundary on L200 shall be in level flight, at the assigned flight level, at least 10 minutes prior to PASIP unless verbally coordinated otherwise. Altitude changes should not be anticipated within this 10 minute buffer from PASIP.

1.8.3.2.3 Aircraft entering the Baghdad FIR shall be in level flight at one of the following levels:

FL150, FL190, FL210, FL230, or FL270

1.8.3.2.4 Aircraft entering the Amman FIR shall be in level flight at one of the following levels:

FL160, FL180, FL200, FL220, FL240, FL260, or FL280

1.8.3.2.5 Aircraft entering the Amman FIR shall be processed at/below FL220 to the maximum extent possible.

1.8.3.2.6 Aircraft operating at the same altitude on the same route shall anticipate a minimum of 10 minutes spacing from other aircraft.

1.8.3.2.7 All aircraft should be prepared to provide their estimated time (in minutes) to PASIP upon ATC request, in either direction of flight.

1.8.3.3 Agreement with Syria

1.8.3.3.1 ATS routes UP975, UL602/UM861 and G202 shall be the only ingress/egress routes between the Baghdad and Damascus FIRs. The air traffic between the FIRs shall be established within the confines of these air routes prior to KANOK, ELEXI, or MODIK as appropriate for the route being flown. ATS routes UP975 and UL602 are temporarily not available, check NOTAMs for current status.

1.8.3.3.2 All aircraft that cross the Damascus/Baghdad FIR boundary on ATS route UP975, UL602/UM861, and G202 shall be in level flight, at an appropriate assigned altitude for direction of flight, at least 10 minutes prior to KANOK, ELEXI, or MODIK unless verbally coordinated otherwise.

1.8.3.3.3 Aircraft entering the Damascus FIR shall be in level flight at the assigned level at least 10 minutes prior to ELEXI, or MODIK intersection, at one of the following levels:

G202	
Flight Level Allocations	Special Instructions
FL160, FL180, FL220, FL240, FL260	Landing Damascus International Airport
FL240, FL260, FL280, FL300, FL320, FL340, FL360, FL380, FL400	Aircraft overflying the Damascus FIR
UL602/UM861	
Flight Level Allocations	Special Instructions
FL300, FL320, FL340, FL360, FL380, FL400	Aircraft overflying the Damascus FIR

1.8.3.3.4 Aircraft entering the Damascus FIR shall be in level flight at the assigned level at least 10 minutes prior to ELEXI, or MODIK intersection, at one of the following levels:

G202	
Flight Level Allocations	Special Instructions
FL150, FL170, FL190, FL230, FL250, FL270	Landing at airports within Baghdad FIR
FL250, FL270, FL290, FL310, FL330	Aircraft overflying the Baghdad FIR
UP975	
Flight Level Allocations	Special Instructions
FL290, FL310, FL330, FL350, FL370, FL390, FL410, FL430, FL450	Aircraft overflying the Baghdad FIR

Note: FL200 and FL210 are not to be assigned to aircraft operating within the Baghdad FIR.

1.8.3.3.5 **Longitudinal.** During the transfer of control, the minimum longitudinal separation to be used between aircraft flying at the same altitude on the same ATS route shall be 10 minutes. Speed control will be applied between aircraft that are at or near the minimum longitudinal separation standards to prevent loss of the prescribed separation minima. Speed control assignment information shall be passed to the receiving ACC.

1.8.3.3.6 **Transfer of Control Point (TCP).** ACCs shall assume total control of aircraft once it has been positively established that the aircraft has passed the following intersection and is inside their respective FIR lateral limits, unless verbally coordinated otherwise.

Transfer of Control Points	
ATS Route UP975	KANOK (FIR Boundary)
ATS Route UL602/UM861	ELEXI (FIR Boundary)
ATS Route G202	MODIK (FIR Boundary)

1.8.3.4 Agreement with Kuwait

1.8.3.4.1 L/UL602 and G795 are the only ingress routes for aircraft between the Baghdad and Kuwait FIRs. Aircraft shall be established on L/UL602 prior to TASMI.

1.8.3.4.2 P/UP975 and G975 are the only egress routes for aircraft between the Baghdad and Kuwait FIRs. Aircraft shall be established on P/UP975 prior to SIDAD.

1.8.3.4.3 All aircraft that cross the Kuwait/Baghdad FIR boundary on L/UL602 shall be in level flight, at the assigned altitude, at least 10 minutes prior to TASMI unless verbally coordinated or flying in accordance with paragraphs 1.8.3.4.5, 1.8.3.4.6 & 1.8.3.4.7. below. Altitude changes should not be anticipated within this 10 minute buffer from TASMI.

1.8.3.4.4 All aircraft that cross the Kuwait/Baghdad FIR boundary on P/UP975 shall be in level flight, at the assigned altitude, at least 10 minutes prior to SIDAD unless verbally coordinated. Altitude changes should not be anticipated within this 10 minute buffer from SIDAD.

1.8.3.4.5 Aircraft departing the Basrah CTA shall enter the Kuwait FIR at 11,000FT AMSL.

1.8.3.4.6 Aircraft landing in the Basrah CTA shall enter the Baghdad FIR at 12,000FT AMSL.

1.8.3.4.7 Aircraft departing/operating from the Kuwait FIR that will over fly the Basrah CTA shall cross TASMI at or above 11,000FT AMSL climbing to FL160.

Note: Kuwait ACC will coordinate with Ali ACC for aircraft requiring other altitudes.

1.8.3.4.8 Aircraft landing within the Kuwait FIR that are over flying the Basrah CTA shall enter the Kuwait FIR at FL170.

1.8.3.4.9 All other aircraft entering the Kuwait FIR shall be in level flight at one of the following levels:

FL190, FL210, FL230, FL250, FL270, FL310 or FL330

1.8.3.4.10 All other aircraft entering the Baghdad FIR shall be in level flight at one of the following levels:

FL160, FL180, FL200, FL220, FL240, FL260, FL280, FL360, FL380, or FL400

1.8.3.5 Agreement with Saudi Arabia

1.8.3.5.1 B411 is the only ingress/egress route for aircraft between the Baghdad and Jeddah FIRs. Aircraft shall be established within the confines of B411 prior to MURIB.

1.8.3.5.2 All aircraft that cross the Jeddah/Baghdad FIR boundary on B411 shall be in level flight, at the assigned altitude, at least 10 minutes prior to MURIB unless verbally coordinated. Altitude changes should not be anticipated within this 10 minute buffer from MURIB.

1.8.3.5.3 Aircraft entering the Jeddah FIR shall be in level flight at one of the following levels:

FL160, FL180, FL220, FL240, FL260 or FL280

1.8.3.5.4 Aircraft entering the Baghdad FIR shall be in level flight at one of the following levels:

FL150, FL170, FL190, FL230, FL250, FL270, FL310 or FL330

1.8.3.5.5 Aircraft flying at the same altitude on the same route shall anticipate a minimum of 10 minutes spacing from other aircraft.

1.8.3.5.6 All aircraft should be prepared to provide their estimated time (in minutes) to RALTI, LOVEK, MURIB, or ARAR VOR/DME upon ATC request, in either direction of flight.

ENR 1.9 AIR TRAFFIC FLOW MANAGEMENT (ATFM)

1.9.1 Slot time allocation procedures for civil overflight and landing aircraft. Aircraft overflights and landings at designated airports in the Baghdad FIR are controlled by a slot time allocation scheme. Refer to section GEN 1.2 for civil aircraft slot procedures.

ENR 1.10 FLIGHT PLANNING

1.10.1 General. The air traffic rules and procedures applicable to air traffic in the Baghdad FIR conform with Annexes 2 and 11 to the Convention on International Civil Aviation and to those portions applicable to aircraft of ICAO Doc 4444 Procedures for Air Navigation Services – Air Traffic Management, and Regional Supplementary Procedures applicable to the EUR/MID/ASIA region.

1.10.2 Mandatory timings for flight plans

1.10.2.1 The Baghdad Air Traffic Services Reporting Office is temporarily closed, therefore operators must submit flight plan details through other means. Operators of flights originating outside, but landing at an aerodrome within, the Baghdad FIR are to submit flight plans for the round trip. Flight plans shall be submitted sufficiently early to ensure it is received by the relevant Air Traffic Control agencies at least 30 minutes prior to estimated off block time (EOBT) for departures from within Iraq, or at least 60 minutes prior to the aircraft reaching the Baghdad FIR boundary for inbound or over flight aircraft.

1.10.2.2 Aircraft that will be more than 15 minutes before or after the slot window are to re-coordinate a new slot time with the RAMCC. In the event of a delay of one hour or more to an aircraft with a filed flight plan, the flight plan shall be cancelled and a new flight plan submitted or a delay message shall be submitted.

1.10.3 Flight plan messages. Aircraft operating within the Iraq FIR shall use the ICAO model flight plan contained in PANS ATM DOC 444/ATM501 Appendix 2, Page A2-11. Complete entries up to and including item 19, and include registration/type of aircraft, boundary estimates to/from the Baghdad FIR, and airport of intended landing.

1.10.4 Procedures applicable to operators (including pilots)

1.10.4.1 The levels at which a flight is to be conducted shall be specified in a flight plan as follows:

1.10.4.1.1 In terms of flight levels if the flight is to be conducted at or above the transition level, and

1.10.4.1.2 In terms of altitudes if the flight is to be conducted in the vicinity of an aerodrome and at or below the transition altitude.

1.10.4.2 Flight levels and altitudes selected for a flight shall ensure adequate terrain clearance along the route to be flown. Flight levels are specified in a flight plan by number and not in terms of feet or meters as in the case with altitudes. Selected flight levels shall be compatible with Appendix 3 Annex 2 to the Convention on International Civil Aviation, Table of Cruising Levels and comply with the cruising levels specified in ENR 1.8.3.

1.10.4.3 Aircraft may enter and exit the Baghdad FIR, only via the following points, and must flight plan accordingly:

COUNTRY	FIX	LAT / LONG
Kuwait (entry)	TASMI (602)	N30°01' 20.00" E047°55' 05.00"
Kuwait (exit)	SIDAD (975)	N29°52' 31.00" E048°29' 44.20"
Turkey	KABAN	N37°14' 56.00" E042°38' 59.00"
Syria	MODIK	N33°28' 06.00" E039°01' 00.00"
Jordan	PASIP	N33°00' 00.00" E038°55' 12.00"
Saudi Arabia	MURIB	N31°12' 36.00" E041°50' 36.00"

Note: When the continuation of air routes UL602 and UP975 to the Damascus FIR boundary are activated and the opening of the air routes between the Baghdad and Tehran FIRs the following will be the complete list of Baghdad FIR entry/exit points:

COUNTRY	FIX	LAT / LONG
Kuwait (entry)	TASMI	N30°01' 20.00" E047°55' 05.00"
Kuwait (exit)	SIDAD	N29°52' 31.00" E048°29' 44.20"
Turkey	KABAN	N37°14' 56.00" E042°38' 59.00"
Syria	MODIK	N33°28' 06.00" E039°01' 00.00"
Syria (entry)	ELEXI(602)	N34°41' 30.00" E041°09' 00.00"
Syria (exit)	KANOK (975)	N36°33' 54.00" E041°41' 00.00"
Jordan	PASIP	N33°00' 00.00" E038°55' 12.00"
Saudi Arabia	MURIB	N31°12' 36.00" E041°50' 36.00"
Iran	MIGMI	N33°45' 54.00" E045°27' 24.00"
Iran	RAGET	N33°30' 48.00" E045°53' 48.00"
Iran	PAXAT	N33°20' 56.00" E046°05' 19.00"

ENR 1.11 ADDRESSING OF FLIGHT PLAN MESSAGES

Flights intending to land in Iraq should file a roundtrip flight plan using the address ORBBZQZX. In addition, it is mandatory for all aircraft, whether landing, departing or overflying Iraq, to enter ETARYXYX as an addressee on their flight plan.

1.11.1 AFS addressee indicators for messages within Baghdad FIR. The ATS messages within Baghdad FIR should be addressed as follows:

Landing/Departing Aerodrome	Message Addressee
Traffic overflying Baghdad	ORBIZQZX
Traffic landing or departing from Baghdad Int'l Aerodrome	ORBIZQZX
Traffic landing or departing from Basrah Int'l Aerodrome	ORBIZQZX ORMMZQZX

The following AFTN addresses indicators are used in the AFTN messages as follows:

Message Addressee	Addressee Indicators/Locations
ORBIZQZX	Air traffic control center-Baghdad Int. Airport
ORMMZQZX	Air traffic control center-Basrah Int. Airport

ENR 1.12 INTERCEPTION OF CIVIL AIRCRAFT**1.12.1 Interception procedures**

1.12.1 The following procedures and visual signals apply throughout the Baghdad FIR in the event of interception of an aircraft. An aircraft that is intercepted by another aircraft shall immediately:

1.12.1.1 Follow the instructions given by the intercepting aircraft, interpreting and responding to visual signals in accordance with the specifications in Appendix 1 of ICAO Annex 2;

1.12.1.2 Notify, if possible the appropriate air traffic services unit;

1.12.1.3 Attempt to establish radio-communication with the intercepting aircraft or with the appropriate intercept control unit, by making a general call on the emergency frequency 121.5 MHZ, giving the identity of the intercepted aircraft and the nature of the flight; if no contact has been established and if practicable, repeat this call on the emergency frequency 243 MHZ;

1.12.1.4 If equipped with SSR transponder, select Mode A Code 7700, unless otherwise instructed by the appropriate air traffic services unit.

1.12.2 Phraseology during interception

1.12.2.1 If radio contact is established during interception but communication in a common language is not possible, attempts shall be made to convey instructions, acknowledgement of instructions and essential information by using the phrases and pronunciation in the following table, transmitting each phrase twice.

Phrase	Pronunciation	Meaning
CALL SIGN	KOL SA-IN	My call sign is (call sign)
WILCO	VILL-KO	Understood. Will comply
CAN NOT	KANN NOTT	Unable to comply
REPEAT	REE-PEET	Repeat your instruction
AM LOST	AM LOSST	Position unknown
MAYDAY	MAYDAY	I am in distress
HIJACK	HI-JACK	I have been hijacked
LAND	LAAND	I request to land at (Place name)
DESCEND	DEE-SEND	I require descent

1.12.2.2 The phrases shown in the table below shall be used by the intercepting aircraft and transmitted twice in the circumstances described in the preceding paragraph.

1.12.2.3 If any instructions received by radio from any sources conflict with those given by the intercepting aircraft by visual signals and/or by radio, the intercepted aircraft shall request immediate clarification while continuing to comply with the visual and/or radio instructions given by the intercepting aircraft.

1.12.2.4 The visual signals for use while intercepting are detailed on page ENR 1.12-3 to ENR 1.12-5.

Phrase	Pronunciation	Meaning
CALL SIGN	KOL SA-IN	What is your call sign?
FOLLOW	FOL-LO	Follow me
DESCEND	DEE-SEND	Descend for landing
YOU LAND	YOU LAAND	Land at this aerodrome
PROCEED	PRO-SEED	You may proceed

1.12.3 Signals for use in the event of interception

1.12.3.1 Signals initiated by intercepting aircraft and responses by intercepted aircraft:

Series	INTERCEPTING Aircraft Signals	Meaning	INTERCEPTED Aircraft Responds	Meaning
1	<p>DAY or NIGHT - Rocking aircraft and flashing navigational lights at irregular intervals (and landing lights in case of a helicopter) from a position slightly above and ahead of, and normally to the left of, the intercepted aircraft (or to the right if the intercepted aircraft is a helicopter) and, after acknowledgement, a slow level turn, normally to the left, (or to the right in the case of a helicopter) on the desired heading.</p> <p><i>Note 1 Meteorological conditions or terrain may required the intercepting aircraft to reverse the positions and direction of turn given above in Series 1.</i></p>	<p>You have been intercepted. Follow me.</p>	<p>DAY or NIGHT - Rocking aircraft, flashing navigational lights at irregular intervals and following.</p> <p><i>Note.-Additional action required to be taken by intercepted aircraft is prescribed in Annex 2. Chapter 3, 3.8.</i></p>	<p>Understood, will comply.</p>

	<i>Note 2.-If the intercepted aircraft is not able to keep pace with the intercepting aircraft, the latter is expected to fly a series of race-track patterns and to rock the aircraft each time it passes the intercepted aircraft.</i>			
2	DAY or NIGHT – An abrupt break away maneuver from the intercepted aircraft consisting of a climbing turn of 90 degrees or more without crossing the line of flight of the intercepted aircraft.	You may proceed.	DAY or NIGHT- Rocking the aircraft.	Understood will comply.
3	DAY or NIGHT- Lowering landing gear (if fitted), showing steady landing lights and over flying RWY in use or, if the intercepted aircraft is a helicopter, overflying the helicopter landing area. In the case of helicopters, the intercepting helicopter makes a landing approach, coming to hover near to the landing area.	Land at this aerodrome.	DAY or NIGHT- Lowering landing gear. (if fitted). showing steady landing lights and following the intercepting aircraft and if, after overflying the RWY in use or helicopter landing area, landing is considered safe. Proceeding to land.	Understood will comply.

1.12.3.2 Signals initiated by intercepted aircraft and responses by intercepting aircraft

Series	INTERCEPTED Aircraft Signals	Meaning	INTERCEPTING Aircraft Responds	Meaning
4	DAY or NIGHT-Raising landing gear (if fitted) and flashing landing lights while passing over RWY in use or helicopter landing area at a height exceeding 1000FT (300M) but not exceeding 2000FT (600M) (in the case of a helicopter, at a height exceeding 170FT (50M) but not exceeding 330FT (100M) above the aerodrome level, and continuing to circle RWY in use or helicopter landing area. If unable to flash landing lights, flash any other lights available.	Aerodrome you have designated is inadequate.	DAY or NIGHT- If it is desired that the intercepted aircraft follow the intercepting aircraft to an alternate aerodrome, the intercepting aircraft raises its landing gear (if fitted) and use the Series 1 signals prescribed for intercepting aircraft. If it is decided to release the intercepted aircraft, the intercepting aircraft uses the Series 2 signals prescribed for intercepting aircraft.	Understood follow me. Understood you may proceed.
5	DAY or NIGHT – Regular switching on and off all available lights but in such a manner as to be distinct from flashing lights.	Cannot Comply.	DAY or NIGHT – Use Series 2 signals prescribed for intercepting aircraft.	Understood.
6	DAY or NIGHT – Irregular flashing of all available lights.	In distress.	DAY or NIGHT- Use Series 2 signals prescribed for intercepting aircraft.	Understood..

ENR 1.13 UNLAWFUL INTERFERENCE

1.13.1 General

1.13.1.1 An aircraft which is being subjected to unlawful interference shall endeavor to notify the appropriate ATS unit of this fact, any significant circumstances associated therewith and any deviation from the current flight plan necessitated by the circumstances, in order to enable the ATS unit to give priority to the aircraft and to minimize conflict with other aircraft.

1.13.1.2 The following procedures are intended for use by aircraft when unlawful interference occurs and the aircraft is unable to notify an ATS unit of this fact via normal air-ground voice communications.

1.13.2 Procedures

1.13.2.1 Unless considerations aboard the aircraft dictate otherwise, the pilot-in-command should attempt to continue flying on the assigned track and at the assigned cruising level at least until notification to an ATS unit is possible or the aircraft is within radar coverage.

1.13.2.2 When an aircraft subjected to an act of unlawful interference must depart from its assigned track or its assigned cruising level without being able to make radiotelephony contact with ATS, the pilot-in-command should, whenever possible:

1.13.2.2.1 Attempt to broadcast warnings on the VHF emergency frequency and other appropriate frequencies, unless considerations aboard the aircraft dictate otherwise. Other equipment such as onboard transponders, data links, etc. should also be used when it is advantageous to do so and circumstances permit; and

1.13.2.2.2 Proceed in accordance with applicable special procedures for in-flight contingencies, where such procedures have been established and promulgated in Doc 7030 – Regional Supplementary Procedures; or

1.13.2.2.3 If no applicable regional procedures have been established, proceed at a level which differs from the cruising levels normally used for IFR flight in the area by 2,000FT (600 M) if above FL290 or by 1,000FT (300 M) if below FL290.

1.13.2.3 An aircraft equipped with an SSR transponder is expected to operate the transponder on Mode A Code 7500 to indicate specifically that it is the subject of unlawful interference. The aircraft may operate the transponder on Mode A Code 7700, to indicate that it is threatened by grave and imminent danger, and requires immediate assistance.

1.13.2.4 Action to be taken by SSR-equipped aircraft which are being subjected to unlawful interference is contained in Annex 11, the PANS-ATM (Doc 4444) and the PANS-OPS (Doc 8168). Action to be taken by CPDLC-equipped aircraft which are being subjected to unlawful interference is contained in Annex 11, the PANS-ATM (Doc 4444), and guidance material on the subject is contained in the Manual of Air Traffic Services Data Link Applications (Doc 9694).

ENR 1.14 AIR TRAFFIC INCIDENTS

The Air Traffic Incident procedures described below are derived from Appendix 4 to ICAO Doc 4444 Procedures for Air Navigation Services – Air Traffic Management.

1.14.1 Definition of air traffic incidents

1.14.1.1 ‘Air traffic incident’ is used to mean a serious occurrence related to the provision of air traffic services, such as:

1.14.1.1.1 Aircraft proximity (AIRPROX);

1.14.1.1.2 Serious difficulty resulting in a hazard to aircraft caused, for example, by:

1.14.1.1.2.1 Faulty procedures;

1.14.1.1.2.2 Non-compliance with procedures, or

1.14.1.1.2.3 Failure of ground facilities.

1.14.2 Definitions for aircraft proximity and AIRPROX.

1.14.2.1 **Aircraft proximity.** A situation in which, in the opinion of the pilot or the air traffic services personnel, the distance between aircraft, as well as relative positions and speed, has been such that the safety of the aircraft involved may have been compromised. Aircraft proximity is classified as follows:

1.14.2.1.1 **Risk of collision.** The risk classification of aircraft proximity in which serious risk of collision has existed.

1.14.2.1.2 **Safety not assured.** The risk classification of aircraft proximity in which serious of the aircraft may have been compromised.

1.14.2.1.3 **No risk of collision.** The risk classification of aircraft proximity in which no risk of collision has existed.

1.14.2.1.4 **Risk not determined.** The risk classification of aircraft proximity in which insufficient information was available to determine the risk involved, or inconclusive or conflicting evidence precluded such determination.

1.14.2.2 **AIRPROX.** The code word used in an air traffic incident report to designate aircraft proximity.

1.14.3 Designation of air traffic incidents: Air traffic incidents are designated and identified in reports as follows:

Type	Designation
Air traffic incident	Incident
as 1.14.1.1.1 above	AIRPROX(aircraft proximity)
as 1.14.1.1.2.1 and .2 above	Procedure
as 1.14.1.1 2 3 above	Facility

1.14.4 Use of the air traffic incident report form (See page 1.14-3 to 1.14-4)

1.14.4.1 The Air Traffic Incident Report Form is intended for use:

1.14.4.1.1 By a pilot for filing a report on an air traffic incident after arrival or for confirming a report made initially by radio during flight.

Note: The form, if available on board, may also be of use in providing a template for making the initial report in flight.

1.14.4.1.2 By an ATS unit for recording an air traffic incident report received by radio, telephone or teleprinter.

Note: The form may be used as a template for the text of a message to be transmitted over the AFS network.

1.14.5 Reporting procedures (including in-flight procedures)

1.14.5.1 The following are the procedures to be followed by a pilot who is or has been involved in an incident:

1.14.5.1.1 During flight, use the appropriate air/ground frequency for reporting an incident of major significance, particularly if it involves other aircraft, so as to permit the facts to be ascertained immediately. Inform air traffic control immediately of intentions to file a report to facilitate a timely investigation.

1.14.5.1.2 As promptly as possible after landing, submit a completed Air Traffic Incident Report Form:

1.14.5.1.2.1 For confirming a report of an incident made initially as in 1.14.5.1.1 above, or for making the initial report on such an incident if it had not been possible to report it by radio; or

1.14.5.1.2.2 For reporting an incident which did not require immediate notification at the time of occurrence.

1.14.5.2 An initial report made by radio should contain the following information;

1.14.5.2.1 Aircraft identification;

1.14.5.2.2 Type of incident, e.g. aircraft proximity; and

1.14.5.2.3 The incident details of A, F, I, J, K, L, M, N and O.

1.14.5.3 The confirmatory report on an incident of major significance initially reported by radio or the initial report on any other incident should be submitted to:

- a. Director, Flight Safety, ICAA, E-mail: iraqfltsafety@yahoo.com**
- b. Director, Air Traffic Services, ICAA, E-mail: al_nueimi@yahoo.com**
- c. Director General, ICAA, E-mail: ibiap1@yahoo.com**
- d. CFACC Safety, E-mail: CAOC-FSLiaison@auab.centaf.af.mil**

1.14.6 Purpose of reporting and handling of the form

1.14.6.1 The purpose of the reporting of aircraft proximity incidents and their investigation is to promote the safety of aircraft. The degree of risk involved in an aircraft proximity incident should be determined in the incident investigation and classified as ‘risk of collision’, ‘safety not assured’, ‘no risk of collision’ or ‘risk not determined’.

1.14.6.2 The purpose of the form is to provide investigation authorities with as complete information on an air traffic incident as possible and to enable them to report back, with the least possible delay to the pilot or operator concerned, the result of the investigation of the incident and, if appropriate, the remedial action taken.

1.14.7 Air traffic incident report form. The Air Traffic Incident Report form (ATIRF) is to be used when submitting or receiving a report on an incident involving a civilian aircraft. Shaded boxes contain items to be included in an initial report. The ATIRF number will be assigned by the ICAA Flight Safety agency. Incidents involving military ATC procedures and separation, airfield operations or facilities will be internally reported, investigated and resolved using established Coalition Forces reporting programs.

1.14.7.1 The ATIRF is available as a standalone document on the RAMCC website (<http://ramcc.dtic.mil>).

ENR 2. AIR TRAFFIC SERVICES AIRSPACE

ENR 2.1 FLIGHT INFORMATION REGIONS AND TERMINAL CONTROL AREAS

The following tables detail dimensions of the Baghdad FIR. Aircraft operating within the Baghdad FIR must maintain continuous air-ground communications with the relevant Air Traffic Services unit and continuously monitor the international distress frequency 121.5 MHz or 243.0 MHz.

2.1.1. Area Control Centers:

Name and Lateral Limits Note: <i>Baghdad FIR is divided into three ACCs as follows:</i>	Upper limit Lower limit and Class	Unit providing ATS	Radio callsign, FREQ, language	Remarks
Balad ACC: From N31°00' E042°10' to N32°02' E044°20' to N32°37' E046°54' then along the national border between Iraq and Iran to N34°30' E045°28', then to N34°30' E041°47' then to N34°51' E041°15', then via the national border between Iraq and Syria to N33°22' E038°48', then via the national border between Iraq and Jordan to N32°09' E039°13', then along the national border between Iraq and Saudi Arabia to N31°00' E042°10'	UNL FL290 Class A UNL ENR 1.4 TMA Class E UNL Surface Class G	Balad ACC	Balad Center 123.525 MHz 274.575 MHz English	Class A airspace air routes only. Remain on airway unless approved by ATC or Military Radar Unit
Kirkuk ACC: From N34°51' E041°15' to N34°30' E041°47' then to N34°30' E045°28', then along the national border between Iraq and Iran to N37°10' E044°47', then along the national border between Iraq and Turkey to N37°07' E042°22', then along the national border between Iraq and Syria to N34°51' E041°15'	UNL FL290 Class A UNL ENR 1.4 TMA Class E UNL Surface Class G	Kirkuk ACC	Kirkuk Center 125.30 MHz 237.325 MHz English	Class A airspace air routes only. Remain on airway unless approved by ATC or Military Radar Unit

Ali ACC: From N31°00' E042°10', along the national border between Iraq and Saudi Arabia to N29°06' E046°33', then along the national border between Iraq and Kuwait to N29°52' E048°23', then to N29°57' E048°35', then along the national border between Iraq and Iran to N32°37' E046°54', then to N32°02' E044°20', then to N31°00' E042°10'.	UNL FL290 Class A UNL ENR 1.4 TMA Class E UNL Surface Class G	Ali ACC	Ali Center 132.775 MHz 322.05 MHz English	Class A airspace air routes only. Remain on airway unless approved by ATC or Military Radar Unit
---	--	---------	--	--

2.1.2. Terminal Control Areas (TMA):

All TMA's listed exclude Class D Control Zones associated with the airfield.

Name and Lateral Limits	Upper limit Lower limit and Class	Unit providing ATS	Radio callsign, FREQ, language
Al Asad TMA: Lateral Limits: 35NM radius of Al Asad, centered on ORAA ARP. (N33°47'08.19" E042°26'28.32") SCTR A: 5NM radius centered on ORAA ARP. SCTR B: 5NM–15NM radius centered on ORAA ARP. SCTR C: 15NM–35NM radius centered on ORAA ARP.	SCTR A A120 A030 Class E SCTR B A120 A010 Class E SCTR C A120 A030 Class E	Al Asad APP	Al Asad Approach 147.85 MHz 298.025 MHz English
Al Taqaddum TMA: Lateral Limits: From N33°46'00" E043°19'00" to N33°38'42" E043°45'07.80" to N33°18'44.4" E044°00'00" to N33°00'00" E044°00'00" to N32°59'45" E043°11'30.6" then along the minor arc of a circle of 55NM radius centered on N33 15' 45.14" E044 14' 04.476" (ORBI ARP) to N33°46'00" E043°19'00".	A120 Surface Class E	Al Taqaddum APP	Al Taqaddum Approach 147.3 MHz 125.25 MHz 295.85 MHz English

<p>Baghdad TMA:</p> <p>Lateral Limits:</p> <p>CTA A: From N33°30'00" E044°08'34" to N33°30'00" E044°19'30" then along the major arc of a circle of 15NM radius centred on N33°15'45.14" E044°14'04.48" (ORBI ARP) to N33°30'00" E044°08'34". Excluding that portion of airspace that overlies the Al Taqaddum TMA.</p> <p>CTA B: From N33°50'00" E043°44'00" to N33°50'00" E043°50'00" to N33°40'00" E043°50'00" to N33°40'00" E044°00'00" to N33°30'00" E044°00'00" to N33°30'00" E044°40'00" to N33°20'00" E044°40'00" to N33°20'00" E044°51'00" to N33°07'52" E044°48'44" then along the major arc of a circle of 30NM radius centred on N33°15'45.14" E044°14'04.48" (ORBI ARP) to N33°20'52" E043°38'45" to N33°50'00" E043°44'00". Excluding that portion of airspace that overlies the Al Taqaddum TMA.</p> <p>CTA C: From N33°50'00" E043°15'00" to N33°50'00" E043°50'00" to N33°40'00" E043°50'00" to N33°40'00" E044°00'00" to N33°30'00" E044°00'00" to N33°30'00" E044°40'00" to N33°20'00" E044°40'00" to N33°20'00" E044°51'00" to N33°20'00" E045°25'042" then along the major arc of a circle of 60NM radius centred on N33°15'45.14" E044°14'04.48" (ORBI ARP) to N33°50'00" E043°15'00". Excluding that portion of airspace that overlies the Al Taqaddum TMA.</p>	<p>CTA A A050 <u>A030</u> Class E</p> <p>CTA B A100 <u>A050</u> Class E</p> <p>CTA C FL180 <u>A100</u> Class E</p>	<p>Baghdad APP</p>	<p>Baghdad Approach</p> <p>128.2 MHz</p> <p>242.5MHz</p> <p>English</p>
--	--	------------------------	---

<p>Balad TMA:</p> <p>Lateral Limits:</p> <p>CTA A: A circle of 15NM radius centered on N33°56'24.70" E044°21'41.70" (ORBD ARP).</p> <p>CTA B: From. N34°01'30" E043°46'03" along the major arc of a circle of 30NM radius centered on N33°56'24.70" E044°21'41.70" (ORBD ARP) to N33°51'04" E044°57'17" then in a straight line to N33°20'00" E044°51'00" to N33°20'00" E044°40'00" to N33°30'00" E044°40'00" to N33°30'00" E044°00'00" to N33°40'00" E044°00'00" to N33°40'00" E043°50'00" to N33°50'00" E043°50'00" to N33°50'00" E043°44'00" to N34°01'30" E043°46'03".</p> <p>CTA C: From N33°50'00" E043°09'44" along the major arc of a circle of radius 60NM centered upon N33°56'24.70" E044°21'41.70" (ORBD ARP) to N33°20'00" E045°19'00" then in a straight line to N33°20'00" E044°51'00" to N33°20'00" E044°40'00" to N33°30'00" E044°40'00" to N33°30'00" E044°00'00" to N33°40'00" E044°00'00" to N33°40'00" E043°50'00" to N33°50'00" E043°50'00" to N33°50'00" E043°44'00" to N33°50'00" E043°09'44".</p>	<p>CTA A A050 <u>A030</u> Class E</p> <p>CTA B A100 <u>A050</u> Class E</p> <p>CTA C FL180 <u>A100</u> Class E</p>	<p>Balad APP</p>	<p>Balad Approach 131.9 MHz</p> <p>246.425 MHz</p> <p>English</p>
<p>Basrah TMA:</p> <p>Lateral Limits: From N31°27.95' E047°43.11' then along the minor arc of a circle of 55NM radius centered on N30°32.94' E047°39.73' (ORMM ARP) to N31°18.56' E047°03.86' to N30°10.84' E046°41.24', then along the minor arc of a circle of 55NM radius centered on N30°32.94' E047°39.73'</p>	<p>SCTR A A120 <u>A010</u> Class E</p> <p>SCTR B A120 <u>A030</u> Class E</p>	<p>Basrah APP</p>	<p>Basrah Approach Primary 119.4 MHz</p> <p>233.225 MHz</p> <p>English</p>

<p>(ORMM ARP) to N29°47.91' E047°04.29', then along the national border between Iraq and Kuwait to N29°52' E048°23', N29°57' E048°35', then along the national border between Iraq and Iran to N31°27.95' E047°43.11'</p> <p>Sector A: 15NM radius of ORMM ARP, within the lateral confines of Basrah TMA.</p> <p>Sector B: 15NM–55NM radius of ORMM ARP, within the lateral confines of Basrah TMA.</p>			
<p>Kirkuk TMA:</p> <p>Lateral Limits: 55NM radius of Kirkuk ARP centered on ORKK ARP. (N35°28.17' E044°20.94')</p> <p>SCTR A: 15NM radius centered on ORKK ARP</p> <p>SCTR B: 15NM–55NM radius centered on ORKK ARP.</p> <p>SCTR C: 55NM radius centered on ORKK ARP</p>	<p>SCTR A FL180 <u>A020</u> Class E</p> <p>SCTR B FL180 <u>A040</u> Class E</p> <p>SCTR C UNL <u>FL180</u> Class E</p>	<p>SCTR A SCTR B Kirkuk APP</p> <p>SCTR C Kirkuk ACC</p>	<p>SCTR A SCTR B Kirkuk Approach 129.75 MHz 264.2 MHz</p> <p>SCTR C 125.3 MHz 237.325 MHz</p> <p>English</p>
<p>Mosul TMA:</p> <p>Lateral Limits: From N36°15.18' E043°45.86' then along the minor arc of a circle of 55NM radius centered on N35°28.17' E044°20.94' (ORKK ARP) to N35°49.26' E043°18.66' then along the major arc of a circle of 30NM radius centered on N36°18'20.74" E043°08'50.63" (ORBM ARP) to N36°15.18' E043°45.86'</p> <p>SCTR A: 15NM radius of ORBM ARP</p> <p>SCTR B: 15NM–30NM radius of ORBM ARP, within the lateral confines of Mosul TMA.</p>	<p>SCTR A A120 <u>A020</u> Class E</p> <p>SCTR B A120 <u>A040</u> Class E</p>	<p>Mosul APP</p>	<p>Mosul Approach 119.45 MHz 259.125 MHz</p> <p>English</p>
<p>Ali Base TMA:</p> <p>Lateral Limits: From N31°18.56' E047°03.86' then along the major arc of a circle 55NM radius</p>	<p>SCTR A FL180 <u>A010</u> Class E</p>	<p>SCTR A SCTR B Ali APP</p>	<p>SCTR A SCTR B Ali Approach 126.295</p>

centered on N30°56.15' E046°05.41' (ORTL ARP) to N30°10.84' E046°41.24', to N31°18.56' E047°03.86'. SCTR A: 15NM radius centered on ORTL ARP SCTR B: 15NM–55NM radius centered on ORTL ARP, within the lateral confines of Ali TMA. SCTR C: 55 NM radius of ORTL ARP, within the lateral confines of Ali TMA.	SCTR B FL180 <div>A030</div> Class E SCTR C UNL <div>FL180</div> Class E	SCTR C Ali ACC	MHz 324.925 MHz SCTR C Ali Center 132.775 MHz 322.05 MHz English
--	---	-------------------	--

2.1.3. Control Zones:

Name and Lateral Limits	Upper limit Lower limit and Class	Unit providing ATS	Radio callsign, FREQ, language
Al Asad Control Zone: Established within 5NM radius of the Al Asad Airport Reference Point (ARP) (N33°47'08.19" E042°26'28.32")	A030 Surface Class D	Al Asad TWR	Al Asad Tower 363.675 MHz English
Al Qaim Control Zone: Established within 5NM radius of position N34°15'58.57" E041°09'44.05"	A030 Surface Class D	Qaim TWR	Qaim Tower 255.8 MHz 139.55 MHz English
Al Sahra Control Zone: Established within 5NM radius of the Al Sahra ARP (N34°40.39' E043°32.58")	A030 Surface Class D	Al Sahra TWR	Spiecher Tower 363.575 MHz English
Al Taji Control Zone: Established within a 5NM radius of the Taji ARP. (N33°31.7' E044°15.7')	A030 Surface Class D	Taji TWR	Taji Tower 130.025 MHz English
Al Taqaddum Control Zone: Established within 5NM radius of the Al Taqaddum ARP (N33°20'16.99" E043°35'49.46")	A030 Surface Class D	Al Taqaddum TWR	Taqaddum Tower 135.775 MHz or 243.5 MHz English
Baghdad Control Zone: Centered on the BIAP ARP. Class D airspace contained within N33 20.46 E44 12.17 to N33 11.85 E44 17.77 thence se via the major arc of a circle of 5NM centered on BIAP ARP to N33 20.46 E44 12.17 SFC to 3000 ft, excluding the portion N33 18.84 E44 09.40 thence SW via the minor arc of a circle of 5NM radius centered on BIAP ARP to N33 10.80 E44 14.76 to N33 18.84 E44 09.40 SFC to 1000 ft. (BIAP ARP N33°15'45.140" E044°14'04.476")	A030 Surface Class D	Baghdad TWR	Baghdad Tower 118.9 MHz or 275.8 MHz English

Balad SE Control Zone: Established within 5NM radius of the Balad ARP (N33°56'24.70" E044°21'41.70")	A030 <u>Surface</u> Class D	Balad TWR	Balad Tower 119.875 MHz or 368.4 MHz English
Basrah Control Zone: Established within 5NM radius of the Basrah ARP (N30°32.94' E047°39.73')	A030 <u>Surface</u> Class D	Basrah TWR	Basrah Tower 118.7MHz or 241.175MHz English
Kirkuk Control Zone: Established within 5NM radius of the Kirkuk ARP (N35°28.17' E044°20.94')	A040 <u>Surface</u> Class D	Kirkuk TWR	Kirkuk Tower 125.55MHz or 327.8MHz English
Korean Village Control Zone: Established within 5NM radius of position N33°01'05.02" E039°56'15.62"	A030 <u>Surface</u> Class D	Korean Village TWR	KAY VEE Tower 339.35 MHz 141.3 MHz English
Mosul Control Zone: Established within 5NM radius of the Mosul ARP (N36°18'20.74" E043°08'50.63")	A040 <u>Surface</u> Class D	Mosul TWR	Mosul Tower 132.825 MHz or 250.025 MHz English
Qayyarah West Control Zone: Established within 5NM radius of the Qayyarah West ARP (N35°46'12" E043°07'25")	A030 <u>Surface</u> Class D	Qarrayah TWR	Qarrayah Tower 122.2 MHz 236.725 MHz English
Washington Army Heliport Control Zone: Established within 3NM radius of position N33°18'19" E044°24'10"	A010 <u>Surface</u> Class D	Washington TWR	Washington Tower 125.100 MHz or 330.750MHz English
Ali Control Zone: Established within 5NM radius of the Ali ARP (N30°56.15' E046°05.41')	A030 <u>Surface</u> Class D	Ali TWR	Ali Tower 128.8 MHz or 397.725 MHz English

ENR 3 ATS ROUTES

ENR 3.1 LOWER ATS ROUTES

Baghdad FIR does not have a separate lower ATS route structure. See ENR 3.3.

ENR 3.2 UPPER ATS ROUTES

Baghdad FIR does not have a separate upper ATS route structure. See ENR 3.3.

ENR 3.3 AREA NAVIGATION ROUTES

3.3.1 Rules applicable to air routes in Baghdad FIR

3.3.1.1 A diagram of the ATS routes within the Baghdad FIR is at ENR 3.3-6. All ATS routes in the Baghdad FIR are area navigation routes (RNAV) designated for aircraft approved for Required Navigation Performance 5 (RNP5) operations. Aircraft must be capable of maintaining RNP5 without reliance on ground based navigation aid updates in the Baghdad FIR.

3.3.1.2 The communications procedures for entering Baghdad FIR are as follows:

3.3.1.2.1 **Entering from Turkey.** Prior to entering the Baghdad FIR contact Kirkuk Center on 125.30 MHz or 237.325 MHz. If no response, proceed on last assigned routing and altitude while attempting contact every 10NM.

3.3.1.2.2 **Entering from Jordan, Syria or Iran.** Prior to entering the Baghdad FIR contact Balad Center 131.900 MHz or 255.800 MHz. If no response, proceed on last assigned routing and altitude while attempting contact every 10NM.

3.3.1.2.3 **Entering from Kuwait at or above 13,000FT AMSL.** Prior to entering the Baghdad FIR contact Ali Center on 132.775 MHz or 322.05 MHz. If no response, proceed on last assigned routing and altitude while attempting contact every 10NM.

3.3.1.2.4 **Entering from Kuwait at or below 12,000FT AMSL.** Prior to entering the Baghdad FIR contact Basrah Approach on 119.4 MHz or 233.225 MHz. If no response, proceed on last assigned routing and altitude while attempting contact every 10NM.

Note: Radio coverage in Iraq is limited at the extremities of all air routes. In particular, eastbound flights should not expect radio contact with Baghdad ACC until passing RAPLU or RALTI unless above FL180. In the event of an emergency requiring descent in an area of poor radio coverage, pilots are to attempt to contact any air traffic unit on a published frequency and/or the emergency frequencies.

3.3.1.3 Area Navigation Route descriptions.


Reporting/ Waypoint ID/ Coordinates. ▲ <i>Compulsory</i> △ <i>As Requested</i>	Magnetic Track. (In/Out)	Distance. (NM)	Levels. MAA MEA MOCA's	Airspace Class.	Route Width. (NM)	Remarks.
ATS Route G795 ▲ TASMI (N30°01'20.00" E047°55'05.00") ▲ BSR (N30°31'32.40" E047°41'12.00")	—/335 335/—	32.4	13,000 FT 8,000 FT 1,600 FT	Class E	12	Ali Center 132.775 MHz 322.050 MHz Basrah Approach 119.400 MHz 233.225 MHz
ATS Route M203 △ LOVEK (N32°22'08.40" E044°40'01.20") △ PUSTO (N33°21'00.00" E042°45'00.00")	—/298 297/—	113.3	FL460 FL150 1,700 FT	Class E: FL150 to FL280 Class A: FL290 to FL460	12	Balad Center 123.525 MHz 274.575 MHz
ATS Route B411 ▲ MURIB N31°12'37.00" E041°50'36.00" △ RALTI N31°42'08.40" E043°00'00.60" △ LOVEK N32°22'08.40" E044°40'01.20" △ NOLDO N32°49'32.40" E045°21'29.40" ▲ PAXAT N33°20'52.34" E046°05'18.79"	—/060 061/061 062/048 048/046 046/—	66.3 93.9 44.4 48.3	FL460 FL150 2,500 FT 2,100 FT 2,300 FT 4,300 FT	Class E: FL150 to FL280 Class A: FL290 to FL460	12	Balad Center 123.525 MHz 274.575 MHz NOLDO to PAXAT NOT AVBL. Refer to NOTAMs for current status.
ATS Route L126 ▲ ILM (N33°34'42.30" E046°24'55.40") ▲ MIGMI (N33°45'54.00" E045°27'24.00") △ SIGNI (N34°00'07.80" E044°42'01.20") △ SOGUM (N34°12'12.00" E043°54'54.00") △ PUSTO (N33°21'00.00" E042°45'00.00")	—/280 279/287 286/283 283/225 224/—	49.3 40.3 40.9 77.5	FL460 FL150 9,900 FT 2,300 FT 1,600 FT 1,700 FT	Class E: FL150 to FL280 Class A: FL290 to FL460	12	Balad Center 123.525 MHz 274.575 MHz ILM to MIGMI NOT AVBL. Refer to NOTAMs for current status.

ATS Route R784			FL460 FL150			
▲KABAN (N37°14'56.00" E042°38'59.00")	—/148					Kirkuk Center 125.30 MHz 237.325 MHz
△KATOT (N36°00'00.00" E043°27'00.00")	149/147	84.2	8,000 FT			
△RAMPI (N35°16'39.60" E043°56'15.00")	147/147	49.4	3,900 FT	Class E: FL150 to FL280	16.5	Balad Center 123.525 MHz 274.575 MHz
▲DASUR (N34°30'05.62" E044°24'17.35")	147/149			Class A: FL290 to FL460		Waypoint DASUR not flight checked for position confirmation
△SIGNI (N34°00'07.80" E044°42'01.20")	150/151	85.2	2,200 FT			
△PARUN (N33°24'12.00" E045°02'01.20")	151/151	39.6	2,300 FT			
△NOLDO (N32°49'32.40" E045°21'29.40")	151/—	38.3	1,500 FT			
ATS Route L417			FL460 FL150			Kirkuk Center 125.30 MHz 237.325 MHz
△RAMPI N35°16'39.60" E043°56'15.00"	—/177			Class E: FL150 to FL280	12	Balad Center 123.525 MHz 274.575 MHz
▲ALVIS N34°30'04.04." E043°55'17.64"	177/177	64.4	2,800 FT	Class A: FL290 to FL460		SOGUM to LOVEK NOT AVBL to civil aircraft at or below FL280.
△SOGUM N34°12'12.00" E043°54'54.00"	177/159	58.9	2,200 FT			Waypoint ALVIS not flight checked for position confirmation.
▲BGD N33°15'38.60" E044°14'57.29"	160/154	57.4	2,200 FT			
△LOVEK N32°22'08.40" E044°40'01.20"	155/—					
ATS Route G202			FL460 FL150			Balad Center 123.525 MHz 274.575 MHz
▲MODIK N33°28'06.00" E039°01'00.00"	—/087	137.8	3,500 FT	Class E: FL150 to FL280	12	PUSTO to PARUN NOT AVBL to civil aircraft at or below FL280
△RAPLU N33°23'00.00" E041°45'30.00"	087/088	49.9	2,600 FT	Class A: FL290 to FL460		RAGET to ILM NOT AVBL. Refer to NOTAMs for current status.
△PUSTO N33°21'00.00" E042°45'00.00"	087/090	75.6	2,200 FT			
▲BGD N33°15'38.60" E044°14'57.29"	090/074	40.4	2,200 FT			
△PARUN N33°24'12.00" E045°02'01.20"	074/077	43.8	4,400 FT			
▲RAGET N33°30'48.00" E045°53'48.00"	078/078	26.3	9,900 FT			
▲ILM N33°34'42.30" E046°24'55.40"	078/—					

ATS Route L200 ▲PASIP N33°00'00.00" E038°55'12.00" △RAPLU N33°23'00.00" E041°45'30.00"	—/076 078/—	144.7	FL460 FL150 4,300 FT	Class E: FL150 to FL280 Class A: FL290 to FL460	12	Balad Center 123.525 MHz 274.575 MHz
ATS Route L602 ▲TASMI (N30°01'20.00" E047°55'05.00") △ALPET (N31°12'19.00" E046°18'44.00") △LOVEK (N32°22'08.40" E044°40'01.20")	—/308 308/307 307/—	109.2 109.2	FL280 FL150 1,800 FT 2,300 FT	Class E	16.5	Ali Center 132.775 MHz 322.050 MHz Balad Center 123.525 MHz 274.575 MHz One-way route. WEST bound traffic only.
ATS Route UL602 ▲TASMI (N30°01'20.00" E047°55'05.00") △ALPET (N31°12'19.00" E046°18'44.00") ▲MUTLO (N32°10'18.98" E044°57'02.83") △LOVEK (N32°22'08.40" E044°40'01.20") △DELM (N33°19'18.31" E043°13'27.59") △ASNOT (N33°29'59.55" E042°57'16.62") ▲ELEXI (N34°41'30.00" E041°09'00.00") △DRZ (N35°17'21.16" E040°11'14.71")	—/308 308/307 307/307 307/305 305/304 304/305 305/303 303/—	109.2 109.2 92.6 17.2 114.8 59.4	FL460 FL290 1,800 FT 2,300 FT 1,700 FT 1,800 FT 2,300 FT 2,400 FT	Class A	16.5	Ali Center 132.775 MHz 322.050 MHz Balad Center 123.525 MHz 274.575 MHz One-way route. WEST bound traffic only. LOVEK to ELEXI NOT AVBL. Refer to NOTAMs for current status. Waypoint MUTLO not flight checked for position confirmation
ATS Route P975 △NOLDO N32°49'32.40" E045°21'29.40" △ILMAP N31°21'33.00" E046°57'02.00" ▲SIDAD N29°52'31.00" E048°29'44.00"	—/133 133/134 134/—	119.6 119.5	FL280 FL150 1,800 FT 1,500 FT	Class E	16.5	Balad Center 123.525 MHz 274.575 MHz Ali Center 132.775 MHz 322.050 MHz One-way route. EAST bound traffic only.

ATS Route UP975			FL460 FL290			Kirkuk Center 125.30 MHz 237.325 MHz
▲LESRI (N37°04'20.00" E041°13'49.00")	—/140					
▲KANOK (N36°33'58.00" E041°40'59.38")	140/137	37.4	4,800 FT			Balad Center 123.525 MHz 274.575 MHz
△GETID (N35°15'50.61" E042°55'58.91")	137/134					
▲LOPAS (N34°30'03.45" E043°38'34.38")	134/134		5,700 FT			Ali Center 132.775 MHz 322.050 MHz
△SOGUM(N34°12'12.00" E043°54'54.00")	134/134	178.9	2,300 FT	Class A	16.5	One-way route. EAST bound traffic only.
△ETBOM (N33°21'37.31" E044°47'52.55")	134/135	67.1	1,500 FT			
△NOLDO (N32°49'32.40" E045°21'29.40")	135/133	42.7				KANKOK to SOGUM NOT AVBL. Refer to NOTAMs for current status.
▲DENKI (N32°22'28.46" E045°51'21.58")	133/133		1,800 FT			
△ILMAP (N31°21'33.00" E046°57'02.00")	133/134	119.6	1,500 FT			Waypoints GETID, LOPAS and DENKI not flight checked for position confirmation
▲SIDAD(N29°52'31.00" E048°29'44.00")	134/—	119.5				

3.3.2 Approved ATS routes and Entry/Exit Points for Baghdad FIR



ENR 3.4 HELICOPTER ROUTES

There are no designated helicopter routes in the Baghdad FIR.

ENR 3.5 OTHER ROUTES

3.5.1 Mandatory Routing: Flights originating and landing within the Baghdad FIR will plan their routing based on the current ATS route structure advising ATC of their intended clearance. ATC will approve or amend these clearances as required. Aircraft operators intending to land in Iraq are to flight plan to and from the airports via the mandatory routes listed below. All aircraft shall navigate on the route centerline. No offset tracking is allowed. Deviations shall not be made without the prior approval of the controlling ATC facility. Levels shall be as instructed by ATC

3.5.1.2 Bordering countries have commenced using RVSM procedures however RVSM is not approved in Iraq. The Iraq ACCs will continue to provide 2,000FT vertical separation for all aircraft above FL290. In some instances RVSM levels may be used in Iraq however this is to ensure that aircraft are not transferred between RVSM and non-RVSM altitudes when entering and exiting the Baghdad FIR. At all times ATC is required to ensure that 2000FT vertical separation exists if a lateral, radar or longitudinal standard can not be guaranteed. The mandatory routings to approved airports are as detailed below:

3.5.2 From KUWAIT to:

Bashur Airport: From TASMI (N30°01.3' E47°55.1') via L602 to ALPET (N31°12.3' E46°18.7') then direct to NOLDO (N32°49.5' E45°21.5') then via R784 to KATOT (N36°00.0 E43°27.0) then direct to ORBR.

Mosul Airport: From TASMI (N30°01.3' E47°55.1') via L602 to ALPET (N31°12.3' E46°18.7') then direct to NOLDO (N32°49.5' E45°21.5') then via R784 to KATOT (N36°00.0 E43°27.0) then direct to ORBM.

Kirkuk Airport: From TASMI (N30°01.3' E47°55.1') via L602 to ALPET (N31°12.3' E46°18.7') then direct to NOLDO (N32°49.5' E45°21.5') then via R784 to RAMPI (N35°16.7' E43°56.3') then direct to ORKK.

Sulaymaniyah International Airport: From TASMI (N30°01.3' E47°55.1') via L602 to ALPET (N31°12.3' E46°18.7') then direct to NOLDO (N32°49.5' E45°21.5') then via R784 to RAMPI (N35°16.7' E43°56.3') then direct to ORSU.

Erbil International Airport: From TASMI (N30°01.3' E47°55.1') via L602 to ALPET (N31°12.3' E46°18.7') then direct to NOLDO (N32°49.5' E45°21.5') then via R784 to KATOT (N36°00.0 E43°27.0) then direct to ORER.

Baghdad International Airport: From TASMI (N30°01.3' E47°55.1') via L602 to LOVEK (N32°22.1' E44°40.0') then via L417 direct to ORBI.

Basrah International Airport: From TASMI (N30°01.3' E47°55.1') via G795 direct to ORMM.

Ali Base Airport: From TASMI (N30°01.3' E47°55.1') via L602 to ALPET (N31°12.3' E46°18.7') then direct to ORTL.

Al Asad Airport: From TASMI (N30°01.3' E47°55.1') then via L602 to LOVEK (N32°22.1' E44°40.0') then via M203 to PUSTO (N33°21.0' E42°45.0') then direct to ORAA.

Al Taqaddum Airport: From TASMI (N30°01.3' E47°55.1') then via L602 to LOVEK (N32°22.1' E44°40.0') then via M203 to PUSTO (N33°21.0' E42°45.0') then direct to ORAT.

Balad Airport: From TASMI (N30°01.3' E47°55.1') via L602 to ALPET (N31°12.3' E46°18.7') then direct to NOLDO (N32°49.5' E45°21.5') then via R784 to SIGNI (N34°00.0' E44°42.0') then direct to ORBD.

3.5.3 From TURKEY to:

Bashur Airport: From KABAN (N37°14.9' E42°39.0') via R784 to KATOT (N36°00.0' E43°27.0') then direct to ORBR.

Mosul Airport: From KABAN (N37°14.9' E42°39.0') via R784 direct to ORBM.

Kirkuk Airport: From KABAN (N37°14.9' E42°39.0') via R784 to KATOT (N36°00.0' E43°27.0') then direct to ORKK.

Sulaymaniyah International Airport: From KABAN (N37°14.9' E42°39.0') via R784 to RAMPI (N35°16.7' E43°56.3') then direct to ORSU.

Erbil International Airport: From KABAN (N37°14.9' E42°39.0') via R784 to KATOT (N36°00.0' E43°27.0') then direct to ORER.

Baghdad International Airport: From KABAN (N37°14.9' E42°39.0') via R784 to RAMPI (N35°16.7' E43°56.3') then via L417 direct to ORBI.

Basrah International Airport: From KABAN (N37°14.9' E42°39.0') via R784 to NOLDO (N32°49.5' E45°21.5') then via P975 to ILMAP (N31°21.5' E46°57.0') then direct to ORMM.

Ali Base Airport: From KABAN (N37°14.9' E42°39.0') via R784 to NOLDO (N32°49.5' E45°21.5') then via P975 to ILMAP (N31°21.5' E46°57.0') then direct to ORTL.

Al Asad Airport: From KABAN (N37°14.9' E42°39.0') via R784 to RAMPI (N35°16.7' E43°56.3') then via L417 to SOGUM (N34°12.2' E43°54.9') then via L126 to PUSTO (N33°21.0' E42°45.0') then direct to ORAA.

Al Taqaddum Airport: From KABAN (N37°14.9' E42°39.0') via R784 to RAMPI (N35°16.7' E43°56.3') then via L417 to SOGUM (N34°12.2' E43°54.9') then via L126 to PUSTO (N33°21.0' E42°45.0') then direct to ORAT.

Balad Airport: From KABAN (N37°14.9' E42°39.0') via R784 to RAMPI (N35°16.7' E43°56.3') then via L417 to SOGUM (N34°12.2' E43°54.9') then direct to ORBD.

3.5.4 From JORDAN to:

Bashur Airport: From PASIP (N33°00.0' E38°55.2') via L200 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0' E42°45.0') then via L126 to SOGUM (N34°12.2' E43°54.9) then via L417 to RAMPI (N35°16.7' E43°56.3') then via R784 to KATOT (N36°00.0' E43°27.0') then direct to ORBR.

Mosul Airport: From PASIP (N33°00.0' E38°55.2') via L200 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0' E42°45.0') then via L126 to SOGUM (N34°12.2' E43°54.9) then via L417 to RAMPI (N35°16.7' E43°56.3') then via R784 to KATOT (N36° 00.0' E43° 27.0') then direct to ORBM.

Kirkuk Airport: From PASIP (N33°00.0' E38°55.2') via L200 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0' E42°45.0') then via L126 to SOGUM (N34°12.2' E43°54.9) then via L417 to RAMPI (N35°16.7' E43°56.3') then direct to ORKK.

Sulaymaniyah International Airport: From PASIP (N33°00.0' E38°55.2') via L200 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0' E42°45.0') then via L126 to SOGUM (N34°12.2' E43°54.9) then via L417 to RAMPI (N35°16.7' E43°56.3') then direct to ORSU.

Erbil International Airport: From PASIP (N33°00.0' E38°55.2') via L200 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0' E42°45.0') then via L126 to SOGUM (N34°12.2' E43°54.9) then via L417 to RAMPI (N35°16.7' E43°56.3') then via R784 to KATOT (N36° 00.0' E43° 27.0') then direct to ORER.

Baghdad International Airport: From PASIP (N33°00.0' E38°55.2') via L200 to RAPLU (N33°23.0' E41°45.5') then via G202 to ORBI.

Basrah International Airport: From PASIP (N33°00.0' E38°55.2') via L200 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0' E42°45.0') then via M203 to LOVEK then direct to ILMAP (N31°21.5' E46°57.0') then direct to ORMM.

Ali Base Airport: From PASIP (N33°00.0' E38°55.2') via L200 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0' E42°45.0') then via M203 to LOVEK (N32°22.1' E44°40.0') then direct to ILMAP (N31°21.5' E46°57.0') then direct to Ali Base Airport.

Al Asad Airport: From PASIP (N33°00.0' E38°55.2') via L200 to RAPLU (N33°23.0' E41°45.5') then direct to ORAA.

Al Taqaddum Airport: the From PASIP (N33°00.0' E38°55.2') via L200 to RAPLU (N33°23.0' E41°45.5') then direct to ORAA.

Balad Airport: From PASIP (N33°00.0' E38°55.2') via L200 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0' E42°45.0') then via L126 to SOGUM (N34°12.2' E43°54.9) then direct to ORBD.

3.5.5 From SYRIA to:

Bashur Airport: From MODIK (N33°28.1' E39°01.0') via G202 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0 E42°45.0) then via L126 to SOGUM (N34°12.2' E43°54.9) then via L417 to RAMPI (N35°16.7' E43°56.3') then via R784 to KATOT (N36° 00.0' E43° 27.0') then direct to ORBR.

Mosul Airport: From MODIK (N33°28.1' E39°01.0') via G202 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0 E42°45.0) then via L126 to SOGUM (N34°12.2' E43°54.9) then via L417 to RAMPI (N35°16.7' E43°56.3') then via R784 to KATOT (N36°00.0' E43°27.0') then direct to ORBM.

Kirkuk Airport: From MODIK (N33°28.1' E39°01.0') via G202 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0 E42°45.0) then via L126 to SOGUM (N34°12.2' E43°54.9) then via L417 to RAMPI (N35°16.7' E43°56.3') then direct to ORKK.

Sulaymaniyah International Airport: From MODIK (N33°28.1' E39°01.0') via G202 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0 E42°45.0) then via L126 to SOGUM (N34°12.2' E43°54.9) then via L417 to RAMPI (N35°16.7' E43°56.3') then direct to ORSU.

Erbil International Airport: From MODIK (N33°28.1' E39°01.0') via G202 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0 E42°45.0) then via L126 to SOGUM (N34°12.2' E43°54.9) then via L417 to RAMPI (N35°16.7' E43°56.3') then via R784 to KATOT (N36° 00.0' E43° 27.0') then direct to ORER.

Baghdad International Airport: From MODIK (N33°28.1' E39°01.0') via G202 to PUSTO (N33°21.0 E42°45.0) then as directed by ATC to ORBI.

Basrah International Airport: From MODIK (N33°28.1' E39°01.0') via G202 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0 E42°45.0) then via L126 to SIGNI (N34°00.0' E44°42.0') then via R784 to NOLDO (N32°49.5' E45°21.5') then via P975 to ILMAP (N31°21.5' E46°57.0') then direct to ORMM.

Ali Base Airport: From MODIK (N33°28.1' E39°01.0') via G202 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0 E42°45.0) then via L126 to SIGNI (N34°00.0' E44°42.0') then via R784 to NOLDO (N32°49.5' E45°21.5') then via P975 to ILMAP (N31°21.5' E46°57.0') then direct to ORTL.

Al Asad Airport: From MODIK (N33°28.1' E39°01.0') via G202 to RAPLU (N33°23.0' E41°45.5') then direct to ORAA.

Al Taqaddum Airport: From MODIK (N33°28.1' E39°01.0') via G202 to RAPLU (N33°23.0' E41°45.5') then direct to ORAT.

Balad Airport: From MODIK (N33°28.1' E39°01.0') via G202 to RAPLU (N33°23.0' E41°45.5') then via G202 to PUSTO (N33°21.0 E42°45.0) then via L126 to SOGUM (N34°12.2' E43°54.9) then direct to ORBD.

3.5.6 From IRAN to:

Bashur Airport: From MIGMI (N33°45.9' E45°27.4') via L126 to SIGNI (N34°00.0' E44°42.0') then via R784 to KATOT (N36° 00.0' E43° 27.0') then direct to ORBR.

Mosul Airport: From MIGMI (N33°45.9' E45°27.4') via L126 to SIGNI (N34°00.0' E44°42.0') then via R784 to KATOT (N36°00.0' E43°27.0') then direct to ORBM.

Kirkuk Airport: From MIGMI (N33°45.9' E45°27.4') via L126 to SIGNI (N34°00.0' E44°42.0') then via R784 to RAMPI (N35°16.7' E43°56.3') then direct to ORKK.

Sulaymaniyah International Airport: From MIGMI (N33°45.9' E45°27.4') via L126 to SIGNI (N34°00.0' E44°42.0') then via R784 to RAMPI (N35°16.7' E43°56.3') then direct to ORSU.

Erbil International Airport: From MIGMI (N33°45.9' E45°27.4') via L126 to SIGNI (N34°00.0' E44°42.0') then via R784 to KATOT (N36°00.0' E43°27.0') then direct to ORER.

Baghdad International Airport: From RAGET (N33°30.8' E45°53.8') via G202 to ORBI.

Basrah International Airport: From RAGET (N33°30.8' E45°53.8') via G202 to PARUN (N33°24.2' E45°02.0') then via R784 to NOLDO (N32°49.5' E45°21.5') then via P975 to ILMAP (N31°21.5' E46°57.0') then direct to ORMM.

3.5.7 From SAUDI ARABIA to:

Bashur Airport: From MURIB (N31°12.6' E41°50.6') via B411 to NOLDO (N32°49.5' E45°21.5') then via R784 to KATOT (N36°00.0' E43°27.0') then direct to ORBR.

Mosul Airport: From MURIB (N31°12.6' E41°50.6') via B411 to NOLDO (N32°49.5' E45°21.5') then via R784 to KATOT (N36°00.0' E43°27.0') then direct to ORBM.

Kirkuk Airport: From MURIB (N31°12.6' E41°50.6') via B411 to NOLDO (N32°49.5' E45°21.5') then via R784 to RAMPI (N35°16.7' E43°56.3'E) then direct to ORKK.

Sulaymaniyah International Airport: From MURIB (N31°12.6' E41°50.6') via B411 to NOLDO (N32°49.5' E45°21.5') then via R784 to RAMPI (N35°16.7' E43°56.3'E) then direct to ORSU.

Erbil International Airport: From MURIB (N31°12.6' E41°50.6') via B411 to NOLDO (N32°49.5' E45°21.5') then via R784 to KATOT (N36°00.0' E43°27.0') then direct to ORER.

Baghdad International Airport: From MURIB (N31°12.6' E41°50.6') via B411 to LOVEK (N32°22.1' E44°40.0') then via L417 direct to ORBI.

Al Asad Airport: From MURIB (N31°12.6' E41°50.6') via B411 to LOVEK (N32°22.1' E44°40.0') then via M203 to P975 (N33°21.0' E42°45.5') then direct to ORAA.

Al Taqaddum Airport: From MURIB (N31°12.6' E41°50.6') via B411 to LOVEK (N32°22.1' E44°40.0') then via M203 to PUS O (N33°13.8' E42°45.9') then direct to ORAT.

Balad Airport: From MURIB (N31°12.6' E41°50.6') via B411 to LOVEK (N32°22.1' E44°40.0') then via L417 to SOGUM (N34°12.2' E43°54.0') then direct to ORBD.

ENR 3.6 ENROUTE HOLDING

There are no enroute holding patterns published in the Baghdad FIR. However, if necessary, such as to establish the required longitudinal separation standard, enroute aircraft may be instructed to hold at one of the designated enroute reporting points. The holding procedures shall be a standard 180 degree right turn to fly outbound on the reciprocal track for one minute then conduct a standard 180 degree right turn to intercept the inbound track to overhead the holding point. ICAO Doc 8168-PAN-OPS refers.

ENR 4. RADIO NAVIGATION AIDS/ SYSTEMS**ENR 4.1 RADIO NAVIGATION AIDS - EN-ROUTE**

Name of station	ID	FREQ and Channel	Hours of operation	Coordinates	Remarks
Al Asad TACAN	MAA	CH57X	H24	N33°47.24' E42°26.6'	VAR 4°E
Al Taqaddum TACAN	MAT	CH70X	H24	N33°20.37' E43°35.64'	VAR 4°E
Baghdad TACAN	BGD	CH43X	H24	N33°15.61' E44°14.97'	VAR 4°E
Baghdad VOR	BGD	110.6MHz	H24	N33°15.64' E44°14.95'	VAR 4°E
Balad SE VORTAC	BLD	CH93X/114.6	H24	N33°56.15' E44°22.08'	VAR 4°E
Basrah TACAN	BAR	CH20	H24	N30°32.93' E47°39.59'	VAR 3°E
Basrah VOR	BSR	CH70X/112.3	H24	N30°31.54' E47°41.20'	VAR 3°E
Kirkuk TACAN	KRK	CH 86X	H24	N35°28.27' E44°20.87'	VAR 4°E
Ali Base TACAN	TAL	CH 84X	H24	N30°56.12' E46°05.44'	VAR 3°E

ENR 4.2 SPECIAL NAVIGATION SYSTEM

There are no special navigation system facilities established in the Baghdad FIR. Note the RNP5 requirements described at GEN 1.5.2.

ENR 4.3 NAME – CODE DESIGNATORS FOR SIGNIFICANT POINTS

Significant points for the Baghdad FIR are listed at ENR 3.3 in the table describing Air Navigation Routes.

ENR 4.4 AERONAUTICAL GROUND LIGHTS—ENROUTE

There are no aeronautical ground lights - enroute in the Baghdad FIR.

ENR 5. NAVIGATION WARNINGS

ENR 5.1 PROHIBITED, RESTRICTED AND DANGER AREAS

5.1.1 All airspace outside the air routes and terminal areas described in this AIP are to be regarded as prohibited areas. Failure to comply with the procedures in this AIP may result in interception by armed coalition fighter aircraft.

5.1.2 The following additional prohibited areas have been established:

5.1.2.1 ORP1, a circle of 0.2 NM radius centered on N33°18'43.00" E044°23'33.00"; SFC – 3000 FT AMSL.

**ENR 5.2 MILITARY EXERCISE AND TRAINING AREAS AND AIR DEFENCE
IDENTIFICATION ZONE**

Not yet published.

**ENR 5.3 OTHER ACTIVITIES OF A DANGEROUS NATURE AND OTHER
POTENTIAL HAZARDS**

All operators are advised that non-military operations could be at significant risk because of ongoing military operations in Iraq. There are continuing reports of indiscriminate small arms and missile attacks on aircraft operating in Iraq, primarily at low altitudes. Therefore, operators that undertake flights within the Baghdad FIR shall do so at their own risk. Compliance with AIP procedures is mandatory; safety of aircraft operating in the Baghdad FIR requires strict adherence to AIP procedures. Failure to comply with the procedures in this AIP may result in interception by armed coalition fighter aircraft.

ENR 5.4 AIR NAVIGATION OBSTACLES - ENROUTE

Air navigational obstacles - enroute have not yet been surveyed in the Baghdad FIR.

ENR 5.5 AERIAL SPORTING AND RECREATIONAL ACTIVITIES

There are no known aerial sporting or recreational activities affecting the Baghdad FIR.

ENR 5.6 BIRD MIGRATION AND AREAS WITH SENSITIVE FAUNA

Historical bird/wildlife activity and migration data is not available. However, an increase in bird and wildlife activity has been observed near RWYs at Baghdad and Kirkuk within +/- one hour of sunrise and sunset. Exercise caution when arriving and departing during these periods.

ENR 6 ENROUTE CHART - ICAO

Enroute Chart – ICAO is not yet established for the Baghdad FIR. Operators should refer to the airspace dimensions described at ENR 2.1 and the routes described at ENR 3.3 and ENR 3.5 for guidance.

**PART 3
AERODROMES (AD)**

PART 3 AERODROMES (AD)**AD 0**

AD 0.1	PREFACE - Not applicable
AD 0.2	RECORD OF AIP AMENDMENT - Not applicable
AD 0.3	RECORD OF SUPPLEMENTS - Not applicable
AD 0.4	CHECKLIST OF AIP PAGES - Not applicable
AD 0.5	LIST OF HAND AMENDMENT TO THE AIP - Not applicable

AD 0.6 TABLE OF CONTENTS TO PART 3**AD 1 AERODROMES – INTRODUCTION**

	Page
AD 1.1 Aerodrome/heliport availability	AD 1.1-1
AD 1.2 Rescue and fire fighting service	AD 1.2-1
AD 1.3 Index to aerodromes	AD 1.2-1

AD 2 AERODROMES**ORAA – Al Asad Airport**

ORAA AD 2.1	Aerodrome location indicator and name	AD 2.1-1
ORAA AD 2.2	Aerodrome geographical and administrative data	AD 2.1-1
ORAA AD 2.3	Operational Hours	AD 2.1-1
ORAA AD 2.4	Handling Facilities and Services	AD 2.1-2
ORAA AD 2.5	Passenger Facilities	AD 2.1-3
ORAA AD 2.6	Rescue and fire fighting services	AD 2.1-3
ORAA AD 2.7	Seasonal availability	AD 2.1-3
ORAA AD 2.8	Aprons, taxiways and check locations/positions data	AD 2.1-4
ORAA AD 2.9	Surface movement guidance and control system and markings	AD 2.1-4
ORAA AD 2.10	Aerodrome obstacles	AD 2.1-4
ORAA AD 2.11	Meteorological information provided.....	AD 2.1-4
ORAA AD 2.12	RWY physical characteristics	AD 2.1-4
ORAA AD 2.13	Approach and RWY Lighting	AD 2.1-7
ORAA AD 2.14	Air Traffic Services Communications Facilities	AD 2.1-8
ORAA AD 2.15	Local Traffic Regulations	AD 2.1-8

ORAI – Al Iskandarariyah New Airport

ORAI AD 2.1	Aerodrome location indicator and name	AD 2.1-9
ORAI AD 2.2	Aerodrome Geographical and Administrative Data ...	AD 2.1-9
ORAI AD 2.12	RWY physical characteristics	AD 2.1-9

ORAT – Al Taqaddum Airport

ORAT AD 2.1	Aerodrome location indicator and name	AD 2.1-10
ORAT AD 2.2	Aerodrome geographical and administrative data	AD 2.1-10
ORAT AD 2.3	Operational Hours	AD 2.1-10
ORAT AD 2.4	Handling Facilities and Services	AD 2.1-11
ORAT AD 2.5	Passenger Facilities	AD 2.1-12
ORAT AD 2.6	Rescue and fire fighting services	AD 2.1-12
ORAT AD 2.7	Seasonal availability	AD 2.1-12

ORAT AD 2.8	Aprons, taxiways and check locations/positions data ...	AD 2.1-13
ORAT AD 2.9	Surface movement guidance and control system and markings	AD 2.1-13
ORAT AD 2.10	Aerodrome obstacles	AD 2.1-13
ORAT AD 2.11	Meteorological information provided.....	AD 2.1-13
ORAT AD 2.12	RWY physical characteristics	AD 2.1-13
ORAT AD 2.13	Air Traffic Services Communication	AD 2.1-14

ORAN – An Numaniyah Airport

ORAN AD 2.1	Aerodrome location indicator and name	AD 2.1-15
ORAN AD 2.2	RWY physical characteristics	AD 2.1-15
ORAN AD 2.12	RWY Physical Characteristics	AD 2.1-15

ORBI – Baghdad International Airport

ORBI AD 2.1	Aerodrome location indicator and name	AD 2.1-16
ORBI AD 2.2	Aerodrome geographical and administrative data.....	AD 2.1-16
ORBI AD 2.3	Operational hours	AD 2.1-17
ORBI AD 2.4	Handling services and facilities	AD 2.1-18
ORBI AD 2.5	Passenger facilities	AD 2.1-18
ORBI AD 2.6	Rescue and fire fighting services	AD 2.1-19
ORBI AD 2.7	Seasonal availability	AD 2.1-19
ORBI AD 2.8	Aprons, taxiways and check locations/positions data....	AD 2.1-19
ORBI AD 2.9	Surface movement guidance and control system and markings	AD 2.1-20
ORBI AD 2.10	Aerodrome obstacles	AD 2.1-20
ORBI AD 2.11	Meteorological information provided.....	AD 2.1-21
ORBI AD 2.12	RWY physical characteristics	AD 2.1-21
ORBI AD 2.13	Declared distance	AD 2.1-21
ORBI AD 2.14	Approach and RWY lighting	AD 2.1-22
ORBI AD 2.15	Other lighting, secondary power supply	AD 2.1-22
ORBI AD 2.16	Helicopter landing area	AD 2.1-22
ORBI AD 2.17	ATS airspace	AD 2.1-23
ORBI AD 2.18	ATS communication facilities	AD 2.1-23
ORBI AD 2.19	Radio navigation and landing aids	AD 2.1-24
ORBI AD 2.20	Local traffic regulations	AD 2.1-25
ORBI AD 2.21	Noise abatement procedures	AD 2.1-25
ORBI AD 2.22	Flight procedures	AD 2.1-26
ORBI AD 2.23	Additional information.....	AD 2.1-26
ORBI AD 2.24	Charts related to an aerodrome	AD 2.1-26

ORBD – Balad Southeast Airport

ORBD AD 2.1	Aerodrome location indicator and name	AD 2.1-28
ORBD AD 2.2	Aerodrome geographical and administrative data	AD 2.1-28
ORBD AD 2.3	Operational hours	AD 2.1-28
ORBD AD 2.4	Handling services and facilities	AD 2.1-29
ORBD AD 2.5	Passenger facilities	AD 2.1-30
ORBD AD 2.6	Rescue and fire fighting services	AD 2.1-30
ORBD AD 2.7	Seasonal availability	AD 2.1-30
ORBD AD 2.8	Aprons, taxiways and check locations/positions data...	AD 2.1-30
ORBD AD 2.9	Surface movement guidance and control system and markings	AD 2.1-30

ORBD AD 2.10	Aerodrome obstacles	AD 2.1-31
ORBD AD 2.11	Meteorological information provided	AD 2.1-31
ORBD AD 2.12	RWY physical characteristics	AD 2.1-31
ORBD AD 2.13	Declared distance	AD 2.1-32
ORBD AD 2.14	Approach and RWY lighting	AD 2.1-33
ORBD AD 2.15	Other lighting, secondary power supply	AD 2.1-33
ORBD AD 2.16	Helicopter landing area	AD 2.1-33
ORBD AD 2.17	ATS airspace	AD 2.1-33
ORBD AD 2.18	ATS communication facilities	AD 2.1-34
ORBD AD 2.19	Radio navigation and landing aids	AD 2.1-34
ORBD AD 2.20	Local traffic regulations	AD 2.1-34
ORBD AD 2.21	Noise abatement procedures	AD 2.1-35
ORBD AD 2.22	Flight procedures	AD 2.1-36
ORBD AD 2.23	Additional information.....	AD 2.1-37
ORBD AD 2.24	Charts related to an aerodrome	AD 2.1-37

ORBR - Bashur Airport

ORBR AD 2.1	Aerodrome location indicator and name	AD 2.1-38
-------------	---	-----------

ORMM - Basrah International Airport

ORMM AD 2.1	Aerodrome location indicator and name	AD 2.1-39
ORMM AD 2.2	Aerodrome geographical and administrative data	AD 2.1-39
ORMM AD 2.3	Operational hours	AD 2.1-39
ORMM AD 2.4	Handling services and facilities	AD 2.1-40
ORMM AD 2.5	Passenger facilities	AD 2.1-41
ORMM AD 2.6	Rescue and fire fighting services	AD 2.1-41
ORMM AD 2.7	Seasonal availability	AD 2.1-42
ORMM AD 2.8	Aprons, taxiways and check locations/positions data.....	AD 2.1-42
ORMM AD 2.9	Surface movement guidance and control system and markings	AD 2.1-42
ORMM AD 2.10	Aerodrome obstacles	AD 2.1-42
ORMM AD 2.11	Meteorological information provided	AD 2.1-42
ORMM AD 2.12	RWY physical characteristics	AD 2.1-43
ORMM AD 2.13	Declared distances	AD 2.1-43
ORMM AD 2.14	Approach and RWY lighting	AD 2.1-43
ORMM AD 2.15	Other lighting, secondary power supply	AD 2.1-44
ORMM AD 2.16	Helicopter landing area	AD 2.1-45
ORMM AD 2.17	ATS airspace	AD 2.1-45
ORMM AD 2.18	ATS communication facilities	AD 2.1-45
ORMM AD 2.19	Radio navigation and landing aids	AD 2.1-45
ORMM AD 2.20	Local traffic regulations	AD 2.1-46
ORMM AD 2.21	Noise abatement procedures	AD 2.1-46
ORMM AD 2.22	Flight procedures	AD 2.1-46
ORMM AD 2.23	Additional Information	AD 2.1-47
ORMM AD 2.24	Charts related to an aerodrome	AD 2.1-47

ORER – Erbil International Airport

ORER AD 2.1	Aerodrome location indicator and name	AD 2.1-48
ORER AD 2.2	Aerodrome geographical and administrative data	AD 2.1-48
ORER AD 2.3	Operational Hours	AD 2.1-48
ORER AD 2.4	Handling Services and Facilities.....	AD 2.1-49

ORER AD 2.5	Passenger Facilities.....	AD 2.1-49
ORER AD 2.6	Rescue and Fire Fighting Services.....	AD 2.1-49
ORER AD 2.7	Seasonal Availability	AD 2.1-49
ORER AD 2.8	Aprons, Taxiways and Check Locations/Positions Data.	AD 2.1-49
ORER AD 2.9	Surface Movement Guidance and Control System and Markings	AD 2.1-50
ORER AD 2.12	RWY physical characteristics	AD 2.1-50
ORER AD 2.14	Approach and RWY Lighting	AD 2.1-51
ORER AD 2.15	Other Lighting, Secondary Power Supply	AD 2.1-51
ORER AD 2.17	Air Traffic Services Airspace	AD 2.1-52
ORER AD 2.18	Air Traffic Services Communication Facilities	AD 2.1-52

ORJA – Jalibah Southeast Airport

ORJA AD 2.1	Aerodrome location indicator and name	AD 2.1-53
ORJA AD 2.2	Aerodrome Geographical and Administrative Data	AD 2.1-53
ORJA AD 2.3	RWY Physical Characteristics	AD 2.1-53

ORKK - Kirkuk Airport

ORKK AD 2.1	Aerodrome location indicator and name	AD 2.1-54
ORKK AD 2.2	Aerodrome Geographical and Administrative Data	AD 2.1-54
ORKK AD 2.3	Operational hours	AD 2.1-54
ORKK AD 2.4	Handling services and facilities	AD 2.1-55
ORKK AD 2.5	Passenger facilities	AD 2.1-56
ORKK AD 2.6	Rescue and fire fighting services	AD 2.1-56
ORKK AD 2.7	Seasonal availability	AD 2.1-56
ORKK AD 2.8	Aprons, taxiways and check locations/positions data	AD 2.1-56
ORKK AD 2.9	Surface movement guidance and control system and markings	AD 2.1-57
ORKK AD 2.10	Aerodrome obstacles	AD 2.1-57
ORKK AD 2.11	Meteorological information provided	AD 2.1-58
ORKK AD 2.12	RWY physical characteristics	AD 2.1-58
ORKK AD 2.13	Declared distances	AD 2.1-59
ORKK AD 2.14	Approach and RWY lighting	AD 2.1-59
ORKK AD 2.15	Other lighting, secondary power supply	AD 2.1-60
ORKK AD 2.16	Helicopter landing area	AD 2.1-60
ORKK AD 2.17	ATS airspace	AD 2.1-60
ORKK AD 2.18	ATS communication facilities	AD 2.1-61
ORKK AD 2.19	Radio navigation and landing aids	AD 2.1-61
ORKK AD 2.20	Local traffic regulations	AD 2.1-62
ORKK AD 2.21	Noise abatement procedures	AD 2.1-62
ORKK AD 2.22	Flight procedures	AD 2.1-63
ORKK AD 2.23	Additional Information	AD 2.1-63
ORKK AD 2.24	Charts related to an aerodrome	AD 2.1-63

ORBM – Mosul Airport

ORBM AD 2.1	Aerodrome location indicator and name	AD 2.1-65
ORBM AD 2.2	Aerodrome geographical and administrative data	AD 2.1-65
ORBM AD 2.3	Operational hours	AD 2.1-65
ORBM AD 2.4	Handling services and facilities	AD 2.1-66
ORBM AD 2.5	Passenger facilities	AD 2.1-66
ORBM AD 2.6	Rescue and fire fighting services	AD 2.1-66

ORBM AD 2.7	Seasonal availability	AD 2.1-67
ORBM AD 2.8	Aprons, taxiways and check locations/positions data	AD 2.1-67
ORBM AD 2.9	Surface movement guidance and control system and markings	AD 2.1-67
ORBM AD 2.10	Aerodrome obstacles	AD 2.1-68
ORBM AD 2.11	Meteorological information provided	AD 2.1-68
ORBM AD 2.12	RWY physical characteristics	AD 2.1-68
ORBM AD 2.13	Declared distances	AD 2.1-69
ORBM AD 2.14	Approach and RWY lighting	AD 2.1-69
ORBM AD 2.15	Other lighting, secondary power supply	AD 2.1-70
ORBM AD 2.16	Helicopter landing area	AD 2.1-70
ORBM AD 2.17	ATS airspace	AD 2.1-70
ORBM AD 2.18	ATS communication facilities	AD 2.1-70
ORBM AD 2.19	Radio navigation and landing aids	AD 2.1-71
ORBM AD 2.20	Local traffic regulations	AD 2.1-71
ORBM AD 2.21	Noise abatement procedures	AD 2.1-71
ORBM AD 2.22	Flight procedures	AD 2.1-72
ORBM AD 2.23	Additional Information	AD 2.1-72
ORBM AD 2.24	Charts related to an aerodrome	AD 2.1-72

ORQT – Qasr Tall Mihil Airport

ORQT AD 2.1	Aerodrome location indicator and name	AD 2.1-74
ORQT AD 2.2	Aerodrome geographical and administrative data	AD 2.1-74

ORQW – Qayyarah West Airport

ORQW AD 2.1	Aerodrome location indicator and name	AD 2.1-75
ORQW AD 2.2	Aerodrome geographical and administrative data	AD 2.1-75
ORQW AD 2.12	RWY Physical Characteristics	AD 2.1-75
ORQW AD 2.18	Air Traffic Services Communication Facilities	AD 2.1-75

ORSH - Al Sahra Airport

ORSH AD 2.1	Aerodrome location indicator and name.....	AD 2.1-76
ORSH AD 2.2	Aerodrome geographical and administrative data .	AD 2.1-76
ORSH AD 2.3	Operational Hours	AD 2.1-76
ORSH AD 2.4	Handling Services and Facilities	AD 2.1-77
ORSH AD 2.5	Passenger facilities	AD 2.1-77
ORSH AD 2.6	Rescue and fire fighting services	AD 2.1-77
ORSH AD 2.7	Seasonal availability	AD 2.1-77
ORSH AD 2.8	Aprons, taxiways and check locations/positions data	AD 2.1-77
ORSH AD 2.9	Surface movement guidance and control system and markings	AD 2.1-78
ORSH AD 2.10	Aerodrome obstacles	AD 2.1-78
ORSH AD 2.11	Meteorological Information Provided.....	AD 2.1-78
ORSH AD 2.12	RWY Physical Characteristics	AD 2.1-78
ORSH AD 2.13	Declared distances	AD 2.1-79
ORSH AD 2.14	Approach and RWY Lighting	AD 2.1-79
ORSH AD 2.15	Other lighting, secondary power supply	AD 2.1-79
ORSH AD 2.16	Helicopter landing area	AD 2.1-79
ORSH AD 2.17	ATS airspace	AD 2.1-80
ORSH AD 2.18	ATS communication facilities	AD 2.1-80
ORSH AD 2.19	Radio navigation and landing aids	AD 2.1-80

ORSH AD 2.20	Local traffic regulations	AD 2.1-80
ORSH AD 2.21	Noise abatement procedures	AD 2.1-81
ORSH AD 2.22	Flight procedures	AD 2.1-81
ORSH AD 2.23	Additional Information	AD 2.1-81

ORSU – Sulaymaniyah International Airport

ORSU AD 2.1	Aerodrome location indicator and name	AD 2.1-82
ORSU AD 2.2	Aerodrome geographical and administrative data	AD 2.1-82
ORSU AD 2.3	Operational Hours	AD 2.1-82
ORSU AD 2.4	Handling Services and Facilities.....	AD 2.1-83
ORSU AD 2.5	Passenger Facilities.....	AD 2.1-83
ORSU AD 2.6	Rescue and Fire Fighting Services.....	AD 2.1-83
ORSU AD 2.7	Seasonal Availability	AD 2.1-83
ORSU AD 2.8	Aprons, Taxiways and Check Locations/Positions Data.	AD 2.1-84
ORSU AD 2.9	Surface Movement Guidance and Control System and Markings	AD 2.1-84
ORSU AD 2.12	RWY physical characteristics	AD 2.1-85
ORSU AD 2.14	Approach and RWY Lighting	AD 2.1-85
ORSU AD 2.15	Other Lighting, Secondary Power Supply	AD 2.1-86
ORSU AD 2.17	Air Traffic Services Airspace	AD 2.1-86
ORSU AD 2.18	Air Traffic Services Communication Facilities	AD 2.1-86
ORSU AD 2.19	Radio Navigation and Landing Aids	AD 2.1-87

ORTF – Tall Afar Airport

ORTF AD 2.1	Aerodrome location indicator and name	AD 2.1-88
ORTF AD 2.2	Aerodrome geographical and administrative data	AD 2.1-88
ORTF AD 2.3	Operational hours	AD 2.1-88
ORTF AD 2.4	Handling services and facilities	AD 2.1-89
ORTF AD 2.5	Passenger facilities	AD 2.1-89
ORTF AD 2.6	Rescue and fire fighting services	AD 2.1-89
ORTF AD 2.7	Seasonal availability	AD 2.1-89
ORTF AD 2.8	Aprons, taxiways and check locations/positions data	AD 2.1-89
ORTF AD 2.9	Surface movement guidance and control system and markings	AD 2.1-90
ORTF AD 2.10	Aerodrome obstacles	AD 2.1-90
ORTF AD 2.11	Meteorological information provided	AD 2.1-90
ORTF AD 2.12	RWY physical characteristics	AD 2.1-90
ORTF AD 2.13	Declared distances	AD 2.1-91
ORTF AD 2.14	Approach and RWY lighting	AD 2.1-91
ORTF AD 2.15	Other lighting, secondary power supply	AD 2.1-92
ORTF AD 2.16	Helicopter landing area	AD 2.1-93
ORTF AD 2.17	ATS airspace	AD 2.1-93
ORTF AD 2.18	ATS communication facilities	AD 2.1-93
ORTF AD 2.19	Radio navigation and landing aids	AD 2.1-93
ORTF AD 2.20	Local traffic regulations	AD 2.1-93
ORTF AD 2.21	Noise abatement procedures	AD 2.1-94
ORTF AD 2.22	Flight procedures	AD 2.1-94
ORTF AD 2.23	Additional Information	AD 2.1-94
ORTF AD 2.24	Charts related to an aerodrome	AD 2.1-94

ORTL – Ali Base Airport

ORTL AD 2.1	Aerodrome location indicator and name	AD 2.1-95
ORTL AD 2.2	Aerodrome geographical and administrative data	AD 2.1-95
ORTL AD 2.3	Operational hours	AD 2.1-95
ORTL AD 2.4	Handling services and facilities	AD 2.1-96
ORTL AD 2.5	Passenger facilities	AD 2.1-97
ORTL AD 2.6	Rescue and fire fighting services	AD 2.1-97
ORTL AD 2.7	Seasonal availability	AD 2.1-97
ORTL AD 2.8	Aprons, taxiways and check locations/positions data	AD 2.1-97
ORTL AD 2.9	Surface movement guidance and control system and markings	AD 2.1-98
ORTL AD 2.10	Aerodrome obstacles	AD 2.1-98
ORTL AD 2.11	Meteorological information provided	AD 2.1-98
ORTL AD 2.12	RWY physical characteristics	AD 2.1-98
ORTL AD 2.13	Declared distances	AD 2.1-99
ORTL AD 2.14	Approach and RWY lighting	AD 2.1-99
ORTL AD 2.15	Other lighting, secondary power supply	AD 2.1-99
ORTL AD 2.16	Helicopter landing area	AD 2.1-100
ORTL AD 2.17	ATS airspace	AD 2.1-100
ORTL AD 2.18	ATS communication facilities	AD 2.1-100
ORTL AD 2.19	Radio navigation and landing aids	AD 2.1-101
ORTL AD 2.20	Local traffic regulations	AD 2.1-101
ORTL AD 2.21	Noise abatement procedures	AD 2.1-101
ORTL AD 2.22	Flight procedures	AD 2.1-102
ORTL AD 2.23	Additional Information	AD 2.1-103
ORTL AD 2.24	Charts related to an aerodrome	AD 2.1-103

ORTI – Taji Airport

ORTI AD 2.1	Aerodrome location indicator and name	AD 2.1-104
ORTI AD 2.2	Aerodrome Geographical and Administrative Data	AD 2.1-104
ORTI AD 2.3	Operational hours	AD 2.1-104
ORTI AD 2.4	Handling services and facilities	AD 2.1-105
ORTI AD 2.5	Passenger facilities	AD 2.1-105
ORTI AD 2.6	Rescue and fire fighting services	AD 2.1-105
ORTI AD 2.7	Seasonal availability	AD 2.1-105
ORTI AD 2.8	Aprons, taxiways and check locations/positions data	AD 2.1-105
ORTI AD 2.9	Surface movement guidance and control system and markings	AD 2.1-106
ORTI AD 2.10	Aerodrome obstacles	AD 2.1-106
ORTI AD 2.11	Meteorological information provided	AD 2.1-106
ORTI AD 2.12	RWY physical characteristics	AD 2.1-106
ORTI AD 2.13	Declared distances	AD 2.1-107
ORTI AD 2.14	Approach and RWY lighting	AD 2.1-107
ORTI AD 2.15	Other lighting, secondary power supply	AD 2.1-108
ORTI AD 2.16	Helicopter landing area	AD 2.1-108
ORTI AD 2.17	ATS airspace	AD 2.1-108
ORTI AD 2.18	ATS communication facilities	AD 2.1-109
ORTI AD 2.19	Radio navigation and landing aids	AD 2.1-109
ORTI AD 2.20	Local traffic regulations	AD 2.1-109
ORTI AD 2.21	Noise abatement procedures	AD 2.1-109
ORTI AD 2.22	Flight procedures	AD 2.1-109
ORTI AD 2.23	Additional Information	AD 2.1-110

ORTI AD 2.24	Charts related to an aerodrome	AD 2.1-110
--------------	--------------------------------------	------------

ORTS – Tikrit South Airport

ORTS AD 2.1	Aerodrome location indicator and name	AD 2.1-111
ORTS AD 2.2	Aerodrome geographical and administrative data	AD 2.1-111

ORUB – Ubaydah Bin Al Jarrah Airport

ORUB AD 2.1	Aerodrome location indicator and name	AD 2.1-112
ORUB AD 2.2	Aerodrome geographical and administrative data	AD 2.1-112
ORUB AD 2.12	RWY physical characteristics	AD 2.1-112
ORUB AD 2.13	Declared distances	AD 2.1-112
ORUB AD 2.18	ATS communication facilities	AD 2.1-112
ORUB AD 2.23	Additional Information	AD 2.1-112

ORUQ – Umm Qasr Airport

ORUQ AD 2.	Aerodrome location indicator and name	AD 2.1-113
ORUQ AD 2.2	Aerodrome geographical and administrative data	AD 2.1-113

AD 3. HELIPORTS**ORAQ – Al Qaim Landing Zone**

ORAQ AD 3.1	Aerodrome location indicator and name	AD 3.1-1
ORAQ AD 3.2	Aerodrome geographical and administrative data ..	AD 3.1-1
ORAQ AD 3.3	Operational Hours	AD 3.1-1
ORAQ AD 3.4	Handling Services and Facilities	AD 3.1-1
ORAQ AD 3.5	Helicopter Landing Area	AD 3.1-1
ORAQ AD 3.6	Air Traffic Services Communication Facilities	AD 3.1-2
ORAQ AD 3.7	Local Traffic Regulations	AD 3.1-2
ORAQ AD3.8	Obstacles	AD 3.1-2

ORRW – Korean Village Landing Zone

ORRW AD 3.1	Aerodrome location indicator and name	AD 3.1-3
ORRW AD 3.2	Aerodrome geographical and administrative data ..	AD 3.1-3
ORRW AD 3.3	Operational Hours	AD 3.1-3
ORRW AD 3.4	Handling Services and Facilities	AD 3.1-3
ORRW AD 3.5	Helicopter Landing Area	AD 3.1-3
ORRW AD 3.6	Air Traffic Services Communication Facilities	AD 3.1-4
ORRW AD 3.7	Local Traffic Regulations	AD 3.1-4
ORRW AD3.8	Obstacles	AD 3.1-4

ORWH – Washington Army Heliport

ORWH AD 3.1	Heliport Location Indicator and Name	AD 3.1-5
ORWH AD 3.2	Heliport Geographical and Administrative Data ...	AD 3.1-5
ORWH AD 3.3	Operational Hours	AD 3.1-5
ORWH AD 3.4	Handling Services and Facilities	AD 3.1-5
ORWH AD 3.5	Helicopter Landing Area	AD 3.1-5
ORWH AD 3.6	Air Traffic Services Communication Facilities	AD 3.1-6
ORWH AD 3.7	Local Traffic Regulations	AD 3.1-6

AD 1. AERODROMES - INTRODUCTION

AD 1.1 AERODROME/HELIPORT AVAILABILITY

1.1.1 The Iraq Ministry of Transportation is responsible for the administration of civil aerodromes within Iraq. Except in an emergency, civil aircraft are only permitted to use those aerodromes, which are available for use, by international commercial air transport as designated International Airports within this section. Other aerodromes may be used only after prior permission has been obtained from the Director General of ICAA and coordinated through the Regional Air Movement Control Center.

1.1.2 The services described herein are based on Annex 14 to the Convention on International Civil Aviation.

AD 1.2 RESCUE AND FIRE FIGHTING SERVICES

AD 1.2.1 Rescue and fire fighting services are provided for civil flights operating at Baghdad and Basrah International Airports. Services are provided to the level of RFF Category 8 unless otherwise advised by NOTAM.

AD 1.2.1 Availability of rescue and fire fighting services at other airports are listed within the relevant Aerodrome entry.

AD 1.3 INDEX TO AERODROMES

Aerodrome Name and Location Indicator	Type of traffic permitted to use the aerodrome			Reference to Aerodrome Section and Remarks
Baghdad International Airport (ORBI)	INTL-NTL	VFR-IFR	S-NS-M	ORBI AD 2.1 lists airfield data. ORMM to be used as alternate.
Basrah International Airport (ORMM)	INTL-NTL	VFR-IFR	S-NS-M	ORMM AD 2.1 lists airfield data. ORBI to be used as alternate.
Erbil International Airport (ORER)	INTL-NTL	VFR-IFR	S-NS-M	ORER AD 2.1 lists airfield data. Can be used as night diversion destination if required.
Sulaymaniyah International Airport (ORSU)	INTL-NTL	VFR-IFR	S-NS-M	ORSU AD 2.1 lists airfield data. Can be used as night diversion destination if required.
	Legend: INTL International NTL National/Domestic S Scheduled NS Non-scheduled M Military P Private – temporarily suspended			

AD 2. AERODROMES**ORAA AD 2.1 AERODROME LOCATION INDICATOR AND NAME**

ORAA - Al Asad

ORAA AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N33°47.14' E42°26.47'' The geographic center of the airfield
2	Direction and distance from city	Bearing 360° at 1.5NM
3	Elevation and Reference Temperature	618FT (188.4 M) and 43.1°C
4	Geoid undulation	Not determined
5	Magnetic variation/Annual change	4°E as of Jan 2004, annual change E000°01'22.16''
6	Aerodrome Administration Address Telephone Telefax Telex AFS Address	Al Asad Air Base is under the control of Coalition Forces
7	Types of traffic permitted	IFR and VFR
8	Transition altitude and level	TA 13 000FT AMSL, TL FL150
9	Remarks	All administrative matters are to be referred to the airport director.

ORAA AD 2.3 OPERATIONAL HOURS

1	Aerodrome Administration	TBD
2	Customs and Immigration	HJ (H24 on request to ICAA)
3	Health and Sanitation	HJ (H24 on request to ICAA)
4	AIS Briefing Office	H24
5	ATS Reporting Office	H24
6	Met Office	H24
7	Air Traffic Services	H24
8	Fuelling	Civilian aircraft fuel requests will not be supported. Aircrew are to pre-plan flight without refuel at ORAA. Transient AMC aircraft must request fuel 24 hours in advance. Priority based on mission essentiality. Maximum delivery 7,920 litres / 30,000 LBS. Expect delays due limited dispensing equipment. Requests to be made to Base OPS on DSN 318-3412-700.
9	Handling	HJ (H24 on request to ICAA)
10	Security	H24
11	De-icing	Not available

12	Remarks	<p>Limited facilities for non-military freight. Except for military, ICRC and UN sponsored flights, approval for HA flights is required from CJTF-7.</p> <p>Prior Permission Required (PPRs): Al Asad ORAA, is a PPR only airfield. PPRs are required for <i>ALL</i> military and civil Fixed Wing aircraft (including aircraft on ATO's) operating at this airfield. Fixed Wing aircraft not issued a PPR may be turned away or met by security forces. All Rotary and Fixed Wing aircraft with a DV code 7 or higher will also require a PPR. Civil operators must contact Al Asad and receive a PPR before requesting a slot time from RAMCC. Military, RAMCC will no longer issue slot times PPR's for military Fixed Wing aircraft also serve as their slot times. Military PPR's are valid for +/- 30min from ETA/ETD. Aircraft must update their PPR's ASAP if unable to meet the coordinated PPR/Slot time through the Airfield Operations PPR's issued within 6 hours, will not be guaranteed priority for handling and may be delayed. The approval Authority is Airfield Operations</p> <p><u>Contact information :</u> Email: NIPR: alasadppr@acemnf-wiraq.usmc.mil SIPR: alasadppr@acemnf-wiraq.usmc.mil DSN # for Airfield Operations is 318-3412-700</p> <p>Permission to operate in the Baghdad FIR is coordinated through Regional Air Movements Coordination Center (RAMCC). Refer GEN 1.2 for current procedures, requirements and contact information.</p>
----	---------	---

ORAA AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	<p>Military coordinated through Al Asad Command Post. No storage for freight or passengers.</p> <p>Civil aircraft must pre-arrange with MoT and coord with ground personnel upon arrival.</p>
---	---------------------------	---

2	Fuel and oil types	Limited supply of JP8. Nil oil
3	Fueling facilities and capacity	Aircraft using hot fuel pits must follow instructions from ATC and hot fuel pit taxi directors. Aircrew should be familiar with fuelling procedures found in Al Asad Air Base Operations Manual, USMC NAVAIR 00-80T-109 and NATOPS Manual prior to hot fuel pit usage. Failure to comply with published procedures may result in aircraft cold fuelling.
4	De-icing facilities	Nil
5	Hanger space for visiting aircraft	Nil
6	Repair facilities for visiting aircraft	Nil
7	Remarks	Limited capacity for passenger operations

ORAA AD 2.5 PASSENGER FACILITIES

1	Hotels at/near aerodrome	Nil
2	Restaurants	Nil
3	Transportation	Nil.
4	Medical facilities	Nil
5	Bank and Post Office	Nil
6	Tourist Office	Nil
7	Remarks	Nil

ORAA AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	RFF Category 2
2	Rescue Equipment	P-19 Rescue vehicle
3	Capability for removal of disabled aircraft	Limited assistance using military assets
4	Remarks	Nil

ORAA AD 2.7 SEASONAL AVAILABILITY

1	Type(s) of clearing equipment	Nil
2	Clearance priorities	Nil
3	Remarks	Nil

**ORAA AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS
DATA**

1	Surface and strength of aprons	Two aprons available for Military and fixed-wing aircraft: Bravo Ramp - 1 150FT X 394 FT LCN39 Charlie Ramp - 1 150FT X 393 FT LCN39
2	Width, surface and strength of TWYs	TWY A 99 FT, ASP, PCN57 FA TWY B, C1, C2 50 FT, ASP, PCN102 TWY C, 83 FT, ASP, PCN 54 TWY E, F, G 83 FT, ASP, PCN94

		TWY E1, G2 North, F1 50 FT, ASP, PCN94 TWY I1, J5, L5 50 FT, ASP, PCN94 TWY K1-13 49 FT, ASP, PCN46
3	Location and elevation of altimeter checkpoints	TBD
4	VOR and INS checkpoints	Not available
5	Remarks	Aircraft will be directed to parking by marshaller.

ORAA AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	Use of aircraft stand ID signs, TWY guide lines and visual docking/parking guidance system at aircraft stands	TBD
2	RWY and TWY markings and lights	Standard markings, lights under reconstruction. Military aircraft refer to NOTAMs at https://www.notams.jcs.mil .
3	Stop bars	Nil
4	Remarks	Nil

ORAA AD 2.10 AERODROME OBSTACLES

ORAA 2.10.1 Tower 150FT AGL erected 2.5NM northeast of airfield marked by infrared light on upper extremity.

ORAA 2.10.2 Antenna 70FT AGL erected 1 NM northwest of airfield marked by infrared light.

ORAA 2.10.3 Tower 150FT AGL east of intersection of TWYs Delta and Oscar.

ORAA 2.10.4 Tower 200FT AGL at N33°49'06.88" E042°31'52.94" marked with red flashing beacon.

ORAA 2.10.5 Antenna 125FT AGL erected 2.5NM north of airfield marked by infrared strobe light.

ORAA AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

ORAA 2.11 Limited weather information, using the location designator of KQAJ vice the ICAO airfield designator, is available from the following websites:

Open access website: <http://adds.aviationweather.noaa.gov/>
Military only websites: <https://afwin.afwa.af.mil/> or <https://28ows.shaw.af.mil/>

ORAA AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	08	26
2	BRG True and Mag		
3	RWY Dimensions	10125 x 338FT	10125 x 338FT
4	PCN		
5	THR Coordinates		
6	THR Elevation		
7	Remarks	Nil	Nil

1	RWY	09L	27R
2	BRG True and Mag	088.5°T, 084.5°M	268.53°T, 264.53°M
3	RWY Dimensions	13124 x 197FT (3999M x 60M)	13124 x 197FT (3999M x 60M)
4	PCN	56 R/B/W/T	56 R/B/W/T
5	THR Coordinates	33°47'22.16"N 042°25'58.71"E	33°47'25.53"N 042°28'34.15"E
6	THR Elevation	595 FT	557FT
7	Remarks	Caution centerline joint erosion. Offset nose wheel slightly.	Caution centerline joint erosion. Offset nose wheel slightly.

1	RWY	09R	27L
2	BRG True and Mag	88.48°T, 84.48°M	268.51°T, 264.51°M
3	RWY Dimensions	13123 x 148FT (3999M x 45M)	13123 x 148FT (3999M x 45M)
4	PCN	56/R/B/W/T	56/R/B/W/T
5	THR Coordinates	33°46'50.82"N 042°24'22.49"E	33°46'54.23"N 042°26'57.91"E

6	THR Elevation	618FT	577FT
7	Remarks	M-31 arresting gear approach end. Assemblies 5 FT 10 IN high located 110 FT from RWY centerline on both sides of RWY. All aircraft C130 and larger approaching 09R shall land 400 FT beyond the arresting gear.	M-31 arresting gear approach end. Assemblies 5 FT 10 IN high located 110 FT from RWY centerline on both sides of RWY. All aircraft C130 and larger approaching 27L shall land 400 FT beyond the arresting gear.

ORAA AD 2.13 APPROACH AND RUNWAY LIGHTING

ORAA 2.13.1 Further information on Al Asad's approach and RWY lighting is available at the following military website:

<https://www.notams.jcs.mil>

1	RWY	08	26	09L	09R	27L	27R
2	Type, length and intensity of approach lighting						
3	Threshold lights, colors and wing bars			GREEN NO/WB	GREEN NO/WB	GREEN NO/WB	GREEN NO/WB
4	Type of visual approach slope indicator system				TAC PAPI LEFT SIDE 2000FT FROM APP END	TAC PAPI LEFT SIDE 2000FT FROM APP END	
5	Length of RWY touchdown zone indicator lights						
6	Length spacing color and intensity of RWY centerline lights						
7	Length spacing color and intensity of RWY edge lights			WHITE 200FT	WHITE 200FT	WHITE 200FT	WHITE 200FT

8	Color of RWY end lights and wingbars			RED NO/WB	RED NO/WB	RED NO/WB	RED NO/WB
9	Length and color of stopway lights						
10	Remarks					Nil	Nil

ORAA AD 2.14 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Call sign	FREQ	Hours of operation	Remarks
APP	Al Asad Approach	118.600 MHz 147.850 MHz 298.025 MHz	H24	Primary Secondary
TWR	Al Asad Tower	131.225 MHz 363.675 MHz	H24	Primary Secondary
GROUND	Al Asad Ground	232.625 MHz 146.375 MHz	H24	Primary Secondary
GCA	Al Asad Final	298.025 MHz 147.850 MHz	H24	Primary Secondary
CLEARANCE DELIVERY SERVICE REMOVED				

ORAA AD 2.15 LOCAL TRAFFIC REGULATIONS

ORAA 2.15.1 Due to the extensive combination of non-military aircraft and military aircraft operating within Al Asad Class D airspace, the following lighting configurations are effective to improve de-confliction and positive control of aircraft:

ORAA 2.15.1.1 By day, aircraft operating as a single ship or the trail aircraft in a formation will have anti-collision lights on.

ORAA 2.15.1.2 By night, aircraft operating as a single ship or the lead of a formation will have IR position lights operating and anti-collision lights on. The trail aircraft will have overt (visible to the unaided eye) navigation lights on. Aircraft not equipped with IR position lights will turn on IR LDG lights prior to entering Al Asad Class D. Aircraft not equipped with an IR lighting capability will turn overt position lights on prior to entering Class D. Aircraft LDG in the vicinity of the Oscar TWY will turn on their IR spotlight at 200FT and below when inside the Oscar reporting points (palm grove and ripper).

ORAA.2.15.1.3 Aircraft taxiing on the airfield during the hours of darkness will have position/formation lights on.

ORAA 2.15.2 Carrier breaks are authorized with prior approval from ATC. Carrier break altitude is 800FT.

ORAA 2.15.3 Overhead procedures. The initial point is located 5 NM from the approach end of the runway. Aircraft are to cross the initial point at or above 4000FT feet, cross the approach end numbers at or above 2700FT, break south, then once wings level on downwind

descend to 1,600FT pattern altitude. All aircraft are to remain south of ALPHA TWY unless otherwise directed by ATC.

ORAI AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORAI – Al Iskandarariyah New Airport

ORAI AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N32°58'12.00" E044°16'12.00" The geographic center of the airfield
2	Elevation and Reference Temperature	135FT (41.1M) and 43.1°C

ORAI AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	14	32
2	BRG True and Mag	TBD	TBD
3	RWY Dimensions	10249 x 98FT (3124M x 30M)	10249 x 98FT (3124M x 30M)
4	PCN	LCN 39	LCN 39
5	THR Coordinates	TBD	TBD
6	THR Elevation	TBD	TBD

ORAT AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORAT – Al Taqaddum Airport

ORAT AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N33°20'16.99" E043°35'49.46" The geographic center of the airfield
2	Elevation and Reference Temperature	275FT (83.8M) and 43.1°C

ORAT AD 2.3 OPERATIONAL HOURS

1	Aerodrome Administration	H24 DSN 302-3221-315
2	Customs and Immigration	HJ (H24 on request to ICAA) Limited
3	Health and Sanitation	HJ (H24 on request to ICAA)
4	AIS Briefing Office	TBD
5	ATS Reporting Office	TBD
6	Met Office	H24 DSN 302-3221-316 244.325UHF
7	Air Traffic Services	H24 DSN 302-3221-312/349
8	Fuelling	H24
9	Handling	HJ (H24 on request to ICAA)
10	Security	H24
11	De-icing	Not available
12	Remarks	<p>Limited facilities for non-military freight. Except for military, ICRC and UN sponsored flights, approval for HA flights is required from MNC-I C3 Avn.</p> <p>Prior Permission Required (PPRs): Al Taqaddum ORAT, is a PPR only airfield. PPRs are required for all transient civil and Non-ATO military fixed wing aircraft. Aircraft not issued a PPR may be turned away or met by security forces.</p> <p><u>Civil Operators.</u> Contact Al Taqaddum and obtain a PPR prior to contacting RAMCC for slot times into and out of Iraq.</p> <p><u>Military Aircraft.</u> RAMCC will no longer issue slot times for Al Taqaddum. PPRs will serve as slot times +/- 30 minutes from PPR ETA/ETD. For ARR/DEP outside of this window contact Al Taqaddum Flight Clearance to update PPR ETA/ETD slot ASAP. PPR numbers remain in effect provided Al Taqaddum Flight Clearance receives updated ETA/ETD.</p> <p>PPRs issued with 6 hours or less notice not guaranteed priority handling and may be delayed. Al Taqaddum Flight Clearance is</p>

		<p>final approval authority for PPR issue or revocation</p> <p><u>Contact information :</u> Al Taqaddum Flight Clearance DSN 318-3422-341 Email: NIPR: tqfc@acemnf-wiraq.usmc.mil SIPR: tqfc@acemnf-wiraq.usmc.smil.mil Airfield Manager. DSN 318-342-2344</p> <p>Permission to operate in the Baghdad FIR is coordinated through Regional Air Movements Coordination Center (RAMCC). Refer GEN 1.2 for current procedures, requirements and contact information.</p>
--	--	---

ORAT AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	<p>The Joint Air Cargo Operations Team (JACOT) is located on R TWY between A TWY and 3000FT NW of P TWY. All traffic is to enter the JACOT at D TWY. Fixed wing aircraft will turn left on R TWY to park on A, O N and E TWYs. DC8 and Airbus aircraft will turn right on R TWY to park in the vicinity of the intersection of R and D TWYs. Rotary wing aircraft will turn right on R TWY to park in the vicinity of the intersection of R and P TWYs.</p> <p>All aircraft for JACOT shall contact KINGFISH KILO on primary frequency 230.000 MHz for information prior to landing. If unable to contact airborne contact KINGFISH KILO when on D TWY</p> <p>Military coordinated through Al Taqaddum Command Post. No storage for freight or passengers.</p> <p>Civil acft must pre-arrange with MOT and coord with ground personnel upon arrival.</p>
2	Fuel and oil types	Limited supply of JP8. Nil oil
3	Fueling facilities and capacity	Fuel available for essential military aircraft only. No hot fuel to fixed wing aircraft.
4	De-icing facilities	Nil
5	Hanger space for visiting aircraft	Nil

6	Repair facilities for visiting aircraft	Nil
7	Remarks	Limited capacity for passenger operations.

ORAT AD 2.5 PASSENGER FACILITIES

1	Hotels at/near aerodrome	Nil
2	Restaurants	Nil
3	Transportation	Nil.
4	Medical facilities	Nil
5	Bank and Post Office	Nil
6	Tourist Office	Nil
7	Remarks	Nil

ORAT AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	Cat II
2	Rescue Equipment	Yes
3	Capability for removal of disabled aircraft	Limited assistance using military assets
4	Remarks	Nil

ORAT AD 2.7 SEASONAL AVAILABILITY

1	Type(s) of clearing equipment	Nil
2	Clearance priorities	Nil
3	Remarks	Nil

ORAT AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS DATA

1	Surface and strength of aprons	Four aprons available for Military and fixed-wing aircraft: OPS - 930 FT X 340 FT LCN48 OPS2 - 1 150 FT X 295 FT LCN48 OPS3 - 1 365 FT X 435 FT LCN48 OPS 4 - 930 FT X 680 FT LCN48
2	Width, surface and strength of TWYs	TXY A, B, C, K, N, O, P are 50FT wide ASP LCN 48 TXY D, F, J are 65FT wide CON LCN 48 TXY E, I, L, M are 70FT wide CON LCN 48 TXY G, H, R are 100FT wide CON LCN 48 TWY Q is unusable and not available TWY S is 50FT wide CON LCN 45 TWY T is 49FT wide CON LCN 45
3	Location and elevation of altimeter checkpoints	TBD
4	VOR and INS checkpoints	Not available
5	Remarks	K TWY between F and A TWYs is a designated non-movement area. R TWY between H and A TWYs is a

		<p>designated non-movement area.</p> <p>R TWY between H and Q TWYs closed to all air and ground traffic.</p> <p>Hot Pits are located on K TWY between D and B TWYs.</p> <p>Hot cargo offload area is located on M TWY between the parallel runways. There is no hot cargo offload on D TWY.</p> <p><i>Note: All aircraft are to be directed by a marshaller to parking.</i></p>
--	--	---

ORAT AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	Use of aircraft stand ID signs, TWY guide lines and visual docking/parking guidance system at aircraft stands	Yellow TWY centerline stripe
2	RWY and TWY markings and lights	Standard markings.
3	Stop bars	Nil
4	Remarks	Nil

ORAT AD 2.10 AERODROME OBSTACLES

Nil identified

ORAT AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

ORAT 2.11.1 Local meteorological services available from METRO on DSN 302-3221-316 or UHF 244.325MHz.

ORAT 2.11.2 Limited weather information, using the location designator of KQEZ vice the ICAO airfield designator, is available from the following websites:

Open access website: <http://adds.aviationweather.noaa.gov/>
 Military only websites: <https://afwin.afwa.af.mil/> or <https://28ows.shaw.af.mil/>

ORAT AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	12L	12R	30L	30R
2	BRG True and Mag	119.0°T 115.3°M	119.0°T 115.6°M	299.0°T 295.6°M	299.0°T 295.3°M
3	RWY Dimensions	12087 x 150FT (3684M x 46M)	13186 x 190FT (4019M x 58M)	13186 x 190FT (4019M x 58M)	12087 x 150FT (3684M x 46M)

4	PCN	40/R/B/W/T	40/R/B/W/T	40/R/B/W/T	40/R/B/W/T
5	THR Coordinates	33°20'49.92"N 043°34'53.56"E	33°20'45.29"N 043°34'35.59"E	33°19'41.18"N 043°36'50.94"E	33°19'51.41"N 043°36'57.82"E
6	THR Elevation	270 FT	275 FT	258 FT	262 FT

ORAT AD 2.13 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
APP	Taqaddum Approach	147.300 MHz 125.250 MHz 295.850 MHz	H24	
TWR	Taqaddum Tower	275.275 MHz 135.775 MHz	H24	Primary Secondary
Clearance Delivery	Taqaddum Clearance	290.85 MHz	H24	Secure
ATIS		226.275 MHz	H24	Secure

ORAN AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORAN – An Numaniyah Airport

ORAN AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N32°30'12.00" E045°19'54.00" The geographic center of the airfield
2	Elevation and Reference Temperature	43FT and 43.1°C
3	Remarks	Airfield not operational

ORAN AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	12	30
2	BRG True and Mag	088.5°T, 084.5°M	88.48°T, 84.48°M
3	RWY Dimensions	9843 x 148FT (3000M x 45M)	9843 x 148FT (3000M x 45M)
4	PCN	TBD	TBD
5	THR Coordinates	TBD	TBD
6	THR Elevation	TBD	TBD

ORBI AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORBI – Baghdad International Airport

ORBI 2.1.1 All operators are cautioned about the high risk to aircraft in the vicinity of ORBI from small arms fire and man portable surface-to-air missiles. Civilian carriers must comply with Baghdad minimum power setting approach procedures. Aircraft requiring extended distance stabilized final approaches are prohibited due to their flight profile increasing vulnerability. Expect SVFR operations during ORBI IMC conditions.

ORBI AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N33°15'45.140" E044°14'04.476" The geographic center of the airfield
2	Direction and distance from city	Bearing 235° at 8NM
3	Elevation and Reference Temperature	114FT (34.6 M) and 43.1°C
4	Geoid undulation	Not determined
5	Magnetic variation/Annual change	4°E as of Jan 2004, annual change E000°01'16.24"
6	Civil Aerodrome Administration Senior Airfield Authority Military (Sather AB) Administration	Iraq Civil Aviation Authority Baghdad International Airport Baghdad, Iraq +964 07901418903 E-mail: IBIAP1@yahoo.com Commander 447 Air Expeditionary Group Airfield Manager: 447 OSS DSN 318-453-2900 E-mail: 447AEG/OSAA@bdab.centaf.af.mil
7	Types of traffic permitted	IFR and VFR
8	Transition altitude and level	TA 13,000 FT AMSL, TL FL150
9	Remarks	Civil aircraft, with the approval of the Senior Airfield Authority, may be authorized to operate between that period civil morning twilight to SR and SS to civil evening twilight. Civil aircraft departures, with the approval of the Senior Airfield Authority (1 hr prior notice required) and when conditions allow, may be authorized to depart between civil evening twilight and SR. All administrative matters are to be referred to the airport director. LDG, parking and fuel charges will be IAW published rates at GEN 4.1 and GEN 4.2. Charges MUST be paid in full in cash (\$US) prior to departure.

ORBI AD 2.3 OPERATIONAL HOURS

1	Aerodrome Administration	Sat-Wed 0800 – 1400, Thu 0800 – 1300, Fri - Closed
2	Customs and Immigration	HJ (H24 on request to ICAA)
3	Health and Sanitation	HJ (H24 on request to ICAA)
4	AIS Briefing Office	TBD
5	ATS Reporting Office	TBD
6	Met Office	TBD
7	Air Traffic Services	H24
8	Fuelling	HJ (must be pre-organized). Small quantities of JP8 and Jet A1 available. Crews advised to carry round trip fuel.
9	Handling	HJ (H24 on request to ICAA)
10	Security	H24
11	De-icing	Not available
12	Remarks	<p>Civilian portion of aerodrome closed to civilian air traffic daily – see NOTAMs for specific times. Limited instrument approaches and departures for civil aircraft. Limited facilities for non-military freight. Except for military, ICRC and UN sponsored flights, approval for HA flights is required from MNC-I.</p> <p>Prior Permission Required (PPRs):Baghdad Civilian ORBI generally does not require a PPR however operators must check the latest ORBI NOTAMs for the most current PPR requirements.</p> <p>Military (Sather AB) portion of aerodrome, is PPR, for use by MNF-I participating nations. Fixed wing ATO assigned aircraft requesting military PPRs should contact airfield management as far in advance as possible. Due to working MOG/flight schedules, PPRs will not be issued until 48 HRS prior to arrival time. PPRs issued within six HRS of arrival will not be guaranteed priority handling and may be delayed. Unauthorized aircraft will be denied landing or detained. PPRs are valid +/- 30 Min from ETA. Baghdad Military ORBI Secure Mil E-mail: 447AEG/OSAA@bdab.centaf.af.smil.mil</p> <p>Permission for civilian aircraft to operate in the Baghdad FIR is coordinated through the Regional Air Movement Control Center (RAMCC). Refer to GEN 1.2 for current</p>

		procedures, requirements and contact information. Permission for military aircraft to operate in the Baghdad FIR is coordinated through Combined Air Operations Center.
--	--	---

ORBI AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	Hazardous Cargo ATOC DSN 318-453-0051 minimum 48 hrs PPR or Commercial contact +914 360 4793 Military coordinated through Baghdad Command Post. Capability for main deck wide-body freighter. No storage for freight or passengers Civil aircraft must pre-arrange with MoT and coordinate with ground personnel upon arrival.
2	Fuel and oil types	Limited supply of AVTUR. Nil oil
3	Fueling facilities and capacity	Limited. Plan flight without fuel from ORBI
4	De-icing facilities	Nil
5	Hanger space for visiting aircraft	Nil
6	Repair facilities for visiting aircraft	Nil
7	Remarks	Limited capacity for passenger operations. Handling services during daylight hours only or by arrangement with MoT and ICAA Military aircraft contact command post 'Kingfish Hotel' on 133.5MHz, 229.425MHz or 229.625MHz 10 minutes prior to ETA. Civil aircraft - Phone 914 822 7190 Military FARP operates H24, available on 33.775MHz. No catering, potable water or toilet conditioning fleet service available. Aircraft operators should expect to provide towing arm.

ORBI AD 2.5 PASSENGER FACILITIES

1	Hotels at/near aerodrome	Nil. Limited in the city
2	Restaurants	5 star in administration building adjoining terminal, one café in departure lounge
3	Transportation	Nil.
4	Medical facilities	Nil
5	Bank and Post Office	In administration building adjoining terminal, open AD administration hours
6	Tourist Office	Nil
7	Remarks	Nil

ORBI AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	RFF Cat 8
2	Rescue Equipment	TBC
3	Capability for removal of disabled aircraft	Limited assistance using military assets
4	Remarks	Nil

ORBI AD 2.7 SEASONAL AVAILABILITY

1	Type(s) of clearing equipment	Nil
2	Clearance priorities	Nil
3	Remarks	Nil

ORBI AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS DATA

1	Surface and strength of aprons	Military Side: Three concrete surfaced aprons for military and civil aircraft: <u>AMC Ramp</u> (Z-1), PCN-61/R/B/W/T; <u>Mid Ramp</u> (Z-2), PCN-59/R/B/W/T; & <u>South Ramp</u> (Z-3), PCN-59/R/B/W/T. Civil Side: Nine concrete surfaced aprons for civil aircraft: <u>Hangar 1 Apron</u> , PCN-63/R/B/W/T; <u>Trim Pad</u> , PCN-64/R/B/W/T; <u>Hangar 2 Apron</u> , PCN-61/R/B/W/T; <u>Echo Ramp</u> , PCN-63/R/B/W/T; <u>Alpha Ramp</u> , PCN-61/R/B/W/T; <u>Delta Ramp & Terminal B & C Apron</u> , PCN-66/R/C/W/T, six gates each for B747 or smaller aircraft; <u>Humanitarian Aid (HA) Apron (Kilo)</u> , PCN-63/R/C/W/T, one parking spot for An-124, two parking spots for Il-76/A-300, three parking spots for smaller aircraft; <u>Victor Ramp (VVIP)</u> , PCN-66/R/C/W/T.
2	Width, surface and strength of TWYs	Military Side: Ten concrete surfaced TWYs for military/civil aircraft. Width: 23m (75ft) [<u>M-North</u> , PCN-46/R/B/W/T; <u>M-South</u> , PCN-50/R/C/W/T; <u>P2</u> (G), PCN-72/R/B/W/T; <u>P3</u> (H), PCN-72/R/B/W/T; <u>P4</u> (J), PCN: 72/R/B/W/T; <u>P5</u> (T), PCN-81/R/B/W/T]. 30m (98ft) [<u>M</u> (Apron Strip), PCN-54/R/B/W/T]. 90m (295ft) [<u>P1</u> South Hammerhead (F), PCN-63/R/B/W/T; <u>P6</u> North Hammerhead (L), PCN-52/R/B/W/T. Civil Side: Twenty concrete surfaced TWYs for civil aircraft. Width: 23m (75ft) [<u>G</u> , PCN-72/R/B/W/T; <u>N</u> , PCN-79/R/B/W/T; <u>O</u> , PCN-68/R/C/W/T; <u>P</u> , PCN-63/R/B/W/T; <u>R</u> , PCN-79/R/B/W/T; <u>S5</u> , PCN-85/R/C/W/T; <u>S6</u> , PCN-64/R/C/W/T]. 30m (98ft) [<u>A</u> , PCN-68/R/C/W/T; <u>S</u> , PCN-58/R/C/W/T; <u>S1</u> , PCN-58/R/C/W/T; <u>S2</u> , PCN-81/R/C/W/T; <u>S3</u> , PCN-81/R/C/W/T; <u>S4</u> , PCN-81/R/C/W/T; <u>T</u> , PCN-68/R/C/W/T; <u>W</u> , PCN-58/R/C/W/T; <u>X</u> , PCN-62/R/C/W/T]. 40m (131ft) [<u>S5</u> , PCN-81/R/C/W/T]. 55m (180ft) [<u>Apron Access B</u> , PCN-58/R/C/W/T; <u>Apron Access C</u> , PCN-58/R/C/W/T]. 60 m (197ft) [<u>Apron Access D</u> , PCN-58/R/C/W/T]. 90 m (295 ft) [Sierra Hammerhead North, PCN-66/R/C/W/T; Sierra Hammerhead South, PCN-64/R/C/W/T].
3	Location and elevation of altimeter checkpoints	On apron at 33°15'50"N 44°12'20"E 113FT

4	VOR and INS checkpoints	Not available
5	Remarks	Use caution on TWY M, AMC Ramp and Mid Ramp, due to moderate and severe spalling and deteriorated joints. Aircraft must coordinate parking with tower/ Command Post/ Airfield Management. Aerobridges not AVBL. Note: <i>All aircraft are to be directed by a marshaller to parking.</i>

ORBI AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	Use of aircraft stand ID signs, TWY guide lines and visual docking/parking guidance system at aircraft stands	See ORBI AD 2-24 charts
2	RWY and TWY markings and lights	Standard markings, lights under reconstruction. Military aircraft refer to DINS NOTAMs at https://www.notams.jcs.mil . RWY 15R/33L Emergency Airfield Lighting System (EALS) in use operating at reduced intensity, non-standard lighting
3	Stop bars	Stop bars where appropriate
4	Remarks	Nil

ORBI AD 2.10 AERODROME OBSTACLES

1	RWY33R	ORBI Obstacle Chart not published		
2	RWY15L	ORBI Obstacle Chart not published		
3	RWY33L	ORBI Obstacle Chart not published		
4	RWY15R	ORBI Obstacle Chart not published		
5	Remarks: Control TWR 321FT (98m) location N331621.654/ E0441335.150. North of civil terminal between threshold RWY15L and RWY15R (no obst lgt). Communication masts approximately 1180FT loc 3NM NNE of airfield (no obst lgt). Restricted Area NE of RWY 33R threshold, N3315.433/ E04416.483, radius 0.5 NM; SFC to 3000FT AGL. Restricted Area NNE of RWY 33R threshold, N3317.95/ E04415.95, radius 0.5 NM, SFC to 2000FT AGL. The following additional obstructions have been identified:			
		LAT	LONG	HGT AMSL (M/FT)
ANT	ANTENNA 15L SIDE	33 17 10.330N	44 13 46.345E	33.816/110.94
ANT1	ANTENNA	33 15 04.871N	44 13 19.989E	71.733/235.34
ANT2	ANTENNA	33 16 43.560N	44 14 22.384E	54.894/180.10
ANT3	ANTENNA	33 16 43.586N	44 14 20.955E	58.622/192.33
ANT4	ANTENNA 33R SIDE	33 15 00.657N	44 15 15.325E	33.029/108.36
ASRA	SURV RADAR	33 15 49.197N	44 13 34.643E	70.679/231.89
COM1	COMMS TWR	33 16 22.110N	44 13 31.798E	79.231/259.94
COM2	COMMS TWR	33 15 21.800N	44 12 58.200E	71.320/234.00
COM3	COMMS TWR	33 13 29.520N	44 13 39.540E	71.320/234.00

COM4	COMMS TWR	33 13 08.300N	44 13 01.090E	93.260/306.00
COM5	COMMS TWR	33 15 63.200N	44 14 34.800E	93.260/306.00
COM6	COMMS TWR	33 16 36.300N	44 13 59.400E	93.260/306.00
COM7	COMMS TWR	33 14 11.300N	44 14 34.200E	56.080/184.00
COM8	COMMS TWR	33 17 10.700N	44 13 10.200E	77.420/254.00
GSA1A	GLD SLP 33R END	33 15 20.585N	44 15 07.765E	46.946/154.02
GSA2A	GLD SLP 15L END	33 16 54.842N	44 14 03.088E	47.804/156.84
GSA3A	GLD SLP 15R END	33 15 55.856N	44 13 02.895E	40.976/134.43
GSA4A	GLD SLP 33L END	33 14 39.683N	44 13 53.847E	46.445/152.38
GSA5A	GLD SLP 33L END	33 14 41.295N	44 13 54.101E	47.875/157.07
LT1	LIGHT POLE	33 14 43.356N	44 13 36.711E	55.660/182.61
LT2	LIGHT POLE	33 14 49.951N	44 13 32.187E	54.401/178.48
LT3	LIGHT POLE	33 15 30.433N	44 13 45.076E	74.131/243.21
LT4	LIGHT POLE	33 15 14.035N	44 13 56.420E	74.425/244.17
LT5	LIGHT POLE	33 15 04.782N	44 14 03.436E	70.037/229.78
LT6	LIGHT POLE	33 15 33.882N	44 13 02.142E	54.980/180.38
LT7	LIGHT POLE	33 16 39.496N	44 13 54.478E	59.809/196.22
MIDM	PA ALARM SYSTEM	33 14 06.656N	44 14 20.608E	55.982/183.67
MOS1	MOSQUE 1	33 14 18.492N	44 15 42.012E	61.630/202.20
MOS2	MOSQUE 2	33 14 18.465N	44 14 58.745E	64.270/210.86
RDT1	RADIO TOWER	33 15 37.643N	44 14 20.910E	94.895/311.34
RDT2	RADIO TOWER	33 16 44.804N	44 14 24.536E	83.614/274.32
RDT3	RADIO TOWER	33 17 04.542N	44 13 07.955E	84.034/275.70
WAT1	WATER TOWER	33 16 31 300N	44 11 50.550E	71.320/234.00

ORBI AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

ORBI 2.11.1 Weather forecasting available – forecaster available H24 on DSN (318) 453-0254, SUN to SAT. Weather radar data is not available.

ORBI 2.11.2 Remote weather brief for military operators available H24 through CENTAF Operational Weather Squadron (OWS) on DSN (312) 965-0907; Comm +1 (803) 895-0907. METRO/PMSV through Command Post, callsign Kingfish Hotel, UHF 229.425MHz.

ORBI 2.11.3 Limited weather information, using the location designator of KQTZ vice the ICAO airfield designator, is available from the following websites:

Open access website: <http://adds.aviationweather.noaa.gov/>
 Military only websites: <https://afwin.afwa.af.mil/> or <https://28ows.shaw.af.mil/>

ORBI AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	15L	33R	15R	33L
2	BRG True and Mag	150°T, 147°M	330°T, 327°M	150°T, 147°M	330°T, 327°M
3	RWY Dimensions	13124FT x 197FT (4000M x 60M)	13124FT x 197FT (4000M x 60M)	10830FT x 148FT (3301M x 45M)	10830FT x 148FT (3301M x 45M)

4	PCN	56 R/C/W/T	56 R/C/W/T	51 R/B/W/T	51 R/B/W/T
5	THR Coordinates	N33°17'01.761" E044°13'52.225"	33°15'09.273"N 044°15'09.412"E	33°16'06.860"N 044°13'00.701"E	33°14'34.037"N 044°14'04.410"E
6	THR Elevation	113 FT	110FT	114FT	113FT
7	Slope of RWY/SWY	Unknown	Unknown	Unknown	Unknown
8	SWY Dimensions	393FT (120M)	400FT (122M)	197FT (60M)	197FT (60M)
9	CWY Dimensions	Not calculated	Not calculated	Not calculated	Not calculated
10	Strip Dimensions	Not calculated	Not calculated	Not calculated	Not calculated
11	Obstacle free zone	Not calculated	Not calculated	Not calculated	Not calculated
12	Remarks	6in concrete slabs with 6ft deep manholes along East and West shoulder edges		Civil use in emergency only 6in dip in surface , due crater repair settling, abeam TWY P-5.	

ORBI AD 2.13 DECLARED DISTANCES

1	RWY	15L	33R	15R	33L
2	TORA	13124FT (4000M)	13124FT (4000M)	10830FT (3301M)	10830FT (3301M)
3	TODA	13124FT (4000M)	13124FT (4000M)	11027FT (3360M)	11027FT (3360M)

ORBI AD 2.14 APPROACH AND RUNWAY LIGHTING

ORBI 2.14.1 Advice on Baghdad's approach and RWY lighting is available at the following military website:

<https://www.notams.jcs.mil>

ORBI AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Aerodrome Beacon	Aerodrome beacon - OTS
2	Location and lighting of anemometer and LDG direction indicator	Not fitted
3	TWY edge and centerline	Lighting under reconstruction. Check NOTAM for latest

	lighting	information. Portable edge lights in use.
4	Secondary power supply including switch-over time	Secondary power to all airfield lighting, switch-over time: 1 minute
5	Remarks	Portable THLD/RWY END lights in use.

ORBI AD 2.16 HELICOPTER LANDING AREA

1	Coordinates of touchdown and lift-off point (TLOF) threshold of final approach and take-off (FATO)	South Mike Helipad: N33°14.550' E044°13.838' North Mike Helipad: N33°15.910' E044°12.920' Rifle Stock Helipad: N33°14.848' E044°13.848' Bottle Neck Helipad: N33°15.322' E044°13.310'
2	TLOF and/or FATO area elevation	South Mike Helipad: 84FT AGL North Mike Helipad: 89FT AGL Rifle Stock Helipad: 76FT AGL Bottle Neck Helipad: 95FT AGL
3	TLOF and FATO area dimensions, surface, strength, marking	All landing surfaces are 100FT x100FT and marked with a white "H"
4	True and MAG BRG of FATO	To be determined
5	Declared distance available	To be determined
6	Approach and FATO lighting	To be determined
7	Remarks	Except Rifle Stock landing area, all other landing areas are within the CMA.

ORBI AD 2.17 AIR TRAFFIC SERVICES AIRSPACE

1	Airspace designation and lateral limits	Detailed in ENR 1.4
2	Vertical limits	
3	Airspace classification	
4	Callsign and Languages	Baghdad ... (Tower) English
5	Transition altitude	13 000FT
6	Remarks	ATS provided by Iraq controllers HJ operating IAW ICAO Standards and Recommended Practices. USAF provides ATS HN.

ORBI AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
ACC	Balad Center	123.525 MHz 274.575 MHz	H24	Primary Secondary
APP	Balad Approach	131.900 MHz 255.800 MHz	H24	Primary Secondary
TWR	Baghdad Tower	118.700 MHz 275.800 MHz	H24	Primary
TWR HELICOPTER	Baghdad Helo	131.700 MHz 118.700 MHz	SR to SS SS to SR	131.700Mhz monitored H24

GROUND	Baghdad Ground	121.700 MHz 264.600 MHz	H24 (UHF not monitored)	Primary Secondary
REMARKS	Due to radio coverage limitations there is no low level coverage with Baghdad Approach below 3000FT AMSL in vicinity of ORBI.			

ORBI AD 2.19 RADIO NAVIGATION AND LANDING AIDS

Type of Aid	Ident	FREQ	Hours of operation	Position of antenna	Elevation of DME	Remarks
VOR 4E	BGD	110.6 MHz	H24	N33°15'38.6" E044°14'57.29"	N/A	Military Use Only PMI MON and THU 0400-0600
TACAN 4E	BGD	CH 43X	H24	N33°15'36.60" E044°14'58.10"	110 FT	Military Use Only
Remarks	Military Approach, Departure and Aerodrome information available from: https://164.214.2.62/products/digitalaero/index.cfm#flip Then under Terminal Instrument Procedure select Europe/North Africa/Middle East, then select Baghdad Intl ORBI					

ORBI AD 2.20 LOCAL TRAFFIC REGULATIONS

ORBI 2.20.1 Fixed wing aircraft conducting spiral approach or departure must remain within 3.5DME and shall use the following patterns:

ORBI 2.20.1.1 RWY 33 left traffic with left spiral (counter clockwise) climb and descent, and

ORBI 2.20.1.2 RWY 15 right traffic with right spiral (clockwise) climb and descent.

ORBI 2.20.1.3 Fixed wing departures from RWY 15 will make no right turns prior to departure end of runway. After departure end of runway, aircraft may initiate a right turn after reaching 800FT AGL unless cleared sooner by Baghdad Tower. Aircraft shall climb to be above 450FT AGL by 1.25NM south of departure end of runway due helicopter operations not above 300FT AGL.

ORBI 2.20.1.4 Fixed wing departures from RWY 33 via left downwind departure will initiate crosswind turn no earlier departure end of runway and at or above 400FT AGL, unless cleared sooner by Baghdad Tower. All aircraft shall climb to be above 800FT AGL by mid-field downwind or 450FT AGL by 1.25NM north of departure end of runway due helicopter operations not above 300FT AGL.

ORBI 2.20.1.5 Circling east of RWY 33R/15L is prohibited. Restricted areas located 1.3NM east of RWY 33R threshold 0.3NM radius centered at N33°15'26" E044°16'528" and 2.0NM east-northeast of RWY15L threshold 0.3NM radius centered at N33°20'42" E044°20'50" SFC to 1,500 FT MSL.

ORBI 2.20.1.6 Restricted area 1NM northwest of RWY 15R threshold 0.4 NM radius centered at N33°16'49.2" E044°12'07.8" SFC to 3,000FT MSL.

ORBI 2.20.2 Rotary wing operations are prohibited from over flight of tent city area, fuel storage and hardened aircraft shelter areas below 1000FT AGL (West side of Mil RWY).

ORBI 2.20.2.1 Rotary wing aircraft must use extreme caution landing and transitioning South Mike taxiway due to unlit obstructions.

ORBI 2.20.2.2 Rotary wing aircraft must land North helipad or South helipad unless otherwise directed by ATC.

ORBI 2.20.2.3 Rotary wing aircraft intending to shut down at BIAP must report landing assured to Baghdad Radio or home unit.

ORBI 2.20.3 Marshaller assistance is required and further information can be obtained from the TWR or SMC. When a local regulation is of importance for the safe operation of aircraft on the apron, the information shall be given to each aircraft by the TWR or SMC or broadcast on the ATIS.

ORBI 2.20.4 Local Traffic Regulations may be requested, in writing, from the Iraq Civil Aviation Authority at the address detailed in GEN 0.1.

ORBI 2.20.5 **Removal of disabled aircraft from RWY.** When an aircraft is disabled on a RWY, it is the duty of owner or user of such aircraft to have it removed as soon as possible. If a disabled aircraft is not removed from the RWY as quickly as possible by the owner or user, the aircraft will be removed by the aerodrome authority at the owner's or user's expense.

ORBI AD 2.21 NOISE ABATEMENT PROCEDURES

ORBI 2.21.1 Departures

Take-off to 1000 ft AGL	Take-off power and take-off flaps climb at V2 +10kt.
1000-3000 ft AGL	Climb at V2+10kt.
At 3000 ft AGL	Normal speed and flap retraction schedules to enroute climb.

Note: *Pilots unable to comply with above procedure shall inform ATC.*

ORBI 2.21.2 Arrivals

Execute final approach at the highest altitude possible (MAX 3000FT) observing ATC instructions, maintain this altitude as long as possible, at least until intercepting ILS glide slope. Reverse thrust other than idle shall not be used between 2330-0600 LMT except for safety reasons.

ORBI AD 2.22 FLIGHT PROCEDURES

ORBI 2.22.1 General

ORBI 2.22.1.1 Civilian aircraft must notify ATC if unable to operate VFR when below 12,000FT using the phrase “UNABLE VFR”. The use of VFR does not negate the requirement for aircraft to carry IFR fuel reserves.

ORBI 2.22.1.2 Where VFR operations are mandated, flights should be carried out in accordance with VFR as specified in ENR 1.2 and ICAO Annexes 2 and 11 (particularly regarding visibility and clearance from cloud). Compliance with these procedures does not relieve pilots of their responsibility to see and avoid other aircraft, or to maintain safe terrain/obstacle clearance at all times when operating VFR.

ORBI 2.22.2 Procedures within Baghdad TMA

ORBI 2.22.2.1 The inbound, transit and out bound routes on charts may be varied at the direction of ATS. If necessary, in case of congestion, inbound aircraft may also be instructed to hold at one of the designated airways reporting points.

ORBI 2.22.3 Radar procedures within Baghdad TMA:

ORBI 2.22.3.1 **Radar vectoring and sequencing.** Normally, aircraft will be vectored and sequenced from SOGUM and LOVEK reporting points to the appropriate final approach track (ILS,VOR/DME/TACAN), so as to ensure an expeditious flow of traffic. Radar vectors and flight levels/altitudes will be provided for spacing and separating the aircraft so that correct LDG intervals are maintained, taking into account aircraft characteristics. Radar vectoring charts are not published since the instrument approach procedures exists at all times until the point where the pilot will resume navigation on final approach or in the circuit.

ORBI 2.22.3.2 **Primary radar approaches.** Primary radar approaches will be carried out for RWYs 15L and 33R as step down commencing descent from 10 NM at an altitude of 900m. Primary radar final approaches will be terminated when aircraft established ILS or when aircraft report “Visual”. Missed approach procedure to be followed in the absence of other ATS instructions are as detailed on the Instrument Approach Charts.

ORBI 2.22.3.3 **Communication failure.** In the event of communication failure, pilots shall act in accordance with communication failure procedures in ICAO Annex 2.

ORBI AD 2.23 ADDITIONAL INFORMATION

ORBI 2.23.1 All aircraft arriving and departing ORBI shall operate VFR unless IMC exists. Practice instrument approaches and departures not available.

ORBI AD 2.24 CHARTS RELATED TO AN AERODROME

ICAO Charts for Baghdad International Airport		
Charts are under development for Baghdad. See http://164.214.2.62/products/digitalaero/index.html for the latest charts.		
1	Aerodrome Chart - ICAO	Not produced
2	Aircraft Parking/Docking Chart – ICAO	Not produced
3	Aerodrome Ground Movement Chart – ICAO	Not produced
4	Precision Approach Terrain Chart – ICAO	Not produced

5	Aerodrome Obstacle Chart – ICAO Type A	Not produced
6	Area Chart – ICAO (arrival and transit routes)	Not produced
7	Standard Departure Chart – Instrument – ICAO	Not produced
8	Area Chart – ICAO (arrival and transit routes)	Not produced
9	Standard Arrival Chart – Instrument - ICAO	Not produced
10	Instrument Approach Chart – ICAO	Not produced
11	Visual Approach Chart	Not produced
12	Bird concentration in the vicinity of the aerodrome	Not produced

ORBD AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORBD – Balad Southeast Airfield

ORBD AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N33°56'24.70" E044°21'41.70" The geographic center of the airfield
2	Direction and distance from city	Bearing 112° at 11NM
3	Elevation and Reference Temperature	161FT (49.07M) and 43.1°C
4	Geoid undulation	Not determined
5	Magnetic variation/Annual change	4°E as of Jan 2004, annual change E000°01'17.15"
6	Aerodrome Administration Address Telephone Telefax Telex AFS Address	This airfield is under the control of Coalition Forces. Balad Southeast Air Base Airfield Manager DSN 318-443-6065
7	Types of traffic permitted	IFR and VFR
8	Transition altitude and level	TA 13 000 FT AMSL, TL FL150
9	Remarks	All administrative matters are to be referred to the airport director. LDG, parking and fuel charges will be IAW published rates at GEN 4.1 and GEN 4.2. Charges MUST be paid in full in cash (\$US) prior to departure.

ORBD AD 2.3 OPERATIONAL HOURS

1	Aerodrome Administration	TBD
2	Customs and Immigration	HJ (H24 on request to ICAA)
3	Health and Sanitation	HJ (H24 on request to ICAA)
4	AIS Briefing Office	TBD
5	ATS Reporting Office	TBD
6	Met Office	DSN 318 458 1087
7	Air Traffic Services	H24
8	Fuelling	TBD
9	Handling	HJ (H24 on request to ICAA)
10	Security	H24
11	De-icing	Not available
12	Remarks	Limited facilities for non-military freight. Except for military, ICRC and UN sponsored flights, approval for HA flights is required from MNC-I. Prior Permission Required (PPRs): Balad ORBD is a PPR only airfield. PPRs are required for military and civil aircraft operating at these airfields. Aircraft not issued a PPR may be turned away or met by

		<p>security forces. PPR good for +/- 30 minutes from PPR approval time. Civil operators must contact these fields and receive a PPR before requesting a slot time into or out of Iraq from RAMCC.</p> <p><u>Contact information :</u></p> <p>BALAD (ORBD) Email: 332EOSS.OSAM@blab.centaf.af.mil DSN # for AIRFLD Manager is 318-443-6065</p> <p>Permission to operate in the Baghdad FIR is coordinated through Regional Air Movements Coordination Center (RAMCC). Refer GEN 1.2 for current procedures, requirements and contact information.</p>
--	--	--

ORBD AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	Military coordinated through Balad SE Command Post. Capability for main deck wide-body freighter. No storage for freight or passengers. Civil acft must pre-arrange with MOT and coord with ground personnel upon arrival.
2	Fuel and oil types	Limited supply of JP4 & GP8. Fuel services not AVBL for transient aircraft without a valid T-DODACC account. Cash sales not AVBL. If requesting 100K pounds or more expect 1 hour turn around. Nil oil
3	Fueling facilities and capacity	Limited. Plan flight without fuel from ORBD
4	De-icing facilities	Two trucks and deicing fluid available
5	Hanger space for visiting aircraft	Nil
6	Repair facilities for visiting aircraft	Nil
7	Remarks	Limited capacity for passenger operations. Handling services during daylight hours only or by arrangement with MoT and ICAA No catering, potable water or toilet conditioning available. Aircraft operators should expect to provide towing arm.

ORBD AD 2.5 PASSENGER FACILITIES

1	Hotels at/near aerodrome	Nil. Limited in the city
2	Restaurants	Nil
3	Transportation	Nil.
4	Medical facilities	Nil
5	Bank and Post Office	Nil
6	Tourist Office	Nil
7	Remarks	Nil

ORBD AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	RFF Cat 8
2	Rescue Equipment	TBC
3	Capability for removal of disabled aircraft	Limited assistance using military assets
4	Remarks	Nil

ORBD AD 2.7 SEASONAL AVAILABILITY

1	Type(s) of clearing equipment	Nil
2	Clearance priorities	Nil
3	Remarks	Nil

ORBD AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS DATA

1	Surface and strength of aprons	Fixed Wing TWYs are B, D, E G, H Rotary Wing TWYs are B, D, E, F, G, H, A1-A13, B1-B12
2	Width, surface and strength of TWYs	TWY B, C, G, H are 100 FT, TWY D and B1-B12 are 50 FT, TWY E & F 66 FT.
3	Location and elevation of altimeter checkpoints	33°57'00E 044°22'00N 180 FT AMSL 15 AGL
4	VOR and INS checkpoints	Not available
5	Remarks	Acraft must coordinate parking with tower/Command post/airfield management Aerobridges not AVBL. Fixed Wing parking is North Bravo Ramp, Transient Rotary Wing is TWY B7-B9. Compass rose on TWY C is not certified. Note: <i>All aircraft are to be directed by a marshaller to parking.</i>

ORBD AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	Use of aircraft stand ID signs, TWY guide lines and visual docking/parking guidance system at aircraft stands	No internally lit TWY or RWY signage or Distance Remaining Markers. Centerline markings do not depict actual centerline. Widths have been extended 100 FT on TWY
---	---	---

		CHARLIE, ECHO, HOTEL, and North/South entrances to BRAVO NORTH RAMP. Compass Rose on TWY CHARLIE not certified.
2	RWY and TWY markings and lights	RWY 12/30 & 14/32 Emergency Airfield Lighting System (EALS), in use operating at reduced intensity, non-standard lighting. Threshold, HIRL, PAPI, solar powered TWY lights.
3	Stop bars	Located on TWY's C, D and E.
4	Remarks	Mobile aircraft arresting system (MAAS) cables installed 2100 FT from the end of RWY 12 and 2400FT from the end of RWY 30; Normal operating position is for departure end cable in raised position

ORBD AD 2.10 AERODROME OBSTACLES

1	RWY12	ORBD Obstacle Chart not published
2	RWY14	ORBD Obstacle Chart not published
3	RWY30	ORBD Obstacle Chart not published
4	RWY32	ORBD Obstacle Chart not published
5	Remarks: The following additional obstructions have been identified:	
WTR1	Water tower	N33°56'50.84" E44°22'35.11" 300.6FT/91.63M
TWR1	Tower (Building)	N33°56'44.43" E44°22'15.70" 217.5FT/66.28M
CTWR	Control Tower	N33°56'52.41" E44°21'59.12" 260.1FT/79.29M

ORBD AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

ORBD 2.11.1 METRO Frequency is 131.85 MHz. Limited weather information, using the location designator of KQTO vice the ICAO airfield designator, is available from the following websites:

Open access website: <http://adds.aviationweather.noaa.gov/>
 Military only websites: <https://afwin.afwa.af.mil/> or <https://28ows.shaw.af.mil/>

ORBD AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	12	14	30	32
2	BRG True and Mag	125.66°T, 121.66°M	145.66°T, 141.66°M	305.67°T, 301.67°M	325.67°T, 321.67°M
3	RWY Dimensions	11459FT x 149FT (3493M x 45.4M)	11490FT x 197FT (3502M x 60M)	11459FT x 149FT (3493M x 45.4M)	11490FT x 197FT (3502M x 60M)
4	PCN	48 F/B/W/T	45RB	48 F/B/W/T	45RB
5	THR	33°56'44.25"N	33°57'25.18"N	33°55'37.95"N	33°55'51.32"N

	Coordinates	044°20'29.54" E	044°21'19.68" E	044°22'20.38" E	044°22'36.60" E
6	THR Elevation	155FT	159FT	158FT	160FT
7	Slope of RWY/SWY	Unknown	Unknown	Unknown	Unknown
8	SWY Dimensions	Unknown	Unknown	Unknown	Unknown
9	CWY Dimensions	Not calculated	Not calculated	Not calculated	Not calculated
10	Strip Dimensions	Not calculated	Not calculated	Not calculated	Not calculated
11	Obstacle free zone	Not calculated	Not calculated	Not calculated	Not calculated
12	Remarks	Departure end cable raised when RWY 12 is the duty RWY	Departure end cable raised when RWY 14 is the duty RWY	Departure end cable raised when RWY 30 is the duty RWY	Departure end cable raised when RWY 32 is the duty RWY
		RWY 13/33 Dirt Strip Closed Aircraft doing a 180 degree turn on the RWY will turn nose through East so as to point jet/prop blast towards the infield to decrease blowing FOD on TWY Bravo and aircraft parking areas. Use caution during wet RWY conditions. Increased potential for hydroplaning due rubber build up on RWY surface.			

ORBD AD 2.13 DECLARED DISTANCES

1	RWY	12	14	30	32
2	TORA	11495FT (3493M)	11490FT (3502M)	11495FT (3493M)	11490FT (3502M)
3	TODA	11495FT (3493M)	11490FT (3502M)	11495FT (3493M)	11490FT (3502M)
4	ASDA	11495FT (3493M)	11490FT (3502M)	11495FT (3493M)	11490FT (3502M)
5	LDA	11495FT (3493M)	11490FT (3502M)	11495FT (3493M)	11490FT (3502M)
6	Remarks	Nil	Nil	Nil	Nil

ORBD AD 2.14 APPROACH AND RUNWAY LIGHTING

Civil aircraft approved for LDG at Balad must review NOTAMs through their appropriate procedures. Advice on Balad SE approach and RWY lighting is available at the following military website: <https://www.notams.jcs.mil>

ORBD AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Aerodrome Beacon	Nil
2	Location and lighting of anemometer and LDG direction indicator	Not fitted
3	TWY edge and centerline lighting	Solar powered TWY edge lights
4	Secondary power supply including switch-over time	Operated on generator and backup generator. Switchover 20 minutes.
5	Remarks	Mobile Aircraft Arresting System (MAAS) and RWY 32/14 DRM left side are lit with non-standard flood lights.

ORBD AD 2.16 HELICOPTER LANDING AREA

1	Coordinates of touchdown and lift-off point (TLOF) threshold of final approach and take-off (FATO)	Approach End RWY 32: 33°56'00"N 44°22'29"E
2	TLOF and/or FATO area elevation	160FT
3	TLOF and FATO area dimensions, surface, strength, marking	RWY 12/30 surface 11495FT RWY 14/32 surface 11490FT
4	True and MAG BRG of FATO	145.66°T, 141.66°M
5	Declared distance available	RWY 12/30 11495FT, RWY 14/32 11490FT
6	Approach and FATO lighting	Emergency Airfield Lighting System: Threshold, REIL, HIRL, PAPI
7	Remarks	All rotary wing LDG will be to the ground with ground taxiing to parking. Pads 1, 2 & 4 are open and marked with an H. Pads 1 & 2 are located between RWY 12/30 and TWY A. Pad 4 is located at the northern end of RWY 12/30 no loading or unloading Pax or cargo on pads. Do not shut down on pads. TWY D between RWY12/30 and RWY14/32 is available for TKOF & LDG.

ORBD AD 2.17 AIR TRAFFIC SERVICES AIRSPACE

1	Airspace designation and lateral limits	Detailed in ENR 1.4
2	Vertical limits	
3	Airspace classification	

4	Callsign and Languages	Balad ... <i>(Tower or Approach)</i> English
5	Transition altitude	13 000FT
6	Remarks	ATS provided by military controllers operating IAW ICAO SARPs and USAF mil standards.

ORBD AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
ACC	Balad Center	123.525 MHz 274.575 MHz	H24	
APP	Balad Approach	131.9 MHz 255.8 MHz 128.200 MHz	H24	Alternate
TWR	Balad Tower	119.875 MHz 368.4 MHz	H24	
GROUND	Balad Ground	128.75 MHz 301.125 MHz	H24	
FINAL	Balad Final	126.425 MHz 246.425 MHz 128.200 MHz 242.500 MHz	H24	Alternate Alternate
ATIS	N/A	247.200 MHz	H24	Nil

ORBD AD 2.19 RADIO NAVIGATION AND LANDING AIDS

Type of Aid	Ident	Frequency	Hours of operation	Position of antenna	Elevation of DME	Remarks
TACAN 4E	BLD	CH93X	H24	N33°56'09.28" E044°22'05.01	160 FT	RWY 14/32 For Military Use Only
PAR 3°	N/A	As directed by APP	H24 (subject to staffing)	N33°56'34.26" E044°21'52.02"	N/A	RWY 32
SRA	N/A	As directed by APP	H24 (subject to staffing)	N33°56'34.26" E044°21'52.02"	N/A	RWY 14/32
Remarks	Military Approach, Departure and Aerodrome information available from: https://164.214.2.62/products/digitalaero/index.cfm#flip Then under Terminal Instrument Procedure select Europe/North Africa/Middle East, then select Balad Southeast ORBD. Radar out of service for preventative maintenance inspection 0200Z-0400Z daily.					

ORBD AD 2.20 LOCAL TRAFFIC REGULATIONS

ORBD 2.20.1 Local Traffic Regulations may be requested, in writing, from ICAA at the address detailed in GEN 0.1.

ORBD 2.20.2 Marshaller assistance may be requested and further information can be obtained from the TWR or SMC. When a local regulation is of importance for the safe operation of aircraft on the apron, the information shall be given to each aircraft by the TWR or SMC or broadcast on the ATIS.

ORBD 2.20.3 All aircraft use caution during approach and departure phases of flight due UAV activity.

ORBD 2.20.4 Aircraft must contact Balad Tower prior to 5NM.

ORBD 2.20.5 Fixed wing and UAV pattern, right traffic RWY 32, left traffic RWY 14, at 1200 FT AMSL.

ORBD 2.20.6 Fixed wing aircraft using the spiraling approach/departure procedure shall request traffic information on possible UAV activity above BSAB Class D airspace (6500-8000FT AMSL) from Baghdad Approach.

ORBD 2.20.7 Fixed wing aircraft departing RWY32 must fly RWY HDG until one-half mile past DEP end of RWY before executing DEP instructions.

ORBD 2.20.8 Rotary wing aircraft will avoid prolonged hover on areas between TWY's and RWYs

ORBD 2.20.9 Rotary wing aircraft are to avoid overflying living areas, fuel storage and hazardous areas below 600FT AGL while approaching or LDG Westside of Pad 1-4 or the FARP. Remain west of the airfield at 300FT AGL outside perimeter.

ORBD 2.20.10 Rotary wing aircraft will operate on the ground with anti-collision and position lights on low intensity (if avail), taxi/ LDG lights as required and no strobes. Aircraft must turn position indicator lights on steady, bright intensity, once established in the FARP's for visual identification by ATC.

ORBD 2.20.11 **Removal of disabled aircraft from RWY.** When an aircraft is disabled on a RWY, it is the duty of owner or user of such aircraft to have it removed as soon as possible. If a disabled aircraft is not removed from the RWY, by the owner or user, as quickly as possible, the aircraft will be removed by the aerodrome authority at the owner's or user's expense.

ORBD AD 2.21 NOISE ABATEMENT PROCEDURES

ORBD 2.21.1 Departures

Take-off to 1000 ft AGL	Take-off power and take-off flaps climb at V2 +10kt.
1000-3000 ft AGL	Climb at V2+10kt.
At 3000 ft AGL	Normal speed and flap retraction schedules to enroute climb.

Note: *Pilots unable to comply with above procedure shall inform ATC.*

ORBD 2.21.2 Arrivals

Execute final approach at the highest altitude possible (MAX 3000FT) observing ATC instructions, maintain this altitude as long as possible, at least until intercepting ILS glide slope.

Reverse thrust other than idle shall not be used between 2330-0600 LMT except for safety reasons.

ORBD AD 2.22 FLIGHT PROCEDURES

ORBD 2.22.1.General

ORBD 2.22.1.1 Within Class A airspace (i.e. above FL 290) all aircraft must operate Instrument Flight Rules (IFR). Additionally, civilian aircraft must operate IFR in Class B but are to operate VFR when flying in VMC in Class D, E and G airspace (flying below 12 000 FT AMSL). Civilian aircraft must notify ATC if unable to operate VFR when below 12 000 FT using the phrase "UNABLE VFR". The use of VFR does not negate the requirement for aircraft to carry IFR fuel reserves.

ORBD 2.22.1.2 In airspace where VFR operations are approved, flights should be carried out in accordance with VFR as specified in ENR 1.2 and ICAO Annexes 2 and 11 (particularly regarding visibility and clearance from cloud). Compliance with these procedures does not relieve pilots of their responsibility to see and avoid other aircraft, or to maintain safe terrain/obstacle clearance at all times when operating VFR.

ORBD 2.22.2 Procedures within Balad Southeast TMA

The inbound, transit and out bound routes on the charts may be varied at the direction of ATS. If necessary, in case of congestion, inbound aircraft may also be instructed to hold at one of the designated airways, reporting points.

ORBD 2.22.3 Radar procedures within Balad Southeast TMA (Update)

ORBD 2.22.3.1 **Radar vectoring and sequencing.** Normally, aircraft will be vectored and sequenced from SOGUM and SIGNI reporting points to the appropriate final approach track (RNAV(GPS), TACAN), so as to ensure an expeditious flow of traffic. Radar vectors and flight levels/altitudes will be provided for spacing and separating the aircraft so that correct LDG intervals are maintained, taking into account aircraft characteristics. Radar vectoring charts are not published since the instrument approach procedures exist at all times until the point where the pilot will resume navigation on final approach or in the circuit.

ORBD 2.22.3.2 **Primary radar approaches.** Primary radar approaches will be carried out for RWYs 14 and 32 as step down commencing descent from 10 NM at an altitude of 900m. Primary radar final approaches will be terminated when aircraft established ILS or when aircraft established visual contact. Missed approach procedure to be followed in the absence of other ATS instructions are as detailed on the Instrument Approach Charts.

ORBD 2.22.3.3 **Communication failure.** In the event of communication failure, pilots shall act in accordance with communication failure procedures in ICAO Annex 2.

ORBD AD 2.23 ADDITIONAL INFORMATION

All aircraft arriving and departing ORBD shall operate VFR unless IMC exists. Practice instrument approaches and departures not available.

ORBD AD 2.24 CHARTS RELATED TO AN AERODROME

ICAO Charts for Balad Southeast		
Charts are under development for Balad Southeast. See http://164.214.2.62/products/digitalaero/index.html for the latest charts.		
1	Aerodrome Chart - ICAO	Not produced
2	Aircraft Parking/Docking Chart – ICAO	Not produced
3	Aerodrome Ground Movement Chart – ICAO	Not produced
4	Precision Approach Terrain Chart – ICAO	Not produced
5	Aerodrome Obstacle Chart – ICAO Type A	Not produced
6	Area Chart – ICAO (arrival and transit routes)	Not produced
7	Standard Departure Chart – Instrument – ICAO	Not produced
8	Area Chart – ICAO (arrival and transit routes)	Not produced
9	Standard Arrival Chart – Instrument - ICAO	Not produced
10	Instrument Approach Chart – ICAO	Not produced
11	Visual Approach Chart	Not produced
12	Bird concentration in the vicinity of the aerodrome	Not produced

ORBR AD 2.1 AERODROME LOCATION INDICATOR AND NAME

Note: Information on Bashur is limited. Therefore the facilities and procedures listed below do not comply with the requirements of ICAO Annex 14.

ORBR – Bashur Airport

Facility	Detail	Comment
RWY Direction	RWY 13/31	RWY damage
RWY (LDA)	RWY 13 - 7333 x 150FT (2235 x 46M) RWY 31 - 4500 X 150FT (1372 x 46M)	
RWY (TODA)	RWY 13 – 4500 x 150FT (1372 x 46M) RWY 31 – 7333 x 150FT (2235 x 46M)	
Airport Elevation	2079 ft AMSL	
Obstruction Information	Nil information	
Frequency	Primary – 131.27 MHz	No secondary notified
Restrictions	Day VFR only	Inadequate lighting
Parking Details	In accordance with ATC instructions (when AVBL)	

ORMM AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORMM – Basrah International Airport

ORMM AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

The facilities and procedures listed below do not necessarily comply with, or adhere to, the requirements of ICAO Annex 14.

1	Aerodrome Reference Point coordinates and site	N30°32'56.646" E047°39'43.712" Located at the center of the RWY
2	Direction and distance from city	BRG 280° at 8NM
3	Elevation and Reference Temperature	11 FT, 44°C
4	Geoid undulation	Not determined
5	Magnetic variation/Annual change	3°E as of Jan 2004, Annual change E000°00'58.36"
6	Aerodrome Administration Address Telephone Telefax Telex AFS Address	Basrah International Airport Basrah-IRAQ. All administrative matters are to be referred to Flight Operations Manager on Synergie Red 963 4110. e-mail: Basrahairops@hotmail.com Mobile: 07801095874
7	Types of traffic permitted	IFR and VFR
8	Transition altitude and level	TA 13 000FT AMSL, TL FL150

ORMM AD 2.3 OPERATIONAL HOURS

1	Aerodrome Administration	H24
2	Customs and Immigration	HJ (H24 on request to ICAA)
3	Health and Sanitization	HJ (H24 on request to ICAA)
4	AIS Briefing Office	TBD
5	ATS Reporting Office	TBD
6	Met Office	TBD
7	Air Traffic Services	H24
8	Fuelling	HJ (must be pre-organized; military moves via Basrah Air OPS, civil moves via Skylink)
9	Handling	HJ (must be pre-organized; military moves via Basrah Air OPS, civil moves via Skylink)
10	Security	H24
11	De-icing	Not available
12	Remarks	All non RAF aircraft are to apply for PPR number from Basrah Air OPS at least 24hrs in advance of any intended movement. Slot times (+/- 15 min) are to be strictly adhered to. Aircraft arriving outside their allocated slot time may be subject to parking delays or refusal of permission to land. Civil

		<p>aircraft operators are to be aware that they operate entirely at their own risk as force protection measures may not be provided. Permission to operate in the Baghdad FIR is coordinated through Regional Air Movements Coordination Center (RAMCC). Refer GEN 1.2 for current procedures, requirements and contact information.</p> <p>Civil aircraft in VMC by day only. Fuel charges will be IAW RAF UK rates. Charges MUST be paid in full in cash (\$USD) prior to departure.</p> <p>Limited operations by civil registered aircraft are permitted into Basrah International Airport and may, on a case by case basis, be authorized subject to the following constraints: 1) All movements require a valid PPR. 2) Where practicable aircraft are to be defensive aid equipped. Requests for PPR approval should be made via email to basrahairops@hotmail.com. PPR requests should include full details of the purpose of the flight, proposed timings and a detailed manifest with reasons for travel. Aircraft operators are to be aware that they undertake flights into Iraq at their own risk and IAW information detailed at http://ramcc.dtic.mil/iraq.htm and in the Iraq AIP. Civil commercial operators are to ensure that their crews, aircraft and associated support/technical personnel are duly certified by their appropriate governments and that the proposed operations have been approved by the Iraq Ministry of Transport IAW the Memorandum of Understanding between the Government of Iraq and the Government of the United Kingdom of Great Britain and Northern Ireland.</p>
--	--	--

ORMM AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	<p>Skylink air logistics and support is now providing cargo handling/ground handling and jet-A1 refueling for aircraft essential to humanitarian and reconstruction efforts. Skylink offices are located in front of Bay 12 for detailed information contact Skylink at basrah.handling@skylink-usa.net.</p>
---	---------------------------	---

		Contact Skylink USA on frequency 120.925 MHz when inbound.
2	Fuel and oil types	<p>Small quantities JP8 and Jet A1 available by PPR only. Crews encouraged carrying round-trip fuel or, if possible, uplifting from Kuwait International Airport.</p> <p>Due to shortage of fuel civil users are to make their request to Skylink in advance. basrah.handling@skylink-usa.net</p> <p>Due to operational requirements there will be limited commercial aviation jet A1 fuel at Basrah Intl Airport. All commercial fuel requests should be submitted via e-mail to basrah.handling@skylink-usa.net. Avcard fuel credit cards accepted by Skylink. Jet A1 prices \$1.50/GAL for cash purchases, \$1.58/GAL for credit purchases. For more information contact Skylink fuels department at bhookins@skylink-usa.net.</p> <p>Nil oil</p>
3	Fueling facilities and capacity	See Cargo above
4	De-icing facilities	Nil
5	Hanger space for visiting aircraft	Nil
6	Repair facilities for visiting aircraft	Nil
7	Remarks	<p>Handling services during daylight hours only or by arrangement with Skylink.</p> <p>Basrah Airfield is strictly PPR. Aircraft arriving outside of PPR slot can expect to hold until Ramp space is available.</p>

ORMM AD 2.5 PASSENGER FACILITIES

1	Hotels at/near aerodrome	Nil. High-rise hotels in the city
2	Restaurants	Nil. Unlimited in the city
3	Transportation	Nil
4	Medical facilities	Emergency cover for military only
5	Bank and Post Office	Nil.
6	Tourist Office	Nil
7	Remarks	Nil

ORMM AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	RFF Cat 8, RAF Cat4A (5A by PPR) USAF Equivalent 2, FAA equivalent C/D
---	--------------------------------------	--

2	Rescue Equipment	4 Carmichael Major Foam Vehicles and 1 Alvis/Unipower Rapid Intervention vehicle
3	Capability for removal of disabled aircraft	Limited assistance using military assets
4	Remarks	NIL

ORMM AD 2.7 SEASONAL AVAILABILITY

1	Type(s) of clearing equipment	Nil
2	Clearance priorities	Nil
3	Remarks	Nil

ORMM AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS DATA

1	Surface and strength of aprons	Main Apron: Concrete - PCN - 100/R/B/W/T Hotel Apron: Concrete-PCN- 100/R/C/W/T.
2	Width, surface and strength of TWYs	Width: 23M Surface: Concrete Strength: PCN - 100/R/B/W/T
3	Location and elevation of altimeter checkpoints	On apron at 30°32'47"N 47°39'55"E 10 FT
4	VOR and INS checkpoints	Not available
5	Remarks	8 TWYs, 3 Aprons

ORMM AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	Use of aircraft stand ID signs, TWY guide lines and visual docking/parking guidance system at aircraft stands	See ORMM AD 2-24
2	RWY and TWY markings and lights	Blue edge-lights at fast turn-offs (TWY B and C) only.
3	Stop bars	Stop bars where appropriate
4	Remarks	Nil

ORMM AD 2.10 AERODROME OBSTACLES

1	RWY14	ORMM Obstacle Chart not available
2	RWY32	ORMM Obstacle Chart not available
3	Tethered Balloon	Position N31 46.29 E47 06.14. SFC to 450FT AGL. Reflective tape on wires

ORMM AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

ORMM 2.11.1 Limited weather information, using the ICAO airfield designator, is available from the following websites:

Open access website: <http://adds.aviationweather.noaa.gov/>
Military only websites: <https://afwin.afwa.af.mil/> or <https://28ows.shaw.af.mil/>

ORMM 2.11.2 METAR and TAF information for Basrah available on EQBK (Mobile Meteorological Unit)

ORMM AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	14	32
2	BRG True and Mag	138T, 135°M	318°T, 315°M
3	RWY Dimensions	13123FT x 148FT (4000M x 45M)	13123FT x 148FT (4000M x 45M)
4	PCN	105	105
5	THR Coordinates	30°33.73'N 047°38.91'E	30°32.13'N 047°40.58E
6	THR Elevation	10FT	10FT
7	Slope of RWY/SWY	Unknown	Unknown
8	SWY Dimensions	300FT	300FT
9	CWY Dimensions	Not calculated	Not calculated
10	Strip Dimensions	Not calculated	Not calculated
11	Obstacle free zone	Not calculated	Not calculated
12	Remarks	Nil	Nil

ORMM AD 2.13 DECLARED DISTANCES

1	RWY	14	32
2	TORA	13123FT (4000M)	13123FT (4000M)
3	TODA	13123FT (4000M)	13123FT (4000M)
4	ASDA	13123FT (4000M)	13123FT (4000M)
5	LDA	13123FT (4000M)	13123FT (4000M)
6	Remarks	Nil	Nil

ORMM AD 2.14 APPROACH AND RUNWAY LIGHTING

Further information on Basrah's approach and RWY lighting is available at the following military website:

<https://www.notams.jcs.mil>

1	RWY	14	32
2	Type, length and intensity of approach lighting	Low intensity uni-directional centerline with single crossbar	Low intensity uni-directional centerline with single crossbar
3	Threshold lights, colors and wing bars	2-light green wing bars adjacent to operating surface.	2-light green wing bars adjacent to operating surface.
4	Type of visual approach slope indicator system	Abbreviated PAPI display on left-hand side of RWY, set to 3 degrees	Abbreviated PAPI display on left-hand side of RWY, set to 3 degrees
5	Length of RWY touchdown zone indicator lights	Not available	Not available
6	Length spacing color and intensity of RWY centerline lights	Not available	Not available
7	Length spacing color and intensity of RWY edge lights	Single white low-intensity Omni-directional lights every 330FT (100M) on both sides.	Single white low-intensity Omni-directional lights every 330FT (100M) on both sides.
8	Color of RWY end lights and wingbars	2-light wing bars adjacent to operating surfaces	2-light wing bars adjacent to operating surfaces
9	Length and color of stopway lights	Not available	Not available
10	Remarks	Nil	Nil

ORMM AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Aerodrome Beacon	Not available
2	Location and lighting of anemometer and LDG direction indicator	Not available
3	TWY edge and centerline lighting	Nil TWY centerline lighting Blue edge-lights at fast turn-offs (TWY B and C) only. Other TWYs marked by retro-reflectors.
4	Secondary power supply including switch-over time	Secondary power to all airfield lighting, switch-over time: 1 minute
5	Remarks	No obstruction lights No serviceable RWY holding point lights Main Apron floodlight available No signal lamps in Tower

	Aerodrome signs not lit
--	-------------------------

ORMM AD 2.16 HELICOPTER LANDING AREA

1	Coordinates of touchdown and lift-off point (TLOF) threshold of final approach and take-off (FATO)	To be determined
2	TLOF and/or FATO area elevation	To be determined
3	TLOF and FATO area dimensions, surface, strength, marking	To be determined
4	True and MAG BRG of FATO	To be determined
5	Declared distance available	To be determined
6	Approach and FATO lighting	To be determined
7	Remarks	Nil

ORMM AD 2.17 AIR TRAFFIC SERVICES AIRSPACE

1	Airspace designation and lateral limits	Detailed ENR 1.4
2	Vertical limits	
3	Airspace classification	
4	Callsign and Languages	Basrah ... <i>(Tower or Approach)</i> Ali <i>(Control)</i> . English
5	Transition altitude	13 000 FT
6	Remarks	Aircraft inbound LDG Basrah from Kuwait FIR are to call Basrah approach 119.4MHz or 233.225MHz by TASMI

ORMM AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
APP	Basrah Approach	119.4 MHz 233.225 MHz	H24	Primary Secondary
TWR	Basrah Tower	118.7 MHz 241.175 MHz	H24	Primary Secondary
INFORMATION	Basrah Information	125.9 MHz 241.175 MHz	H24	Primary Secondary
FINAL	Basrah Final	123.1 MHz 233.225 MHz	H24	Primary Secondary
Remarks	All Basrah ATS provided by military controllers operating IAW UK Mil AIP however, QNH will be used throughout.			

ORMM AD 2.19 RADIO NAVIGATION AND LANDING AIDS

Type of Aid	Ident	Freq	Hours of operation	Position of antenna	Elevation of DME	Remarks
TACAN 3°	BAR	108.3 MHz CH 20X	H24	N30°32'55.8" E047°39'35.4"		RWY 14/32
SRA	Basrah Final		H24	N/A		RWY 14/32

VOR DME	BSR	112.3 CH 70X	H24	N30 31.54 E 047 41.20		RWY 14/32
------------	-----	-----------------	-----	--------------------------	--	--------------

ORMM AD 2.20 LOCAL TRAFFIC REGULATIONS

ORMM 2.20.1 For operational reasons ATC may require approach to RWY 14 for LDG RWY 32.

ORMM 2.20.2 VFR approaches available on request, irregular, randomized approach points are encouraged. At night below 15000FT AMSL, all internal and external lights to be switched off, if possible, until short finals. Civilian operators are to avoid making a 40min/Time Of Departure call unless requesting a revised slot time. SIDs are available, however aircraft are encouraged to make non-standard VFR departures onto random initial departures tracks. Unless on a SID, aircraft MUST depart VFR. IFR available when above safety altitude of 1500FT AMSL.

ORMM 2.20.3 **Removal of disabled aircraft from RWY.** When an aircraft is disabled on a RWY, it is the duty of owner or user of such aircraft to have it removed as soon as possible. If a disabled aircraft is not removed from the RWY, by the owner or user, as quickly as possible, the aircraft will be removed by the aerodrome authority at the owner's or user's expense.

ORMM 2.20.4 Circuit Heights.

Light Aircraft circuit height.– 1,000FT

Normal circuit height – 1,500FT

ORMM AD 2.21 NOISE ABATEMENT PROCEDURES

2.21.1 Departures

Take-off to 1000 ft AGL Take-off power and take-off flaps climb at V2 +10kt.

1000-3000 ft AGL Climb at V2+10kt.

At 3000 ft AGL Normal speed and flap retraction schedules to enroute climb.

Note: *pilots unable to comply with above procedure shall inform ATC.*

ORMM 2.21.2 Arrivals

Execute final approach at the highest altitude possible (MAX 3000FT) observing ATC instructions, maintain this altitude as long as possible, at least until intercepting ILS glide slope.

Reverse thrust other than idle shall not be used between 2330-0600 LMT except for safety reasons.

ORMM AD 2.22 FLIGHT PROCEDURES

ORMM 2.22.1 Civilian aircraft must notify ATC if unable to operate VFR when below 12,000FT using the phrase "UNABLE VFR". The use of VFR does not negate the requirement for aircraft to carry IFR fuel reserves.

ORMM 2.22.2 Where VFR operations are mandated, flights should be carried out in accordance with VFR as specified in ENR 1.2 and ICAO Annexes 2 and 11 (particularly regarding visibility and clearance from cloud). Compliance with these procedures does not relieve pilots of their responsibility to see and avoid other aircraft, or to maintain safe terrain/obstacle clearance at all times when operating VFR

ORMM AD 2.23 ADDITIONAL INFORMATION

Nil

ORMM AD 2.24 CHARTS RELATED TO AN AERODROME

Approach, Aerodrome and Taxi Charts for Basrah are under construction. Refer to AIDU website or via the address below for latest information.

<http://www.aidu.mod.uk>

No 1 AIDU (RAF)
RAF Northolt
West End Road
Ruislip
Middex HA4 6NG
UK

ICAO Charts for Basrah International Airport		
1	Aerodrome Chart - ICAO	
2	Aircraft Parking/Docking Chart – ICAO	
3	Aerodrome Ground Movement Chart – ICAO	
4	Precision Approach Terrain Chart – ICAO	
5	Aerodrome Obstacle Chart – ICAO Type A	
6	Area Chart – ICAO (arrival and transit routes)	
7	Standard Departure Chart – Instrument – ICAO	
8	Area Chart – ICAO (arrival and transit routes)	
9	Standard Arrival Chart – Instrument - ICAO	
10	Instrument Approach Chart – ICAO	
11	Visual Approach Chart	Not produced
12	Bird concentration in the vicinity of the aerodrome	

ORER AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORER – Erbil International Airport

ORER AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N36°14.26' E043°57.79'
2	Direction and distance from city	318°MAG, 3.7 NM
3	Elevation and Reference Temperature	1341 FT AMSL
4	Aerodrome Administration Address Telephone Telefax Telex AFS Address	Kurdistan Regional Government (KRG) Erbil International Airport B.O. Box No 8 Ph: 0032484459767 or 008821667700111 E-mail: arbilgc@yahoo.com Website:
5	Magnetic variation	TBD
6	Types of traffic permitted	VFR (IFR ops to be confirmed)
7	Transition altitude and level	TA 13 000 FT AMSL, TL FL150
8	Remarks	All administrative matters are to be referred to the airport manager. LDG and parking charges will be IAW published rates at GEN 4.1 and GEN 4.2. Charges MUST be paid in full in cash (\$US) prior to departure.

ORER AD 2.3 OPERATIONAL HOURS

1	Aerodrome Administration	TBD
2	Customs and Immigration	H24 with prior approval – contact airport manager
3	Health and Sanitation	TBD
4	AIS Briefing Office	TBD
5	ATS Reporting Office	TBD
6	Met Office	TBD
7	Air Traffic Services	Nil
8	Fuelling	H24 with prior approval – contact airport manager
9	Handling	H24 with prior approval – contact airport manager
10	Security	H24
11	De-icing	Not available
12	Remarks	Civil aircraft are authorized to operate 24 hours a day. Prior Permission Required (PPRs): Erbil ORER, is a PPR only airfield. PPRs are required for military and civil aircraft operating at this airfield. Civil operators must contact the airfield management for a PPR before requesting a slot time into or out of Iraq from RAMCC. PPRs are valid +/- 30 MIN from ETA. <u>Contact information :</u> Kurdistan Regional Government (KRG)

		<p>Erbil Airport B.O. Box No 8 Ph: 0032484459767 or 008821667700111 E-mail: arbilgc@yahoo.com</p> <p>Permission to operate in the Baghdad FIR is coordinated through Regional Air Movements Coordination Center (RAMCC). Refer GEN 1.2 for current procedures, requirements and contact information.</p>
--	--	--

ORER AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	Contact Airport Manager
2	Fuel and oil types	Contact Airport Manager
3	Fueling facilities and capacity	Contact Airport Manager
4	De-icing facilities	Nil
5	Hanger space for visiting aircraft	Nil
6	Repair facilities for visiting aircraft	Nil
7	Remarks	Nil

ORER AD 2.5 PASSENGER FACILITIES

1	Hotels at/near aerodrome	TBD
2	Restaurants	TBD
3	Transportation	TBD
4	Medical facilities	Medical Center available
5	Bank and Post Office	TBD
6	Tourist Office	TBD
7	Remarks	Nil

ORER AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	RFF Cat 7
2	Rescue Equipment	TBD
3	Capability for removal of disabled aircraft	TBD
4	Remarks	Nil

ORER AD 2.7 SEASONAL AVAILABILITY

1	Type(s) of clearing equipment	TBD
2	Clearance priorities	TBD
3	Remarks	Nil

ORER AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS DATA

1	Surface and strength of aprons	Separate passenger and cargo aprons available. Apron strength TBD. Both aprons have capacity for four medium sized aircraft.
---	--------------------------------	--

2	Width, surface and strength of TWYs	No main TWY available, aircraft required to back track on RWY. Three exit TWYs available. TWY strength TBD.
3	Location and elevation of altimeter checkpoints	Not available
4	VOR and INS checkpoints	Not available
5	INS Checkpoints	TBD
6	Remarks	Nil

ORER AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	Use of aircraft stand ID signs, TWY guide lines and visual docking/parking guidance system at aircraft stands	TBD
2	RWY and TWY markings and lights	RWY markings threshold, centerline, touchdown RWY lighting approach, threshold, centerline and edge. TWYs marked to ICAO standard. TWYs centerline lighting.
3	Stop bars	TBD
4	Remarks	Nil

ORER AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	15	33
2	BRG True and Mag	152.0°T, (TBD)°M	332.0°T, (TBD)°M
3	RWY Dimensions	9186 x 98FT (2800M x 30M)	9186 x 98FT (2800M x 30M)
4	PCN	6S/F/A/W/T	6S/F/A/W/T
5	THR Coordinates	N36°14'52.54" E043°57'22.32"	N36°13'38.22" E043°58'12.00"
6	THR Elevation	TBD	TBD
7	Slope of RWY	0.085%	0.085%

ORER AD 2.14 APPROACH AND RUNWAY LIGHTING

1	RWY	15	33
2	Type, length and intensity of approach lighting	TBA	TBA
3	Threshold lights, colors and wing bars	TBA	TBA
4	Type of visual approach slope indicator system	PAPI	PAPI
5	Length of RWY touchdown zone indicator lights	TBA	TBA
6	Length spacing color and intensity of RWY centerline lights	TBA	TBA
7	Length spacing color and intensity of RWY edge lights	TBA	TBA
8	Color of RWY end lights and wingbars	TBA	TBA
9	Length and color of stopway lights	TBA	TBA
10	Remarks	TBA	TBA

ORER AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Aerodrome Beacon	Yes
2	Location and lighting of anemometer and LDG direction indicator	IWI
3	TWY edge and centerline lighting	
4	Secondary power supply including switch-over time	TBD
5	Remarks	Nil

ORER AD 2.17 AIR TRAFFIC SERVICES AIRSPACE

1	Airspace designation and lateral limits	Uncontrolled airport
2	Vertical limits	Nil
3	Airspace classification	Class G
4	Callsign and Languages	English
5	Transition altitude	13 000 FT
6	Remarks	See ORER 2.18.

ORER AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
ACC	Kirkuk Center	125.30 MHz 237.325 MHz	H24	Primary Secondary
REMARKS	Kirkuk Center will provide an enroute service to the base of Class E airspace, (4,000FT AMSL).			

ORJA AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORJA – Jalibah Southeast Airport

ORJA AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N30°32'42.00" E046°36'12.00" The geographic center of the airfield
2	Elevation and Reference Temperature	105FT (32M) and 43.1°C

ORJA AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	12L/30R	12R/30L	12C/30C
2	BRG True and Mag	TBD	TBD	TBD
3	RWY Dimensions	11309 x 98FT (1065M x 32M)	11340 x 98FT (2609M x 29M)	9990 x 148FT (2609M x 29M)
4	PCN	TBD	TBD	TBD
5	THR Coordinates	TBD	TBD	TBD
6	THR Elevation	TBD	TBD	TBD

ORKK AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORKK – Kirkuk Airport

ORKK AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N35°28'10.12" E044°20'56.16" The geographic center of the airfield
2	Direction and distance from city	Bearing 277° at 2NM
3	Elevation and Reference Temperature	1061FT (323.4 M) and 43.1°C
4	Geoid undulation	Not determined
5	Magnetic variation/Annual change	4°E as of Jan 2004, annual change E000°01'22.16"
6	Aerodrome Administration Address Telephone AFS Address	Iraq Civil Aviation Authority Baghdad International Airport Baghdad Airfield Management DSN 318 444 2456 Civil acft by day only
7	Types of traffic permitted	IFR, VFR and SVFR (civil and RW only)
8	Transition altitude and level	TA 13 000 FT AMSL, TL FL150
9	Remarks	Abandoned airfield (K-1) at KKK R307/004 (N35 45.44 E044 17 03.97) located in close proximity to ORKK. All administrative matters are to be referred to the airport director. LDG, parking and fuel charges will be IAW published rates at GEN 4.1 and GEN 4.2. Charges MUST be paid in full in cash (\$US) prior to departure.

ORKK AD 2.3 OPERATIONAL HOURS

1	Aerodrome Administration	H24
2	Customs and Immigration	Nil
3	Health and Sanitation	Nil
4	AIS Briefing Office	H24
5	ATS Reporting Office	H24
6	Met Office	DSN 318 444 2460
7	Air Traffic Services	H24
8	Fuelling	H24
9	Handling	H24
10	Security	H24
11	De-icing	Nil
12	Remarks	Aircraft must have Prior Permission Required (PPR) for Kirkuk except for mil RW aircraft LDG at FARP. RW aircraft repositioning from the FARP to AMC or DV ramp must coordinate with Airfield Management on 119.25MHz or 253.7MHz before departing the FARP. Civil operators

		<p>must receive a PPR before requesting a slot time from RAMCC. Aircraft not issued a PPR may be turned away.</p> <p>To obtain PPR information contact Airfield Management at DSN (318) 444-2456/2457, or by E-Mail on the global address list under KRAB 506 EOSS AM OPS: 506eoss.amops@krab.centaf.af.mil 506eoss.amops@krab.aorcentaf.af.mil</p> <p>No instrument approaches and departures for civil aircraft. Limited facilities for non-military freight. Except for military, ICRC and UN sponsored flights, approval for HA flights is required from MNC-I.</p> <p>Permission to operate in the Baghdad FIR is coordinated through Regional Air Movements Coordination Center (RAMCC). Refer GEN 1.2 for current procedures, requirements and contact information.</p>
--	--	--

ORKK AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	<p>Military coordinated through Kirkuk Command Post. Capability for main deck wide-body freighter. No storage for freight or passengers Civil acft must pre-arrange with MOT and coord with ground personnel upon arrival.</p>
2	Fuel and oil types	JP8
3	Fueling facilities and capacity	<p>Limited. Plan flight without fuel from ORKK</p> <p>Use of position lights are mandatory for all helicopters using the North ramp FARP from sunrise to sunset.</p>
4	De-icing facilities	Nil
5	Hanger space for visiting aircraft	Nil
6	Repair facilities for visiting aircraft	Nil
7	Remarks	<p>Limited capacity for passenger operations. Handling services during daylight hours only or by arrangement with MOT and ICAA Military aircraft contact command post 'Stone Krab' on 128.1MHz, 245.6MHz 10 minutes prior to ETA Civil aircraft - Phone DSN 318 444 2456, 318 444 0085.</p>

	No catering, potable water or toilet conditioning available. Aircraft operators should expect to provide towing arm.
--	--

ORKK AD 2.5 PASSENGER FACILITIES

1	Hotels at/near aerodrome	Military billeting AVBL on limited basis.
2	Restaurants	AVBL
3	Transportation	AVBL
4	Medical facilities	AVBL
5	Bank and Post Office	Postal Services AVBL
6	Tourist Office	Nil
7	Remarks	Nil

ORKK AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	Airport Category 7
2	Rescue Equipment	T-3000 X 2 P-19 X 3 P-18 X 1
3	Capability for removal of disabled aircraft	Limited assistance using military assets
4	Remarks	Nil

ORKK AD 2.7 SEASONAL AVAILABILITY

1	Type(s) of clearing equipment	Nil
2	Clearance priorities	Nil
3	Remarks	Nil

ORKK AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS DATA

1	Surface and strength of aprons	All parking aprons are rated PCI "GOOD", however a potential FOD hazard exists for all due to weathered joint seals. All heavy acft (C5 and heavier) are restricted to LDG and parking on RWY 13/31
2	Width, surface and strength of TWYs	All TWYs are asphalt. Widths are as follows: TWY A – 65FT TWY B – 60FT; 50FT wide between RWY 13/31 and RWY 14/32 TWY C – 50FT TWY D – 50FT TWY E – 50FT TWY F – 50FT immediately west of RWY 14/32; increasing to 66FT intersecting RWY 13/31 TWY G – 50FT TWY H – 50FT TWY J – 50FT

		TWY K – 50FT TWY L – 50FT TWY M – 50FT (mil use only) TWY N – 50FT (mil use only) TWY O – 50FT (mil use only) TWY P – 50FT (mil use only) TWY Q – 50FT (mil use only) TWY R – 50FT (mil use only) TWY S – 50FT (mil use only) TWY T – 50FT (mil use only) TWY U – 50FT (mil use only) TWY V – 50FT (mil use only) TWY Z – 50FT
3	Location and elevation of altimeter checkpoints	Not available at this time.
4	VOR and INS checkpoints	Not available
5	Remarks	Acft must coordinate parking with tower/Command post/airfield management Aerobridges not AVBL. A TWY north of Control Tower limited to aircraft with 135FT wingspan or less due obstructions. Follow me van will be provided. Note: <i>All aircraft are to be directed by a marshaller to parking.</i>

ORKK AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	Use of aircraft stand ID signs, TWY guide lines and visual docking/parking guidance system at aircraft stands	See ORKK AD 2-24 charts
2	RWY and TWY markings and lights	No approach lights. Emergency Airfield Lighting System (EALS) in use operating at reduced intensity, non-standard lighting.
3	Stop bars	Stop bars where appropriate (VFR hold lines)
4	Remarks	Use caution when taxiing from RWY 13 to TWY ALPHA. Raised threshold lights on approach end RWY 32 approximately 33 FT from RWY 13/31 extended centerline.

ORKK AD 2.10 AERODROME OBSTACLES

1	RWY 13	ORKK Obstacle Chart not published
2	RWY 14	ORKK Obstacle Chart not published
3	RWY 31	ORKK Obstacle Chart not published
4	RWY 32	ORKK Obstacle Chart not published
5	Remarks: All obstructions are unlit. The following additional obstructions have been identified:	
CTWR	Control Tower	N35°28'02.89" E44°21'27.96" 1147.1FT/349.64M

WT1	Water Tower	N35°27'10.47" E44°22'18.02" 1175.7FT/358.36M
-----	-------------	--

ORKK AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

ORKK 2.11.1 Weather warnings, watches and advisories, Pilot to Metro Service, observations and Terminal Area Forecasts and other services are available. For more information contact the Met Office on DSN (318) 444 2690.

ORKK 2.11.2 Limited weather information, using the location designator of KQTX vice the ICAO airfield designator, is available from the following websites:

Open access website: <http://adds.aviationweather.noaa.gov/>
 Military only websites: <https://afwin.afwa.af.mil/> or <https://28ows.shaw.af.mil/>

ORKK AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	13	14	31	32
2	BRG True and Mag	133.26°T, 129.26°M	145.31°T, 141.31°M	313.27°T, 309.27°M	325.32°T, 321.32°M
3	RWY Dimensions	9809FT x 148FT (2990M x 45M)	8535FT x 160FT (2601M x 49M)	9809FT x 148FT (2990M x 45M)	8535FT x 160FT (2601M x 49M)
4	PCN	46/R/B/W/T	79/F/B/W/T	46/R/B/W/T	79/R/B/W/T
5	THR Coordinates	N35°28'44.12" E044°20'04.07"	N35°28'43.97" E044°20'37.03"	N35°27'37.63" E044°21'30.43"	N35°27'34.55" E044°21'35.75"
6	THR Elevation	1033 FT	1050FT	1059FT	1061FT
7	Slope of RWY/SWY	Unknown	Unknown	Unknown	Unknown
8	SWY Dimensions	Unknown	Unknown	Unknown	Unknown
9	CWY Dimensions	Not calculated	Not calculated	Not calculated	Not calculated
10	Strip Dimensions	Not calculated	Not calculated	Not calculated	Not calculated
11	Obstacle free zone	Not calculated	Not calculated	Not calculated	Not calculated
12	Remarks	Mobile arresting gear 1910ft fm approach end	Nil	Mobile arresting gear 2036ft fm approach end	Nil

		For MAAS cable removal please contact Kirkuk Tower NLT 45 minutes prior to arrival on FREQ 125.55MHz. or 327.8MHz. Potential FOD hazard exists. Unless in EMERGENCY situations, fighter aircraft should not use reverse thrust. Men and Equipment located 200FT from the edge of RWY 13/31
--	--	--

ORKK AD 2.13 DECLARED DISTANCES

1	RWY	13	14	31	32
2	TORA	9809FT (2990M)	8535FT (2601M)	9809FT (2990M)	8535FT (2601M)
3	TODA	9809FT (2990M)	8535FT (2601M)	9809FT (2990M)	8535FT (2601M)
4	ASDA	9809FT (2990M)	8535FT (2601M)	9809FT (2990M)	8535FT (2601M)
5	LDA	9809FT (2990M)	8535FT (2601M)	9809FT (2990M)	8535FT (2601M)
6	Remarks	Nil	Nil	Nil	Nil

ORKK AD 2.14 APPROACH AND RUNWAY LIGHTING

ORKK 2.14.1 Advice on Kirkuk's approach and RWY lighting is available at the following military website:

<https://www.notams.jcs.mil>.

1	RWY	13	14	31	32
2	Type, length and intensity of approach lighting	NONE	NONE	NONE	NONE
3	Threshold lights, colors and wing bars	EALS raised	EALS raised	EALS raised	EALS raised
4	Type of visual approach slope indicator system	PAPI	PAPI	PAPI	PAPI
5	Length of RWY touchdown zone indicator lights	NONE	NONE	NONE	NONE
6	Length spacing color and intensity of RWY centerline lights	NONE	NONE	NONE	NONE

7	Length spacing color and intensity of RWY edge lights	200FT	200FT	200FT	200FT
8	Color of RWY end lights and wingbars	NONE	NONE	NONE	NONE
9	Length and color of stopway lights	NONE	NONE	NONE	NONE
10	Remarks	PAPI only available when emergency airfield lighting system is turned on. Airfield blackout operations in effect daily from sunset to sunrise. See European, North Africa and Middle East Enroute Supplement for additional information. All airfield lighting is EALS			

ORKK AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Aerodrome Beacon	Nil
2	Location and lighting of anemometer and LDG direction indicator	Not fitted
3	TWY edge and centerline lighting	EALS/solar powered lights installed.
4	Secondary power supply including switch-over time	No secondary power supply for solar TWY lights. Lights are replaced as needed.
5	Remarks	Nil

ORKK AD 2.16 HELICOPTER LANDING AREA

1	Coordinates of touchdown and lift-off point (TLOF) threshold of final approach and take-off (FATO)	To be determined
2	TLOF and/or FATO area elevation	To be determined
3	TLOF and FATO area dimensions, surface, strength, marking	To be determined
4	True and MAG BRG of FATO	To be determined
5	Declared distance available	To be determined
6	Approach and FATO lighting	To be determined
7	Remarks	Nil

ORKK AD 2.17 AIR TRAFFIC SERVICES AIRSPACE

1	Airspace designation and lateral limits	Detailed in ENR 1.4
2	Vertical limits	

3	Airspace classification	
4	Callsign and Languages	Kirkuk ...(<i>Tower, Approach</i>), Kirkuk (<i>Center</i>). – English
5	Transition altitude	13 000 FT
6	Remarks	ATS provided by military controllers operating IAW USAF/FAA Standards. All aircraft (fixed wind and rotary) approaching Kirkuk ATC as soon as possible for airfield update and threat status.

ORKK AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
ACC	Kirkuk Control	125.30MHz 237.325MHz 125.050MHz 264.200MHz	H24	Primary Secondary
APP	Kirkuk Approach	129.750 MHz 264.2 MHz	H24	Primary Secondary
TWR	Kirkuk Tower	125.550 MHz 327.800 MHz	H24	Primary Secondary
GROUND	Kirkuk Ground	127.375 MHz 256.45 MHz	H24	Primary Secondary
ATIS	N/A	N/A	H24	Nil

ORKK AD 2.19 RADIO NAVIGATION AND LANDING AIDS

Type of Aid	Ident	FREQ	Hours of operation	Position of antenna	Elevation of DME	Remarks
TACAN 4E	KRK	CH86X	H24	N35°28'16.42" E44°20'52.45"	1049 FT	Military Use Only. PMI WED 0400Z-0600Z
PAR 3°	N/A	As directed by APP	H24 (subject to staffing)	N35°28'10.12" E44°20'56.98"	N/A	RWY 13. Military Use Only. PMI SAT – TUE & THU 0400Z – 0600Z WED 0600Z FRI 0400Z – 0800Z
ASR 4E	N/A	As directed by APP	H24 (subject to staffing)	N35°28'11.69" E44°20'58.03"	N/A	PMI SAT – TUE & THU

						1900Z – 2059Z
Remarks	Approach, Departure and Aerodrome information available from: https://164.214.2.62/products/digitalaero/index.cfm#flip Then under Terminal Instrument Procedure select Europe/North Africa/Middle East, then select Kirkuk and add ORKK					

ORKK AD 2.20 LOCAL TRAFFIC REGULATIONS

ORKK 2.20.1 Marshaller assistance may be requested and further information can be obtained from the TWR or SMC. When a local regulation is of importance for the safe operation of aircraft on the apron, the information shall be given to each aircraft by the TWR or SMC or broadcast on the ATIS.

ORKK 2.20.2 Local Traffic Regulations may be requested, in writing, from the Iraq Civil Aviation Authority at the address detailed in GEN 0.1.

ORKK 2.20.3 **Removal of disabled aircraft from RWY.** When an aircraft is disabled on a RWY, it is the duty of owner or user of such aircraft to have it removed as soon as possible. If a disabled aircraft is not removed from the RWY, by the owner or user, as quickly as possible, the aircraft will be removed by the aerodrome authority at the owner's or user's expense.

ORKK AD 2.21 NOISE ABATEMENT PROCEDURES

ORKK 2.21.1 Departures

Do not over fly the AMC ramp. South ramp, North ramp, FARP, RAPCON, TACAN, or tent city below 1000 ft AGL.

Take-off to 1000 ft AGL Take-off power and take-off flaps climb at V2 +10kt.

1000-3000 ft AGL Climb at V2+10kt.

At 3000 ft AGL Normal speed and flap retraction schedules to enroute climb.

Note: *Pilots unable to comply with above procedure shall inform ATC.*

ORKK 2.21.2 Arrivals

Do not over fly the AMC ramp, Hawg (A-10) ramp, Apache ramp, fuel bladder, RAPCON, TACAN, or tent city below 1000 ft AGL.

Execute final approach at the highest altitude possible (MAX 3000FT) observing ATC instructions, maintain this altitude as long as possible, at least until intercepting ILS glide slope.

Reverse thrust other than idle shall not be used between 2330-0600 LMT except for safety reasons.

ORKK AD 2.22 FLIGHT PROCEDURES

ORKK 2.22.1.General

ORKK 2.22.1.1 Civil aircraft must notify ATC if unable to operate VFR when below 12000FT using the phrase “UNABLE VFR”. The use of VFR does not negate the requirement for aircraft to carry IFR fuel reserves.

ORKK 2.22.1.2 In airspace where VFR operations are approved, flights should be carried out in accordance with VFR as specified in ENR 1.2 and ICAO Annexes 2 and 11. Compliance with these procedures does not relieve pilots of their responsibility to see and avoid other aircraft, or to maintain safe terrain/obstacle clearance at all times when operating VFR.

ORKK 2.22.2 Procedures within Kirkuk TMA

The inbound, transit and out bound routes on the charts may be varied at the direction of ATS. If necessary, in case of congestion, inbound aircraft may also be instructed to hold at one of the designated airways, reporting points.

ORKK 2.22.3 Radar procedures within Kirkuk TMA

ORKK 2.22.3.1 **Radar vectoring and sequencing.** Normally, aircraft will be vectored and sequenced from SOGUM and KATOT reporting points to the appropriate final approach track (RNAV(GPS), TACAN), so as to ensure an expeditious flow of traffic. Radar vectors and flight levels/altitudes will be provided for spacing and separating the aircraft so that correct LDG intervals are maintained, taking into account aircraft characteristics. Radar vectoring charts are not published since the instrument approach procedures exists at all times until the point where the pilot will resume navigation on final approach or in the circuit.

ORKK 2.22.3.2 **Primary radar approaches.** Primary radar approaches will be carried out for RWYs 13 and 31 as step down commencing descent from 10 NM at an altitude of 900m. Primary radar final approaches will be terminated when aircraft established ILS or when aircraft established visual contact. Missed approach procedure to be followed in the absence of other ATS instructions are as detailed on the Instrument Approach Charts.

ORKK AD 2.23 ADDITIONAL INFORMATION

ORKK 2.23.1 All aircraft arriving and departing ORKK shall operate VFR unless IMC exists. Practice instrument approaches and departures not available.

ORKK AD 2.24 CHARTS RELATED TO AN AERODROME

ICAO Charts for Kirkuk Charts are under development for Kirkuk.		
1	Aerodrome Chart – ICAO	Not produced
2	Aircraft Parking/Docking Chart – ICAO	Not produced
3	Aerodrome Ground Movement Chart – ICAO	Not produced
4	Precision Approach Terrain Chart – ICAO	Not produced
5	Aerodrome Obstacle Chart – ICAO Type A	Not produced
6	Area Chart – ICAO (arrival and transit routes)	Not produced
7	Standard Departure Chart – Instrument – ICAO	Not produced
8	Area Chart – ICAO (arrival and transit routes)	Not produced
9	Standard Arrival Chart – Instrument - ICAO	Not produced
10	Instrument Approach Chart – ICAO	Not produced

11	Visual Approach Chart	Not produced
12	Bird concentration in the vicinity of the aerodrome	Not produced

ORBM AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORBM – Mosul Airport

ORBM AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N36°18.35' E43°08.84'” The geographic center of the airfield
2	Direction and distance from city	Bearing 142° at 2NM
3	Elevation and Reference Temperature	709FT (216.1 M) and 43.1°C
4	Geoid undulation	Not determined
5	Magnetic variation/Annual change	4°E as at Sep 2003, annual change not determined
6	Aerodrome Administration Address Telephone Telefax Telex AFS Address	Iraq Civil Aviation Authority Baghdad International Airport Baghdad Airfield Management
7	Types of traffic permitted	VFR/Limited IFR capability
8	Transition altitude and level	TA 13 000 FT AMSL, TL FL150
9	Remarks	All administrative matters are to be referred to the airport director. LDG, parking and fuel charges will be IAW published rates at GEN 4.1 and GEN 4.2. Charges MUST be paid in full in cash (\$US) prior to departure.

ORBM AD 2.3 OPERATIONAL HOURS

1	Aerodrome Administration	TBD
2	Customs and Immigration	HJ (H24 on request to ICAA)
3	Health and Sanitation	HJ (H24 on request to ICAA)
4	AIS Briefing Office	TBD
5	ATS Reporting Office	TBD
6	Met Office	DNVT 302 581 7426
7	Air Traffic Services	H24
8	Fuelling	TBD
9	Handling	HJ (H24 on request to ICAA)
10	Security	H24
11	De-icing	Not available
12	Remarks	Military or civil aircraft do not need Prior Permission Required (PPRs) to operate at ORBM. <u>Contact information :</u> MOSUL (ORBM) Email: orbmppr@yahoo.com DSN # for Airfield Manager 318-240-006

		No instrument approaches or departures for civil aircraft. Limited facilities for non-military freight. Except for military, ICRC and UN sponsored flights, approval for HA flights is required from MNC-I C3 Avn.
--	--	---

ORBM AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	Military coordinated through Mosul Command Post. Capability for main deck wide-body freighter. No storage for freight or passengers Civil acft must pre-arrange with MoT and coord with ground personnel upon arrival.
2	Fuel and oil types	Limited supply of JP8. Nil oil
3	Fueling facilities and capacity	Only emergency fuel available to fixed wing aircraft larger than C-23.
4	De-icing facilities	Nil
5	Hanger space for visiting aircraft	Nil
6	Repair facilities for visiting aircraft	Nil
7	Remarks	Limited capacity for passenger operations. Handling services during daylight hours only or by arrangement with MoT and ICAA. No catering, potable water or toilet conditioning available. Aircraft operators should expect to provide towing arm.

ORBM AD 2.5 PASSENGER FACILITIES

1	Hotels at/near aerodrome	Nil. Limited in the city
2	Restaurants	Nil
3	Transportation	Nil
4	Medical facilities	Nil
5	Bank and Post Office	Nil
6	Tourist Office	Nil
7	Remarks	Nil

ORBM AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	TBD
2	Rescue Equipment	TBC
3	Capability for removal of disabled aircraft	Limited assistance using military assets
4	Remarks	Nil

ORBM AD 2.7 SEASONAL AVAILABILITY

1	Type(s) of clearing equipment	Nil
2	Clearance priorities	Nil
3	Remarks	Nil

**ORBM AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS
DATA**

1	Surface and strength of aprons	TBD
2	Width, surface and strength of TWYs	TBD
3	Location and elevation of altimeter checkpoints	TBD
4	VOR and INS checkpoints	Not available
5	Remarks	Parallel taxiway closed for fixed wing aircraft operations. Transient helicopter parking is on the north ramp near the RWY. Hover OPS not permitted on the north ramp, ground taxi only. Exercise caution for fixed wing aircraft. FOD hazard, no ground taxi via TWY Alpha between TWY Delta and TWY Echo. Acft must coordinate parking with tower/Command post/airfield management Aerobridges not AVBL. <i>Note: All aircraft are to be directed by a marshaller to parking.</i>

**ORBM AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND
MARKINGS**

1	Use of aircraft stand ID signs, TWY guide lines and visual docking/parking guidance system at aircraft stands	See ORBM AD 2-24 charts
2	RWY and TWY markings and lights	Mosul's markings and lights under reconstruction. Refer to NOTAMs at https://www.notams.jcs.mil .
3	Stop bars	Stop bars where appropriate
4	Remarks	Nil

ORBM AD 2.10 AERODROME OBSTACLES

1	RWY15	ORBM Obstacle Chart not published
2	RWY33	ORBM Obstacle Chart not published
3	Remarks: The following additional obstructions have been identified:	
COMTW	Control Tower	N36°18'33.87" 43°08'56.20" 769.8FT/234.63M
BLDG	Building	N36°17'05.37" 43°09'11.99" 800.8FT/244.08M
BLUET2	Tower	N36°17'38.91" 43°08'45.65" 841.3FT/256.43M
HNGR	Hanger	N36°18'59.11" 43°08'48.59" 760.4FT/231.77M
WT4	Water Tower	N36°18'59.71" 43°08'08.23" 832.9FT/253.86M

ORBM AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

ORBM 2.11.1 METRO available on primary 131.050 MHz or alternate 124.150 MHz. Limited weather information, using the location designator of KQTU vice the ICAO airfield designator, is available from the following websites:

Open access website: <http://adds.aviationweather.noaa.gov/>
Military only websites: <https://afwin.afwa.af.mil/> or <https://28ows.shaw.af.mil/>

ORBM AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	15	33
2	BRG True and Mag	157.59T 153.59M	337.60T 333.60M
3	RWY Dimensions	8695 x 148 (2650M x 45M)	8695 x 148 (2650M x 45M)
4	PCN	Unknown	Unknown
5	THR Coordinates	36°19'00.48"N 043°08'30.39"E	36°17'41.00"N 043°09'10.88"E
6	THR Elevation	709 FT	705FT
7	Slope of RWY/SWY	Unknown	Unknown
8	SWY Dimensions	292FT	260FT
9	CWY Dimensions	Not calculated	Not calculated
10	Strip Dimensions	Not calculated	Not calculated
11	Obstacle free zone	Not calculated	Not calculated
12	Remarks	RWY widens at end to 350 FT	RWY widens at end to 350 FT

ORBM AD 2.13 DECLARED DISTANCES

1	RWY	15	33
2	TORA	8695FT	8695FT
3	TODA	8695FT	8695FT
4	ASDA	8987FT	8955FT
5	LDA	8987FT	8955FT
6	Remarks	Nil	Nil

ORBM AD 2.14 APPROACH AND RUNWAY LIGHTING

ORBM 2.14.1 Advice on Mosul's approach and RWY lighting is available via NOTAM.

1	RWY	15	33
2	Type, length and intensity of approach lighting		
3	Threshold lights, colors and wing bars	Threshold lights installed 10FT prior to RWY surface.	Threshold lights installed 10FT prior to RWY surface.
4	Type of visual approach slope indicator system		
5	Length of RWY touchdown zone indicator lights		
6	Length spacing color and intensity of RWY centerline lights		
7	Length spacing color and intensity of RWY edge lights	Last 2000FT of RWY edge lighting is amber.	Last 2000FT of RWY edge lighting is amber.
8	Color of RWY end lights and wingbars		
9	Length and color of		

	stopway lights		
10	Remarks	Airfield has solar RWY edge, threshold, RWY end and TWY lights, unable to change intensity. Airfield lighting not available sunrise to sunset. Daytime IFR operations not permitted due to lighting deficiencies.	

ORBM AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Aerodrome Beacon	Nil
2	Location and lighting of anemometer and LDG direction indicator	Not fitted
3	TWY edge and centerline lighting	Mosul's lighting under reconstruction. Check NOTAM for latest information. https://www.notams.jcs.mil
4	Secondary power supply including switch-over time	TBD
5	Remarks	Nil

ORBM AD 2.16 HELICOPTER LANDING AREA

1	Coordinates of touchdown and lift-off point (TLOF) threshold of final approach and take-off (FATO)	To be determined
2	TLOF and/or FATO area elevation	To be determined
3	TLOF and FATO area dimensions, surface, strength, marking	To be determined
4	True and MAG BRG of FATO	To be determined
5	Declared distance available	To be determined
6	Approach and FATO lighting	To be determined
7	Remarks	Nil

ORBM AD 2.17 AIR TRAFFIC SERVICES AIRSPACE

1	Airspace designation and lateral limits	Detailed in ENR 1.4
2	Vertical limits	
3	Airspace classification	
4	Callsign and Languages	Mosul ...(<i>Tower or Approach</i>)
5	Transition altitude	13 000 FT
6	Remarks	ATS provided by military controllers operating IAW US Army Standards.

ORBM AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
APP	Mosul Approach	119.45 MHz 259.125 MHz	H24	
TWR	Mosul Tower	132.825 MHz 250.025 MHz	H24	Primary Secondary
GROUND	Mosul Ground	120.2 MHz 262.125 MHz	H24	
ATIS	N/A	127.25 MHz	H24	Nil

ORBM AD 2.19 RADIO NAVIGATION AND LANDING AIDS

Type of Aid	Ident	FREQ	Hours of operation	Position of antenna	Elevation of DME	Remarks
PAR 3°	N/A	As directed by APP	Not AVBL		N/A	
Remarks	No radio navigation and LDG aids available.					

ORBM AD 2.20 LOCAL TRAFFIC REGULATIONS

ORBM 2.20.1 Instrument approach/departure procedures are not authorized when Aerostat(s) are operating. Aerostat located 1.12NM northwest of RWY 33 approach end threshold.

ORBM 2.20.2 Caution uncontrolled vehicles/personnel operating in close proximity to the RWY.

ORBM 2.20.3 Marshaller assistance may be requested and further information can be obtained from the TWR or SMC. When a local regulation is of importance for the safe operation of aircraft on the apron, the information shall be given to each aircraft by the TWR or SMC or broadcast on the ATIS.

ORBM 2.20.4 Local Traffic Regulations may be requested, in writing, from ICAA at the address detailed in GEN 0.1.

ORBM 2.20.5 **Removal of disabled aircraft from RWY.** When an aircraft is disabled on a RWY, it is the duty of owner or user of such aircraft to have it removed as soon as possible. If a disabled aircraft is not removed from the RWY, by the owner or user, as quickly as possible, the aircraft will be removed by the aerodrome authority at the owner's or user's expense..

ORBM AD 2.21 NOISE ABATEMENT PROCEDURES**ORBM 2.21.1 Departures**

Take-off to 1000 ft AGL Take-off power and take-off flaps climb at V2 +10kt.

1000-3000 ft AGL Climb at V2+10kt.

At 3000 ft AGL Normal speed and flap retraction schedules to enroute climb.

Note: *Pilots unable to comply with above procedure shall inform ATC.*

ORBM 2.21.2 Arrivals

Execute final approach at the highest altitude possible (MAX 3000FT) observing ATC instructions, maintain this altitude as long as possible, at least until intercepting ILS glide slope.

Reverse thrust other than idle shall not be used between 2330-0600 LMT except for safety reasons.

ORBM AD 2.22 FLIGHT PROCEDURES

ORBM 2.22.1.General

ORBM 2.22.1.1 Civil aircraft must notify ATC if unable to operate VFR when below 12,000FT using the phrase “UNABLE VFR”. The use of VFR does not negate the requirement for aircraft to carry IFR fuel reserves.

ORBM 2.22.1.2 In airspace where VFR operations are approved, flights should be carried out in accordance with VFR as specified in ENR 1.2 and ICAO Annexes 2 and 11 (particularly regarding visibility and clearance from cloud). Compliance with these procedures does not relieve pilots of their responsibility to see and avoid other aircraft, or to maintain safe terrain/obstacle clearance at all times when operating VFR.

ORBM 2.22.2 Procedures within Mosul TMA

ORBM 2.22.2.1 The inbound, transit and out bound routes on the charts may be varied at the direction of ATS. If necessary, in case of congestion, inbound aircraft may also be instructed to hold at one of the designated airways reporting points.

ORBM AD 2.23 ADDITIONAL INFORMATION

ORBM 2.23.1 All aircraft arriving and departing ORBM shall operate VFR unless IMC exists. Practice instrument approaches and departures not available.

ORBM AD 2.24 CHARTS RELATED TO AN AERODROME

ICAO Charts for Mosul International Airport		
Charts are under development for Mosul. See http://164.214.2.62/products/digitalaero/index.html for the latest charts.		
1	Aerodrome Chart - ICAO	Not produced
2	Aircraft Parking/Docking Chart – ICAO	Not produced
3	Aerodrome Ground Movement Chart – ICAO	Not produced
4	Precision Approach Terrain Chart – ICAO	Not produced
5	Aerodrome Obstacle Chart – ICAO Type A	Not produced
6	Area Chart – ICAO (arrival and transit routes)	Not produced
7	Standard Departure Chart – Instrument – ICAO	Not produced
8	Area Chart – ICAO (arrival and transit routes)	Not produced
9	Standard Arrival Chart – Instrument - ICAO	Not produced

10	Instrument Approach Chart – ICAO	Not produced
11	Visual Approach Chart	Not produced
12	Bird concentration in the vicinity of the aerodrome	Not produced

ORQT AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORQT – Qasr Tall Muhl Airport

ORQT AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N33°18'24.00" E044°14'30.00" The geographic center of the airfield
2	Elevation and Reference Temperature	114FT (34.7M) and 43.1°C

ORQW AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORQW – Qayyarah West Airport

ORQW AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N35°46.03' E43°07.51' The geographic center of the airfield
2	Elevation and Reference Temperature	749FT (228.3M) and 43.1°C

ORQW AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

ORQW 2.11.1 Limited weather information, using the location designator of KQCO vice the ICAO airfield designator, is available from the following websites:

Open access website: <http://adds.aviationweather.noaa.gov/>
Military only websites: <https://afwin.afwa.af.mil/> or <https://28ows.shaw.af.mil/>

ORQW AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	15	33
2	BRG True and Mag	Unknown	Unknown
3	RWY Dimensions	11486FT x 197FT (3500Mx60M)	11486FT x 197FT (3500Mx60M)
4	PCN	36 R/B/W/T	36 R/B/W/T
5	THR Coordinates	Unknown	Unknown
6	THR Elevation	Unknown	Unknown
7	Slope of RWY/SWY	Unknown	Unknown
8	SWY Dimensions	Not calculated	Not calculated
9	CWY Dimensions	Not calculated	Not calculated
10	Strip Dimensions	Not calculated	Not calculated
11	Obstacle free zone	Not calculated	Not calculated

ORQW AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
TWR	Qayyarah Tower	122.200 MHz 236.725 MHz	H24	Primary Secondary

ORSH AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORSH – Al Sahra (Spiecher AAF)

ORSH AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

The facilities and procedures listed below do not necessarily comply with, or adhere to, the requirements of ICAO Annex 14.

1	Aerodrome Reference Point coordinates and site	N34° 40.39' E043° 32.58" 38S LD 66514 37772 Located at the center of the runway
2	Direction and distance from city	300 BRG 8NM
3	Elevation and Reference Temperature	451 FT (137.5M), 44°C
4	Geoid undulation	Not determined
5	Magnetic variation/Annual change	3°E as of Jan 2004, Annual change E000°00'58.36"
6	Aerodrome Administration Address Telephone Telefax Telex AFS Address	Al Sahra Airfield Tikrit-IRAQ Airfield Manager/Standards/Safety; DNVT: 302-536-6520 ATS COMMANDER: DNVT: 302-536-6507
7	Types of traffic permitted	VFR and SVFR
8	Transition altitude and level	13 000FT

ORSH AD 2.3 OPERATIONAL HOURS

1	Aerodrome Administration	H24
2	Customs and Immigration	None
3	Health and Sanitization	None
4	AIS Briefing Office	TBD
5	ATS Reporting Office	TBD
6	Met Office	TBD
7	Air Traffic Services	H24
8	Fuelling	Limited to Army Aircraft
9	Handling	HJ
10	Security	H24
11	De-icing	Not available
12	Remarks	Aerodrome Prior Permission Required fixed wing aircraft that are not in the Global Decision Support System (GDSS). Aircraft not issued a PPR may be turned away or met by Security Forces. RAMCC no longer issue slot times for military aircraft – PPRs for military fixed wing aircraft also serve as slot times. PPRS are requested from the following email addresses: Alsahra.Operations@Us.Army.Mil or Alsahra.Towersafely@42id.Army.Smil.Mil.

		Al Sahra Operations available on DSN 302-536-3170
--	--	---

ORSH AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	USAF ADAG
2	Fuel and oil types	Limited to Army Aircraft
3	Fueling facilities and capacity	Limited to Army Aircraft
4	De-icing facilities	Nil
5	Hanger space for visiting aircraft	Nil
6	Repair facilities for visiting aircraft	Nil

ORSH AD 2.5 PASSENGER FACILITIES

1	Hotels at/near aerodrome	Nil.
2	Restaurants	Nil.
3	Transportation	Nil
4	Medical facilities	Emergency cover for military only
5	Bank and Post Office	Nil.
6	Tourist Office	Nil
7	Remarks	Nil

ORSH AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	Unknown
2	Rescue Equipment	Commercial type fire trucks and equipment
3	Capability for removal of disabled aircraft	Limited assistance using military assets
4	Remarks	Nil

ORSH AD 2.7 SEASONAL AVAILABILITY

1	Type(s) of clearing equipment	Nil
2	Clearance priorities	Nil
3	Remarks	Nil

ORSH AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS DATA

1	Surface and strength of aprons	Unknown/Untested
2	Width, surface and strength of taxiways	Width: 23M Surface: Concrete Strength: PCN - 100/R/B/W/T
3	Location and elevation of altimeter checkpoints	None
4	VOR and INS checkpoints	Not available
5	Remarks	

ORSH AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	Use of aircraft stand ID signs, TWY guide lines and visual docking/parking guidance system at aircraft stands	Nil
2	Runway and Taxiway markings and lights	RWY 32R / 14L no runway lights RWY 32L/14R solar runway lights and green/red runway end lights. Various Helipads have amber solar lights. FARP area and some taxiways have blue solar lights. Operational FARP points lighted individually with amber solar light.
3	Stop bars	Nil
4	Remarks	Nil

ORSH AD 2.10 AERODROME OBSTACLES

1	RWY14	ORSH Obstacle Chart not available
2	RWY32	ORSH Obstacle Chart not available
3	Remarks	Nil

ORSH AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

ORSH 2.11.1 METRO Frequency 33.60ct. Limited weather information, using the location designator of KQSL vice the ICAO airfield designator, is available from the following websites:

Open access website: <http://adds.aviationweather.noaa.gov/>
Military only websites: <https://afwin.afwa.af.mil/> or <https://28ows.shaw.af.mil/>

ORSH AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

RUNWAY 32R/14L Closed to fixed wing traffic

1	RWY	32L	14R
2	BRG True and Mag	318°T, 315°M	138T, 135°M
3	RWY Dimensions	10237FT x 140FT (3120M x 43M)	10237FT x 140FT (3120M x 43M)
4	PCN	105	105
5	THR Coordinates	Unknown	N34°39'58.36" E043° 32'21.41"
6	THR Elevation	451FT	451FT
7	Slope of	Unknown	Unknown

	RWY/SWY		
8	SWY Dimensions	Unknown	Unknown
9	CWY Dimensions	Not calculated	Not calculated
10	Strip Dimensions	Not calculated	Not calculated
11	Obstacle free zone	Not calculated	Not calculated
12	Remarks	Nil	Nil

ORSH AD 2.13 DECLARED DISTANCES

1	RWY	32L	14R
2	TORA	10237FT (3120M)	10237FT (3120M)
3	TODA	10237FT (3120M)	10237FT (3120M)
4	ASDA	TBD	TBD
5	LDA	TBD	TBD
6	Remarks	Nil	Nil

ORSH AD 2.14 APPROACH AND RUNWAY LIGHTING

See ORSH AD 2.9

ORSH AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Aerodrome Beacon	Not available
2	Location and lighting of anemometer and LDG direction indicator	Not available
3	Taxiway edge and centerline lighting	Refer ORSH AD 2.9(2)
4	Secondary power supply including switch-over time	Nil
5	Remarks	No obstruction lights No serviceable runway holding point lights

ORSH AD 2.16 HELICOPTER LANDING AREA

1	Coordinates of touchdown and lift-off point (TLOF) threshold of final approach and take-off (FATO)	To be determined
2	TLOF and/or FATO area elevation	To be determined
3	TLOF and FATO area dimensions, surface,	To be determined

	strength, marking	
4	True and MAG BRG of FATO	To be determined
5	Declared distance available	To be determined
6	Approach and FATO lighting	To be determined
7	Remarks	Nil

ORSH AD 2.17 AIR TRAFFIC SERVICES AIRSPACE

1	Airspace designation and lateral limits	See Current ACO
2	Vertical limits	SFC to 3000' AMSL
3	Airspace classification	Class D
4	Callsign and Languages	Spiecher ...(<i>Tower</i>)
5	Transition altitude	13 000 FT
6	Remarks	ATS provided by military controllers operating IAW US Army Standards.

ORSH AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
TWR	Spiecher Tower	141.500 MHz 335.300 MHz	H24	Primary Secondary
GCA	Spiecher GCA	120.1 MHz 311.6 MHz	1500Z to 0400Z Avbl other times with minimum 30mins prior notice	Primary Secondary

ORSH AD 2.19 RADIO NAVIGATION AND LANDING AIDS

Type of Aid	Ident	FREQ	Hours of operation	Position of antenna	Elevation of DME	Remarks
NDB	TKT	1669kHz	H24			

ORSH AD 2.20 LOCAL TRAFFIC REGULATIONS

ORSH 2.20.1 **Inbound/Outbound Instructions:** Flight altitudes:

ORSH 2.20.1.1 By day, 200FT AGL or below.

ORSH 2.20.1.2 By night, Inbound 400FT AGL, Outbound 200' AGL

ORSH 2.20.1.3 Traffic Pattern 200FT AGL for all rotary wing aircraft.

ORSH 2.20.2 All aircraft will contact Spiecher Tower prior to entering the Al Sahra Class D airspace.

ORSH 2.20.3 If conducting operations solely within the Class D, contact tower to request transit to or entry.

ORSH 2.20.4 Rotary wing aircraft. All RW aircraft inbound from or outbound to the West will use RWY 14R/32L. All RW aircraft inbound from or outbound to the East will use RWY 14L/32R. RW pattern altitude refer para 2.20.1.3.

ORSH 2.20.5 Fixed wing aircraft. All FW aircraft will use RWY 14R/32L. RWY 14L/32R is not available to FW aircraft.

ORSH AD 2.21 NOISE ABATEMENT PROCEDURES

None

ORSH AD 2.22 FLIGHT PROCEDURES

ORSH 2.22.1 Traffic Pattern. West traffic uses RWY 32L/14R and East traffic uses RWY 32R/14L. RW pattern altitude 200FT AGL. If conducting operations within the Class D, contact Tower to request entry.

ORSH AD 2.23 ADDITIONAL INFORMATION

Nil

ORSU AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORSU – Sulaymaniyah International Airport

ORSU AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

The facilities and procedures listed in ORSU's entry do not necessarily comply with, or adhere to, the requirements of ICAO Annex 3, 9, 11, 14, 15, 17 and 18.

1	Aerodrome Reference Point coordinates and site	N35°33'38.88" E045°18'52.98"
2	Direction and distance from city	272°MAG, 6.48NM
3	Elevation and Reference Temperature	2470FT AMSL 43.3° Celsius
4	Aerodrome Administration Address Telephone Telefax Telex AFS Address	Kurdistan Regional Government (KRG) Sulaymaniyah International Airport Ph: ++(964) (0) 7701530273 or ++(964) (0) 7701505186. Nil Telefax. E-mail: sulairport@yahoo.com Website: www.sulairport.net
5	Magnetic variation	4°E
6	Types of traffic permitted	VFR
7	Transition altitude and level	TA 13,000 FT AMSL, TL FL150
8	Remarks	All data in the ORSU entry is supplied by Airport Manager. All administrative matters are to be referred to the Airport Administrator. LDG and parking charges will be IAW published rates at GEN 4.1 and GEN 4.2.

ORSU AD 2.3 OPERATIONAL HOURS

1	Aerodrome Administration	H24
2	Customs and Immigration	H24
3	Health and Sanitation	TBD
4	AIS Briefing Office	TBD
5	ATS Reporting Office	TBD
6	Met Office	TBD
7	Air Traffic Services	H24 - Nil ATC services. Advisory, Traffic Information and Alerting Services only.
8	Fuelling	H24
9	Handling	H24
10	Security	TBD
11	De-icing	Not available
12	Remarks	Civil aircraft, not requiring compliance with ICAO Annexes 14, 15 or 17, may be authorized to operate 24 hours a day.

	<p>Prior Permission Required (PPRs): Sulaymaniyah International Airport is a PPR only airfield. PPRs are required for all aircraft operating at this airfield. Operators must contact the Airfield Administration for a PPR before requesting a slot time into or out of Iraq from RAMCC. PPRs are valid +/- 30 MIN from ETA.</p> <p><u>Contact information :</u> Kurdistan Regional Government (KRG) Sulaymaniyah International Airport Phone: ++(964) (0) 7701530273 or ++(964) (0) 7701505186 E-mail: sulairport@yahoo.com Permission to operate in the Baghdad FIR is coordinated through Regional Air Movements Coordination Center (RAMCC). Refer GEN 1.2 for current procedures, requirements and contact information.</p>
--	--

ORSU AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	TBD
2	Fuel and oil types	JET A1 avbl. Oil – TBD
3	Fueling facilities and capacity	H24
4	De-icing facilities	TBD
5	Hanger space for visiting aircraft	TBD
6	Repair facilities for visiting aircraft	TBD
7	Remarks	Nil

ORSU AD 2.5 PASSENGER FACILITIES

1	Hotels at/near aerodrome	In Sulaymaniyah City
2	Restaurants	Avbl at terminal
3	Transportation	Buses and taxis
4	Medical facilities	Medical Center available
5	Bank and Post Office	TBD
6	Tourist Office	TBD
7	Remarks	Nil

ORSU AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	RFF Cat 6
2	Rescue Equipment	
3	Capability for removal of disabled aircraft	TBD
4	Remarks	Two Ziegler 8000L CAP Two Water Tankers 10000L CAP Two Ambulances

ORSU AD 2.7 SEASONAL AVAILABILITY

1	Type(s) of clearing equipment	Nil
2	Clearance priorities	Nil
3	Remarks	Nil

ORSU AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS DATA

1	Surface and strength of aprons	Surface: Concrete PCN: 85/R/C/Y/T Dimensions: 304M x 165M
2	Width, surface and strength of TWYs	(Main Taxiway – parallel to RWY) Surface: Concrete PCN: 85/R/C/Y/T Dimensions: 3500M x 30M plus 3M shoulders on each side (Rapid Exit TWYs) Surface: Concrete PCN: 85/R/C/Y/T Dimensions: 27M wide
3	Location and elevation of altimeter checkpoints	Not available
4	VOR and INS checkpoints	Not available
5	INS Checkpoints	North Apron: N35°33'29.69624" E045°19'33.67531" ELEV 747.7819M (2452.7 FT) Center Apron: N35°33'31.79018" E045°19'30.94025" ELEV 747.9652M (2453.3 FT) South Apron: N35°33'33.88570" E045°19'28.20590" ELEV 748.1366M (2453.9 FT)
6	Remarks	Nil

ORSU AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	Use of aircraft stand ID signs, TWY guide lines and visual docking/parking guidance system at aircraft stands	Day and Night: TWY sign boards Day: Finger sign boards
2	RWY and TWY markings and lights	RWY markings: Threshold, centerline, touchdown, edge. RWY lighting: threshold and edges TWY markings: Centerline TWY lighting: edge
3	Stop bars	TBD
4	Remarks	NIL

ORSU AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	13	31
2	BRG True and Mag	133.35°T, 130°M	313.35°T, 310°M
3	RWY Dimensions	11484 x 148FT (3500M x 45M)	11484 x 148FT (3500M x 45M)
4	PCN	85/R/C/Y/T	85/R/C/Y/T
5	THR Coordinates	N35°34'17.73145" E045°18'01.89884"	N35°33'00.43258" E045°19'43.68297"
6	THR Elevation	2492FT (759.7578M)	2440FT (743.7395M)
7	Slope of RWY	0.6%	0.6%

ORSUAD 2.13 DECLARED DISTANCES

1	RWY	13	31
2	TORA	3500M	3500M
3	TODA	3800M	3800M
4	ASDA	3500M	3500M
5	LDA	3500M	3500M

ORSU AD 2.14 APPROACH AND RUNWAY LIGHTING

1	RWY	13	31
2	Type, length and intensity of approach lighting	CAT 1 Barrette Length 900M Variable intensity	CAT 1 Barrette Length 900M Variable intensity
3	Threshold lights, colors and wing bars	Green Wing Bars	Green Wing Bars
4	Type of visual approach slope indicator system	PAPI 4 units on each side 3° approach slope 400M from THR	PAPI 4 units on each side 3° approach slope 400M from THR
5	Length of RWY touchdown zone	TBD	TBD

	indicator lights		
6	Length spacing color and intensity of RWY centerline lights	TBD	TBD
7	Length spacing color and intensity of RWY edge lights	60M White	60M White
8	Color of RWY end lights and wing bars	Red Wing Bar REIL avbl	Red Wing Bar REIL avbl
9	Length and color of stopway lights	TBD	TBD
10	Remarks	Nil	Nil

ORSU AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Aerodrome Beacon	Avbl
2	Location and lighting of anemometer and LDG direction indicator	WDI
3	TWY edge and centerline lighting	Blue edge lights only
4	Secondary power supply including switch-over time	Avbl with 16 second switch-over time
5	Remarks	Nil

ORSU AD 2.17 AIR TRAFFIC SERVICES AIRSPACE

1	Airspace designation and lateral limits	Uncontrolled airport
2	Vertical limits	NIL
3	Airspace classification	G
4	Callsign and Languages	Sulaymaniyah Advisory/English
5	Transition altitude	13,000 FT
6	Remarks	See ORSU 2.18.

ORSU AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
ACC	Kirkuk Center	125.30 MHz 237.325 MHz	H24	Primary Secondary
Local Airport Advisory	Sulaymaniyah Advisory	118.3 MHz	H24	Uncontrolled, CTAF procedures apply. Advisory service only

REMARKS	Kirkuk Center will provide an enroute service to the base of Class E airspace (4,000FT AMSL).
---------	---

ORSU AD 2.19 RADIO NAVIGATION AND LANDING AIDS

Type of Aid	Ident	FREQ	OP Hours	Position of antenna	Elevation
D/VOR	SUL	117.0 MHz	H24	N35°34'46.48824" E045°17' 24.24197"	767.2494M
DME/P		111.7Mhz CH54X	H24	N 35 33 02. 92436 E 045 19 30.46155	743.8151M
ILS	RNJ		H24		
GP		333.5 MHz		N 35 33 03.23378 E 045 19 31.26357	743.8149M
LLZ		111.7 MHz		N 35 34 26.47670 E 045 17 50.37166	763.6537M
Remarks	ILS and DME are collocated.				

ORTF AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORTF – Tall Afar Airfield

ORTF AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

The facilities and procedures listed below do not necessarily comply with, or adhere to, the requirements of ICAO Annex 14.

1	Aerodrome Reference Point coordinates and site	N36°16.99' E42°24.18' Located at the center of the runway
2	Direction and distance from city	015 deg at 6NM
3	Elevation and Reference Temperature	996FT
4	Geoid undulation	Not determined
5	Magnetic variation/Annual change	3°E as of Jan 2004, Annual change E000°00'58.36''
6	Aerodrome Administration Address Telephone Telefax Telex AFS Address	US ARMY All administrative matters to Air Operations. DNVT 318-250-8087 (Airport Manager), DNVT 318-250-8087 (Airport Safety) Thuraya 88-2166-722-5434
7	Types of traffic permitted	VFR
8	Transition altitude and level	TA 13,000 FT AMSL, TL FL150

ORTF AD 2.3 OPERATIONAL HOURS

1	Aerodrome Administration	H24
2	Customs and Immigration	NA
3	Health and Sanitization	NA
4	AIS Briefing Office	TBD
5	ATS Reporting Office	H24
6	Met Office	H24
7	Air Traffic Services	H24
8	Fuelling	H24 (not avbl to fixed wing aircraft)
9	Handling	H24 limited MHE
10	Security	H24
11	De-icing	Not available
12	Remarks	PPR required 24HRS in advance for all transient aircraft. Contact Airport Manager @ 318-250-8087 Permission to operate in the Baghdad FIR is coordinated through Regional Air Movements Coordination Center (RAMCC). Refer GEN 1.2 for current procedures, requirements and contact information. Civil aircraft in VMC by day only. Fuel N/A to all Fixed Wing aircraft except C-23 Sherpa.

--	--	--

ORTF AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	Limited MHE on site.
2	Fuel and oil types	JP8 Limited Mil oil
3	Fueling facilities and capacity	Four point FARP for Rotary Wing aircraft Fuel, maintenance and AGE not available for fixed wing aircraft. Fixed wing aircraft must carry round-trip fuel.
4	De-icing facilities	Nil
5	Hanger space for visiting aircraft	Nil
6	Repair facilities for visiting aircraft	Nil
7	Remarks	Handling services only for Rotary Wing .

ORTF AD 2.5 PASSENGER FACILITIES

1	Hotels at/near aerodrome	Nil.
2	Restaurants	Nil.
3	Transportation	Nil
4	Medical facilities	Emergency cover for military only
5	Bank and Post Office	Limited
6	Tourist Office	Nil
7	Remarks	Nil

ORTF AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	USAF Equivalent 2, FAA equivalent C/D
2	Rescue Equipment	Listed at Airfield Safety
3	Capability for removal of disabled aircraft	Limited assistance using military and contractor assets
4	Remarks	Contractor services. In extreme circumstances or dictated by military necessity, disabled aircraft may be pushed to clear maneuvering areas.

ORTF AD 2.7 SEASONAL AVAILABILITY

1	Type(s) of clearing equipment	Nil
2	Clearance priorities	Nil
3	Remarks	Nil

ORTF AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS DATA

1	Surface and strength of aprons	N/A
2	Width, surface and strength of taxiways	Width: 100 FT Surface: Asphalt

		Strength: G 80F/A/W/T, E 119F/A/W/T, F 169F/A/W/T
3	Location and elevation of altimeter checkpoints	N/A
4	VOR and INS checkpoints	N/A
5	Remarks	7Taxiways, 3 Useable, 0 Aprons H TWY closed to all fixed and rotary wing aircraft. E, F and G TWYs used for cargo and passenger operations as directed by ATC. Drainage ditched located along edges of E and F TWYs. 6FT drop exceeding recommended slope.

ORTF AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	TWY guide lines	Incomplete at this time
2	Runway and Taxiway markings and lights	Paint Markings Solar Lighting mark RWY edge and taxiways. No fixed distance markings on RWY 13/31 No RWY Holding point line marked on F TWY No centerline markings on E, F and G TWYs
3	Stop bars	Stop bars to be installed
4	Remarks	Wind Indicator, unlit, located 246 FT east of RWY 31 centerline

ORTF AD 2.10 AERODROME OBSTACLES

1	RWY13	ORTF Obstacle Chart not available
2	RWY31	ORTF Obstacle Chart not available 12FT Unlit obstruction located 295FT from the RWY centerline, SE end of RWY 31. Violates transitional surface. 4FT unlit obstruction located within 150 FT of Helipad One.
3	Remarks	

ORTF AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

ORTF 2.11.1 Limited weather information, using the location designator of KQTI vice the ICAO airfield designator, is available from the following websites:

Open access website: <http://adds.aviationweather.noaa.gov/>
Military only websites: <https://afwin.afwa.af.mil/> or <https://28ows.shaw.af.mil/>

ORTF AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	13	31
2	BRG	130	310
3	RWY Dimensions	9842 FT X 147 FT	9842 FT X 147 FT
4	PCN	105	105
5	THR Coordinates	UNK	UNK
6	THR Elevation	996 FT	996 FT
7	Slope of RWY/SWY	UNK	UNK
8	SWY Dimensions	233FT	233FT
9	CWY Dimensions	Not calculated	Not calculated
10	Strip Dimensions	Not calculated	Not calculated
11	Obstacle free zone	Standard ICAO	Standard ICAO
12	Remarks	Nil	Nil

ORTF AD 2.13 DECLARED DISTANCES

1	RWY	13	31
2	TORA	9842 FT	9842 FT
3	TODA	9842 FT	9842 FT
4	ASDA	9842 FT	9842 FT
5	LDA	9842 FT	9842 FT
6	Remarks	Nil	Nil

ORTF AD 2.14 APPROACH AND RUNWAY LIGHTING

ORTF 2.14.1 Further information on Tall Afar approach and runway lighting is available via NOTAM.

1	RWY	13	31
2	Type, length and intensity of approach lighting	NA	NA
3	Threshold lights, colors and wing bars	NA	NA
4	Type of visual approach slope indicator system	NA	NA
5	Length of RWY touchdown zone indicator lights	NA	NA
6	Length spacing color and intensity of RWY centerline lights	NA	NA
7	Length spacing color and intensity of RWY edge lights	NA	.NA
8	Color of RWY end lights and wingbars	NA	NA
9	Length and color of stop way lights	NA	NA
10	Remarks	Nil	Nil

ORTF AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Aerodrome Beacon	NA
2	Location and lighting of anemometer and LDG direction indicator	NA
3	Taxiway edge and centerline lighting	NA
4	Secondary power supply including switch-over time	NA
5	Remarks	Obstruction lights No serviceable runway lights No serviceable taxiway lights Signal lamps in Tower Aerodrome signs not lit

ORTF AD 2.16 HELICOPTER LANDING AREA

1	Coordinates of South Helipad (TENANT)	38S-KF-6795-1744
2	Coordinates of North Helipad (PAX TERM)	38S-KF-6755-1792
3	Coordinates of Rifles Pad (VIP PAD)	38S-KF-6750-1856
4	Coordinates of Transient parking	38S-KF-6685-1875
5	Lighting	Solar Lighting
6	NA	NA
7	Remarks	All rotary wing passenger aircraft will use pax terminal pad as directed by ATC. No engine shutdown on pax pad.

ORTF AD 2.17 AIR TRAFFIC SERVICES AIRSPACE

1	Airspace designation and lateral limits	Class D, SFC – 3,000 AGL, 5NM Radius
2	Vertical limits	
3	Airspace classification	
4	Call sign and Languages	Tall Afar...(Tower) . English
5	Transition altitude	13,000 FT
6	Remarks	Aircraft inbound LDG Tall Afar call tower on 118.70(P) or 380.050(P) prior to 5 NM to clear airspace

ORTF AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
TWR	Tall Afar Tower	118.700MHz 380.050MHz	H24	Primary
Remarks	All Tall Afar ATS provided by military controllers operating IAW US Mil AIP.			

ORTF AD 2.19 RADIO NAVIGATION AND LANDING AIDS

Type of Aid	Ident	FREQ	Hours of operation	Position of antenna	Elevation of DME	Remarks
NDB	ORTF	1735KHz	H24	Unknown		

ORTF AD 2.20 LOCAL TRAFFIC REGULATIONS

ORTF 2.20.1 For operational reasons ATC may require approach to RWY 31 for LDG and RWY 13 for departures.

ORTF 2.20.2 VFR approaches from irregular, randomised approach points are encouraged utilizing available approach/departure procedures. Aircraft operators are to avoid over flight of the city of Tall Afar. Aircraft are encouraged to make non-standard VFR departures onto random initial departures tracks utilizing available arrival/departure procedures. Aircraft MUST depart VFR.

ORTF 2.20.3 All C17 aircraft limited to MTOW 345,000 LBS. Use full length of RWY on landing and no hard braking. Use rolling reduced take-offs only, No TRT take-offs without Airfield Manager approval. For C17 and IL76 aircraft, taxi inboard engines only on E, F and G TWYs. Contact Airfield Manager on DSN 318-250-8065 for further information.

ORTF 2.20.4 **Removal of disabled aircraft from RWY.** When an aircraft is disabled on a RWY, it is the duty of owner or user of such aircraft to have it removed as soon as possible. If a disabled aircraft is not removed from the RWY, by the owner or user, as quickly as possible, the aircraft will be removed by the aerodrome authority at the owner's or user's expense.

ORTF AD 2.22 FLIGHT PROCEDURES

ORTF 2.22.1 Flight procedures for Tall Afar are under construction.

ORTF AD 2.23 ADDITIONAL INFORMATION

ORTF 2.23.1 Additional information is available at <https://www.afd.scott.af.mil>

ORTF AD 2.24 CHARTS RELATED TO AN AERODROME

ORTF 2.24.1 Approach, Aerodrome and Taxi Charts for Tall Afar are under construction.

ICAO Charts for Tall Afar Airfield		
1	Aerodrome Chart – ICAO	MIL
2	Aircraft Parking/Docking Chart – ICAO	NA
3	Aerodrome Ground Movement Chart – ICAO	NA
4	Precision Approach Terrain Chart – ICAO	NA
5	Aerodrome Obstacle Chart – ICAO Type A	NA
6	Area Chart – ICAO (arrival and transit routes)	NA
7	Standard Departure Chart – Instrument – ICAO	NA
8	Area Chart – ICAO (arrival and transit routes)	NA
9	Standard Arrival Chart – Instrument - ICAO	NA
10	Instrument Approach Chart – ICAO	NA
11	Visual Approach Chart	MIL
12	Bird concentration in the vicinity of the aerodrome	NA

ORTL AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORTL – Ali Base Airfield

ORTL AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N30°56.15' E046°05.41''' The geographic center of the airfield
2	Direction and distance from city	Bearing 230° at 10NM
3	Elevation and Reference Temperature	20FT (6.1 M) and 43.1°C
4	Geoid undulation	Not determined
5	Magnetic variation/Annual change	3°E as of Jan 2004, annual change E000°01'05.09''
6	Types of traffic permitted	IFR and VFR
7	Transition altitude and level	TA 13 000 FT AMSL, TL FL150
8	Remarks	All administrative matters are to be referred to the airport director. LDG, parking and fuel charges will be IAW published rates at GEN 4.1 and GEN 4.2. Charges MUST be paid in full in cash (\$US) prior to departure. Limited Flight Planning Facilities available.

ORTL AD 2.3 OPERATIONAL HOURS

1	Aerodrome Administration	H12
2	Customs and Immigration	Not Available
3	Health and Sanitation	Not Available
4	AIS Briefing Office	H24
5	ATS Reporting Office	H16
6	Met Office	H24 – DSN 318-445-2482
7	Air Traffic Services	H24
8	Fueling	H24
9	Handling	HJ (H24 on request to ICAA)
10	Security	H24
11	De-icing	Not available
12	Remarks	<p>Prior Permission Required (PPR) for all transient aircraft. Call Airfield authorities at DSN 318-445-2448 or 2449 to obtain a PPR number. Limited facilities for non-military freight. Except for military, ICRC and UN sponsored flights, approval for HA flights are required from CJTF-7.</p> <p>Permission to operate in the Baghdad FIR is coordinated through Regional Air Movements Coordination Center (RAMCC). Refer GEN 1.2 for current procedures, requirements and contact information.</p>

		Ali Base is PPR for all transient aircraft. Call Airfield Management at DSN 318-445-2448 or 2449 to obtain PPR number. PPR Email: 407AEG/EOSS/AMOP2@tlab.aorcentaf.af.mil
--	--	---

ORTL AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	Military coordinated through Ali Base Command Post. Capability for main deck wide-body freighter. No storage for freight or passengers. Civil acft must pre-arrange with ATOC and coord with ground personnel upon arrival.
2	Fuel and oil types	Limited supply of JP8. Nil oil
3	Fueling facilities and capacity	Limited. Plan flight without fuel from ORTL
4	De-icing facilities	Nil
5	Hanger space for visiting aircraft	Nil
6	Repair facilities for visiting aircraft	Nil
7	Remarks	<p>Prior permission required</p> <p>Strictly 48 hours PPR through Ali Base Air Operations PPRs are required for military and civil aircraft operating at these airfields. Aircraft not issued a PPR may be turned away or met by security forces. Civil operators must contact these fields and receive a PPR before requesting a slot time into or out of Iraq from RAMCC</p> <p>Email: 407AEG/EOSS/AMOP2@tlab.aorcentaf.af.mil AMOPS DSN 318-445-2448 or 2449</p> <p>Limited facilities for non-military freight. Except for military, ICRC and UN sponsored flights. All aircraft must obtain a slot time from RAMCC.</p> <p>Military coordinated through Ali Base Command Post 'Kingfish Foxtrot' on 230.3MHz. 30 minutes prior to LDG. Capability for main deck wide-body freighter. No storage for freight or passengers. Military acft specialist available for off-load. 1-60k Loader, 2-25k Loaders NGSL, 1-10k Fork Lift. Adjustable aircraft steps available for all large aircraft. Marshalling, ground power, LOX available. Aircraft operators should expect to provide towing arm.</p>

ORTL AD 2.5 PASSENGER FACILITIES

1	Hotels at/near aerodrome	Nil
2	Restaurants	Nil
3	Transportation	Nil.
4	Medical facilities	Nil
5	Bank and Post Office	Nil
6	Tourist Office	Nil
7	Remarks	Nil

ORTL AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	ARFF Crash Category 7
2	Rescue Equipment	Level III Medical Facility
3	Capability for removal of disabled aircraft	Limited assistance using military assets
4	Remarks	Nil

ORTL AD 2.7 SEASONAL AVAILABILITY

1	Type(s) of clearing equipment	Nil
2	Clearance priorities	Nil
3	Remarks	Nil

ORTL AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS DATA

1	Surface and strength of aprons	Concrete, Alpha ramp 38RBWT, Bravo ramp 48RBWT
2	Width, surface and strength of TWYs	FW TWYs are B, D, E G, H RW TWYs are B, D, E, G, H, B7-B12 TWY A is 100FT wide, TWY B is 70FT wide, TWY C, D, E, F, G, and H are 66FT wide. TWY B7-B12 are 50FT wide
3	Location and elevation of altimeter checkpoints	Not available
4	TACAN and INS checkpoints	Not available
5	Remarks	TWY E closed between RWY 30R/12L and RWY 30L/12R. Acft must coordinate parking with tower/Command post/airfield management Aerobridges not AVBL. <i>Note: All aircraft are to be directed by a marshaller to parking.</i>

ORTL AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	Use of aircraft stand ID signs, TWY guide lines and visual docking/parking guidance system at aircraft stands	Reflective distance remaining markings. TWY and RWY signage.
2	RWY and TWY markings and lights	No approach lights. RWY Edge Lights every 200FT. RWY 12L/R and 30 L/R Emergency Airfield Lighting System (EALS) in use operating at reduced intensity, non-standard lighting. REILS, HIRLS, TWY (supplemented by solar reflectors). TWY lighting limited, exercise extreme caution.
3	Stop bars	NIL
4	Remarks	TWY ALPHA limited to rotary wing acft between TWYs KILO and CHARLIE. Rotary wing traffic parking on CHARLIE RAMP will ground taxi to the ramp using TWY KILO or JULIET.

ORTL AD 2.10 AERODROME OBSTACLES

1	RWY12L	ORTL Obstacle Chart not published
2	RWY12R	ORTL Obstacle Chart not published
3	RWY30L	ORTL Obstacle Chart not published
4	RWY30R	ORTL Obstacle Chart not published
5	Remarks: Ant Tower 30°56'26.7"N 46°05'41.9"E 98' AGL (121' AMSL)	

ORTL AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

ORTL 2.11.1 Meteorological services are available from Ali Base weather. Limited weather information, using the location designator of KQXJ vice the ICAO airfield designator, is available from the following websites:

Open access website: <http://adds.aviationweather.noaa.gov/>
 Military only websites: <https://afwin.afwa.af.mil/> or <https://28ows.shaw.af.mil/>

ORTL AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	12L	12R	30L	30R
2	BRG True and Mag	118.45°T, 115.45°M	118.45°T, 115.45°M	298.47°T, 295.47°M	298.46°T, 295.46°M
3	RWY Dimensions	10935FT x 148FT (3333M x 45M)	9991FT x 148FT (3045M x 45M)	9991FT x 148FT (3045M x 45M)	10935FT x 148FT (3333M x 45M)
4	PCN	41 R/W/B/T	45 R/B/W/T	45 R/B/W/T	41 R/W/B/T

5	THR Coordinates	30°56'40.83"N 046°04'33.37"E	30°56'24.54"N 046°04'29.11"E	30°55'37.42"N 046°06'09.96"E	30°55'49.26"N 046°06'23.76"E
6	THR Elevation	19FT	19FT	19FT	20FT
7	Slope of RWY/SWY	Unknown	Unknown	Unknown	Unknown
8	SWY Dimensions	Unknown	Unknown	Unknown	Unknown
9	CWY Dimensions	Not calculated	Not calculated	Not calculated	Not calculated
10	Strip Dimensions	Not calculated	Not calculated	Not calculated	Not calculated
11	Obstacle free zone	Not calculated	Not calculated	Not calculated	Not calculated
12	Remarks	Nil	arresting gear 1460ft fm approach end	Nil	arresting gear 1450ft fm approach end

ORTL AD 2.13 DECLARED DISTANCES

1	RWY	12L	12R	30L	30R
2	TORA	10935FT (3333M)	9991FT (3045M)	9991FT (3045M)	10935FT (3333M)
3	TODA	10935FT (3333M)	9991FT (3045M)	9991FT (3045M)	10935FT (3333M)
4	ASDA	10935FT (3333M)	9991FT (3045M)	9991FT (3045M)	10935FT (3333M)
5	LDA	10935FT (3333M)	9991FT (3045M)	9991FT (3045M)	10935FT (3333M)
6	Remarks	Nil	Nil	Nil	Nil

ORTL AD 2.14 APPROACH AND RUNWAY LIGHTING

ORTL 2.14.1 Status of Ali Base's approach and RWY lighting is available via NOTAM.

ORTL AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Aerodrome Beacon	Nil
2	Location and lighting of anemometer and LDG direction indicator	Not fitted
3	TWY edge and centerline	Centerline lighting not available, solar powered edge

	lighting	lighting on all taxiways except for TWY A
4	Secondary power supply including switch-over time	Nil
5	Remarks	Nil

ORTL AD 2.16 HELICOPTER LANDING AREA

1	Coordinates of touchdown and lift-off point (TLOF) threshold of final approach and take-off (FATO)	To be determined
2	TLOF and/or FATO area elevation	To be determined
3	TLOF and FATO area dimensions, surface, strength, marking	To be determined
4	True and MAG BRG of FATO	To be determined
5	Declared distance available	To be determined
6	Approach and FATO lighting	To be determined
7	Remarks	Nil

ORTL AD 2.17 AIR TRAFFIC SERVICES AIRSPACE

1	Airspace designation and lateral limits	Detailed in ENR 1.4
2	Vertical limits	
3	Airspace classification	
4	Callsign and Languages	Ali...(Tower, Approach or Control), English
5	Transition altitude	13 000 FT
6	Remarks	ATS provided by military controllers operating IAW ICAO and USAF Military Standards. Radar traffic advisories available on transponder equipped aircraft only.

ORTL AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
ACC	Ali Center	132.775 MHz 322.050 MHz	H24	Primary Secondary
APP	Ali Approach	126.925 MHz 324.925 MHz	H24	Primary Secondary
TWR	Ali Tower	128.800 MHz 397.725 MHz	H24	Primary Secondary
GROUND	Ali Ground	120.700 MHz 282.350 MHz	H24	Primary Secondary
ATIS	N/A	N/A	N/A	Nil

ORTL AD 2.19 RADIO NAVIGATION AND LANDING AIDS

Type of Aid	Ident	FREQ	Hours of operation	Position of antenna	Elevation of DME	Remarks
TACAN 3E	TAL	CH84X	H24	N30°56'06.94" E046°05'26.15"	19 FT	For Military Use Only
PAR 3°	N/A	As directed by APP	H24 (subject to staffing)	N30°56'07.00" E046°05'19.30"	N/A	RWY 12R/30L For Military Use Only
SRA 3E	N/A	As directed by APP	H24 (subject to staffing)	N30°56'17.72" E046°05'37.69"	N/A	For Military Use Only
Remarks	Military Approach, Departure and Aerodrome information available from: https://164.214.2.62/products/digitalaero/index.cfm#flip Then under Terminal Instrument Procedure select Europe/North Africa/Middle East, then select Ali Base ORTL					

ORTL AD 2.20 LOCAL TRAFFIC REGULATIONS

ORTL 2.20.1 Marshaller assistance may be requested and further information can be obtained from the TWR or SMC. When a local regulation is of importance for the safe operation of aircraft on the apron, the information shall be given to each aircraft by the TWR or SMC.

ORTL 2.20.2 Local Traffic Regulations may be requested, in writing, from the Iraq Civil Aviation Authority at the address detailed in GEN 0.1.

ORTL 2.20.3 **Removal of disabled aircraft from RWY.** When an aircraft is disabled on a RWY, it is the duty of owner or user of such aircraft to have it removed as soon as possible. If a disabled aircraft is not removed from the RWY, by the owner or user, as quickly as possible, the aircraft will be removed by the aerodrome authority at the owner's or user's expense.

ORTL 2.20.4 No 180 degree turns on runway for large frame aircraft unless no other option is available.

ORTL 2.20.5 All large frame aircraft are to start takeoff roll one thousand feet from the threshold of RWY 30L/12R.

ORTL 2.20.6 Heavy aircraft should avoid using reverse thrusters. If reverse thrusters are required, use the in-boards only to the maximum extent possible to avoid FOD damage. All C-130 or larger aircraft must use minimum power settings during taxi operations, i.e. in-board engines only.

ORTL AD 2.21 NOISE ABATEMENT PROCEDURES**ORTL 2.21.1 Departures**

Take-off to 1000 ft AGL Take-off power and take-off flaps climb at V2 +10kt.

1000-3000 ft AGL Climb at V2+10kt.

At 3000 ft AGL Normal speed and flap retraction schedules to enroute climb.

Note: *Pilots unable to comply with above procedure shall inform ATC.*

ORTL 2.21.2 Arrivals

Execute final approach at the highest altitude possible (MAX 3000FT) observing ATC instructions, maintain this altitude as long as possible, at least until intercepting ILS glide slope.

Reverse thrust other than idle shall not be used between 2330-0600 LMT except for safety reasons.

ORTL AD 2.22 FLIGHT PROCEDURES

ORTL 2.22.1.General

ORTL 2.22.1.1 Within Class A airspace (i.e. above FL 290) all aircraft must operate Instrument Flight Rules (IFR). Additionally, civilian aircraft must operate IFR in Class B but are to operate VFR when flying in VMC in Class D, E and G airspace (flying below 12 000 FT AAMSL). Civilian aircraft must notify ATC if unable to operate VFR when below 12 000 FT using the phrase "UNABLE VFR". The use of VFR does not negate the requirement for aircraft to carry IFR fuel reserves.

ORTL 2.22.1.2 In airspace where VFR operations are approved, flights should be carried out in accordance with VFR as specified in ENR1.2 and ICAO Annexes 2 and 11 (particularly regarding visibility and clearance from cloud). Compliance with these procedures does not relieve pilots of their responsibility to see and avoid other aircraft, or to maintain safe terrain/obstacle clearance at all times when operating VFR.

ORTL 2.22.2 Procedures within Ali Base TMA

ORTL 2.22.2.1 The inbound, transit and out bound routes on the charts may be varied at the direction of ATS. If necessary, in case of congestion, inbound aircraft may also be instructed to hold at one of the designated airway reporting points.

ORTL 2.22.3 Radar procedures within Ali Base TMA

ORTL 2.22.3.1 **Radar vectoring and sequencing.** Normally, aircraft will be vectored and sequenced from DISAR and BSR reporting points to the appropriate final approach track (ASR, PAR, TACAN), so as to ensure an expeditious flow of traffic. Radar vectors and flight levels/altitudes will be provided for spacing and separating the aircraft so that correct LDG intervals are maintained, taking into account aircraft characteristics. Radar vectoring charts are not published since the instrument approach procedures exist at all times until the point where the pilot will resume navigation on final approach or in the circuit.

ORTL 2.23.3.2 **Primary radar approaches.** Primary radar approaches will be carried out for RWYs 12R and 30L as step down commencing descent from 10 NM at an altitude of 900m. Primary radar final approaches will be terminated when aircraft established ILS or when

aircraft established visual contact. Missed approach procedure to be followed in the absence of other ATS instructions are as detailed on the Instrument Approach Charts.

ORTL 2.23.3.3 **Communication failure.** In the event of communication failure, pilots shall act in accordance with communication failure procedures in ICAO Annex 2.

ORTL AD 2.23 ADDITIONAL INFORMATION

ORTL 2.23.1 All aircraft arriving and departing ORTL shall operate VFR unless IMC exists. Practice instrument approaches and departures not available.

ORTL AD 2.24 CHARTS RELATED TO AN AERODROME

ICAO Charts for Ali Base International Airport		
Charts are under development for Ali Base. See http://164.214.2.62/products/digitalaero/index.html for the latest charts.		
1	Aerodrome Chart - ICAO	Not produced
2	Aircraft Parking/Docking Chart – ICAO	Not produced
3	Aerodrome Ground Movement Chart – ICAO	Not produced
4	Precision Approach Terrain Chart – ICAO	Not produced
5	Aerodrome Obstacle Chart – ICAO Type A	Not produced
6	Area Chart – ICAO (arrival and transit routes)	Not produced
7	Standard Departure Chart – Instrument – ICAO	Not produced
8	Area Chart – ICAO (arrival and transit routes)	Not produced
9	Standard Arrival Chart – Instrument - ICAO	Not produced
10	Instrument Approach Chart – ICAO	Not produced
11	Visual Approach Chart	Not produced
12	Bird concentration in the vicinity of the aerodrome	Not produced

ORTI AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORTI – Al Taji Airfield

ORTI AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

ORTI 2.2.1 The facilities and procedures listed below do not necessarily comply with, or adhere to, the requirements of ICAO Annex 14.

1	Aerodrome Reference Point coordinates and site	N33°31'22.1" E044°15'25.9" Located at center of RWY
2	Direction and distance from city	Generally N/NW, approx. 14 NM
3	Elevation and Reference Temperature	121 FT, 44°C
4	Geoid undulation	Not determined
5	Magnetic variation/Annual change	UNK
6	Aerodrome Administration Address Telephone Telefax Telex AFS Address	3d Infantry Division Aviation Brigade POC: CW5 Asuncion VOIP: 302-242-6036 DSN: 318-834-3801
7	Types of traffic permitted	IFR and VFR
8	Transition altitude and level	13 000 FT

ORTI AD 2.3 OPERATIONAL HOURS

1	Aerodrome Administration	TBD
2	Customs and Immigration	TBD
3	Health and Sanitization	TBD
4	AIS Briefing Office	TBD
5	ATS Reporting Office	TBD
6	Met Office	24 hrs
7	Air Traffic Services	CTL TWR (24 hours); GCA (1900-0500 7 days/wk; any time Wx is less than 1000' ceiling or 3 SM visibility)
8	Fueling	Cold refuel 24 hrs (PPR required); Taji FARP available 24 hrs
9	Handling	TBD
10	Security	24 hours
11	De-icing	TBD
12	Remarks	24 hour cold refuel PPR required for transit aircraft. Taji FARP located 38S MC 3220 1116. Contact Taji FARP at DSN 318-834-3014/3015 or VOIP 242-6160 for PPR. Taji FARP FREQ 88.10. Permission to operate in the Baghdad FIR is coordinated through Regional Air Movements Coordination Center (RAMCC). Refer GEN 1.2 for current procedures and requirements

ORTI AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	TBD
2	Fuel and oil types	TBD
3	Fueling facilities and capacity	See remarks under operational hours
4	De-icing facilities	TBD
5	Hanger space for visiting aircraft	TBD
6	Repair facilities for visiting aircraft	TBD
7	Remarks	

ORTI AD 2.5 PASSENGER FACILITIES

1	Hotels at/near aerodrome	TBD
2	Restaurants	TBD
3	Transportation	TBD
4	Medical facilities	TBD
5	Bank and Post Office	TBD
6	Tourist Office	TBD
7	Remarks	

ORTI AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	UNK
2	Rescue Equipment	UNK
3	Capability for removal of disabled aircraft	Assistance available using military assets
4	Remarks	

ORTI AD 2.7 SEASONAL AVAILABILITY

1	Type(s) of clearing equipment	TBD
2	Clearance priorities	TBD
3	Remarks	

ORTI AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS DATA

1	Surface and strength of aprons	N/A
2	Width, surface and strength of TWYs	Width: UNK Surface: Concrete Strength: UNK
3	Location and elevation of altimeter checkpoints	N/A
4	VOR and INS checkpoints	N/A
5	Remarks	5 TWYs

ORTI AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	Use of aircraft stand ID signs, TWY guide lines and visual docking/parking guidance system at aircraft stands	See ORTI AD 2-24
2	RWY and TWY markings and lights	RWY lights are in place for the approach to RWY 34/16 and the length of the RWY. Amber parking lights for Taji FARP are in place. TWY lighting exists for TWYs Alpha, Bravo, Charlie and Delta. Pilot-controlled intensity lighting is not available.
3	Stop bars	N/A
4	Remarks	

ORTI AD 2.10 AERODROME OBSTACLES

1	RWY16	ORTI Obstacle Chart N/A
2	RWY34	ORTI Obstacle Chart N/A
3	Remarks	

ORTI AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

ORTI 2.11.1 Limited weather information, using the location designator of KQAA vice the ICAO airfield designator, is available from the following websites:

Open access website: <http://adds.aviationweather.noaa.gov/>
Military only websites: <https://afwin.afwa.af.mil/> or <https://28ows.shaw.af.mil/>

ORTI AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	16	34
2	BRG True and Mag	160 Magnetic	340 Magnetic
3	RWY Dimensions	5790FT x 164FT (1764M x 50M)	5790FT x 164FT (1754M x 50M)
4	PCN	UNK	UNK
5	THR Coordinates	MGRS 38SMC3072010485 N33°31'52.96" E044°15'13.14"	MGRS 38SMC3126008810 N33°30'58.86" E044°15'35.45"
6	THR Elevation	121FT	121FT
7	Slope of RWY/SWY	UNK	UNK
8	SWY Dimensions	UNK	UNK

9	CWY Dimensions	Not calculated	Not calculated
10	Strip Dimensions	Not calculated	Not calculated
11	Obstacle free zone	Not calculated	Not calculated
12	Remarks	Nil	Nil

ORTI AD 2.13 DECLARED DISTANCES

1	RWY	16	34
2	TORA	5755FT (1755M)	5755FT (1755M)
3	TODA	5755FT (1755M)	5755FT (1755M)
4	ASDA	5755FT (1755M)	5755FT (1755M)
5	LDA	5755FT (1755M)	5755FT (1755M)
6	Remarks	Nil	Nil

ORTI AD 2.14 APPROACH AND RUNWAY LIGHTING

ORTI 2.14.1 Further information on Taji's approach and RWY lighting is available at the following military website:

<https://www.notams.jcs.mil>

1	RWY	16	34
2	Type, length and intensity of approach lighting	N/A	N/A
3	Threshold lights, colors and wing bars	Red lights on final approach end, red at departure end	Red lights on final approach end, red at departure end
4	Type of visual approach slope indicator system	N/A	N/A
5	Length of RWY touchdown zone indicator lights	N/A	N/A
6	Length spacing color and intensity of RWY centerline	N/A	N/A

	lights		
7	Length spacing color and intensity of RWY edge lights	Amber, solar powered lights. Spacing distance unknown	Amber, solar powered lights. Spacing distance unknown.
8	Color of RWY end lights and wingbars	Red lights at approach/departure end	Red lights at approach/departure end
9	Length and color of stopway lights	N/A	N/A
10	Remarks	Nil	Nil

ORTI AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Aerodrome Beacon	N/A
2	Location and lighting of anemometer and LDG direction indicator	N/A
3	TWY edge and centerline lighting	N/A
4	Secondary power supply including switch-over time	N/A; RWY lights are solar-powered
5	Remarks	Nil

ORTI AD 2.16 HELICOPTER LANDING AREA

1	Coordinates of touchdown and lift-off point (TLOF) threshold of final approach and take-off (FATO)	To be determined
2	TLOF and/or FATO area elevation	To be determined
3	TLOF and FATO area dimensions, surface, strength, marking	To be determined
4	True and MAG BRG of FATO	To be determined
5	Declared distance available	To be determined
6	Approach and FATO lighting	To be determined
7	Remarks	Nil

ORTI AD 2.17 AIR TRAFFIC SERVICES AIRSPACE

1	Airspace designation and lateral limits	5 NM Class D airspace
2	Vertical limits	
3	Airspace classification	
4	Callsign and Languages	Taji Tower (English)
5	Transition altitude	As directed by tower
6	Remarks	Nil

ORTI AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
TWR	Taji Tower	122.0 MHz 40.850 MHz 227.325 MHz	24 hours	Primary Secondary
GCA Feeder	Taji GCA	141.275 MHz 43.7(A) MHz 300.050 MHz	1900-0500 or weather < 1000'/3sm	Primary Secondary
GCA Final	Taji GCA	139.600 MHz 325.675 MHz	1900-0500 or weather < 1000'/3sm	Primary Secondary

ORTI AD 2.19 RADIO NAVIGATION AND LANDING AIDS

Type of Aid	Ident	FREQ	Hours of operation	Position of antenna	Elevation of DME	Remarks
NDB	TAJI	1650 MHz	24 hrs.	UNK	UNK	Nil

ORTI AD 2.20 LOCAL TRAFFIC REGULATIONS

Pilots will announce their position in relation to the sector diagram. Note that there is a sector suffix for the airspace within the Class D, so a two-letter sector identifier is required. The single sector designator is used for flight-following beyond the 5NM Class D. Call the appropriate sector inbound or outbound. Example: "Taji Tower, VIPER77 is INDIA ALPHA inbound." Or "Taji Tower, HEAVYARM04 requests DELTA ALPHA departure." Aircraft North of the MB/MC "00" grid line within the MNC-I AO Baghdad Boundary will maintain radio contact with Taji Tower for advisories and position reports. Contact Baghdad Radio on 127.350, 352.375 and 61.675, South of the MB/MC "00" grid line and Balad Approach above 3000' AMSL. Contact Taji tower within the Taji Class D Airspace. South bound traffic should FREQ change to Baghdad Radio prior to the MC 00 east-west grid line. All traffic must avoid the PAH north of the RWY. Inbound altitude day and night is 200FT AGL. Outbound altitude day and night is 300FT AGL.

ORTI AD 2.21 NOISE ABATEMENT PROCEDURES

ORTA 2.21.1 **Departures.** Avoid overflight of Life Support Area (LSA) west of the airfield on departure.

ORTA 2.21.2 **Arrivals.** Avoid overflight of Life Support Area (LSA) west of airfield.

ORTI AD 2.22 FLIGHT PROCEDURES

ORTI 2.22.1 Pilots will announce their position in relation to the sector diagram. Note that there is a sector suffix for the airspace within the Class D, so a two-letter sector identifier is required. The single sector designator is used for flight-following beyond the 5NM Class D. Call the appropriate sector inbound or outbound. Example: "Taji Tower, VIPER77 is INDIA ALPHA inbound." Or "Taji Tower, HEAVYARM04 requests DELTA ALPHA departure." Aircraft North of the MB/MC "00" grid line within the MNC-I AO Baghdad Boundary will maintain radio contact with Taji Tower for advisories and position reports. Contact Baghdad Radio on 127.350, 352.375 and 61.675, South of the MB/MC "00" grid line and Balad Approach above 3000FT AMSL. Contact Taji tower within the Taji Class D Airspace. South

bound traffic should **FREQ** change to Baghdad Radio prior to the MC 00 east-west grid line. All traffic must avoid the PAH north of the RWY. Inbound altitude day and night is 200FT AGL. Outbound altitude day and night is 300FT AGL.

ORTI AD 2.23 ADDITIONAL INFORMATION

None

ORTI AD 2.24 CHARTS RELATED TO AN AERODROME

ICAO Charts for Al Taji Airfield		
1	Aerodrome Chart - ICAO	Not produced
2	Aircraft Parking/Docking Chart – ICAO	Not produced
3	Aerodrome Ground Movement Chart – ICAO	Not produced
4	Precision Approach Terrain Chart – ICAO	Not produced
5	Aerodrome Obstacle Chart – ICAO Type A	Not produced
6	Area Chart – ICAO (arrival and transit routes)	Not produced
7	Standard Departure Chart – Instrument – ICAO	Not produced
8	Area Chart – ICAO (arrival and transit routes)	Not produced
9	Standard Arrival Chart – Instrument - ICAO	Not produced
10	Instrument Approach Chart – ICAO	Not produced
11	Visual Approach Chart	Not produced
12	Bird concentration in the vicinity of the aerodrome	Not produced

ORTS AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORTS – Tikrit South Airport

ORTS AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N34°32'06.00" E043°40'42.00" The geographic center of the airfield
2	Elevation and Reference Temperature	330FT (100.6M) and 43.1°C

ORUB AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORUB – Ubaydah Bin Al Jarrah Airfield

ORUB AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N32°28'54.00" E045°45.24.00 "The geographic center of the airfield
2	Elevation and Reference Temperature	68FT

ORUB AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

1	RWY	11L	29R	11R	29L
2	BRG	TBD	TBD	TBD	TBD
3	RWY Dimensions	10180FT X 150 FT (3102M x 45M)	10180FT X 150 FT (3103M x 45M)	11680FT X 150 FT (3560M x 45M)	11680FT X 150 FT (3560M x 45M)
12	Remarks	Nil	Nil	Nil	Nil

ORUB AD 2.13 DECLARED DISTANCES

1	RWY	11L	29R	11R	29L
2	TORA	10180FT 3102M	10180FT 3102M	11680FT 3560M	11680FT 3560M
3	TODA	10180FT 3102M	10180FT 3102M	11680FT 3560M	11680FT 3560M
6	Remarks	Nil	Nil	Nil	Nil

ORUB AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
TWR	Blair Tower	135.50MHz 244.05MHz	TBD	Primary Secondary
Remarks	Nil			

ORUB AD 2.23 ADDITIONAL INFORMATIONORUB 2.23.1 Additional information is available at <https://www.afd.shaw.af.mil>.

ORUQ AD 2.1 AERODROME LOCATION INDICATOR AND NAME

ORUQ – Umm Qasr Airport

ORUQ AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N30°01'12.00" E047°55'24.00" The geographic center of the airfield
2	Elevation and Reference Temperature	33FT (10.1M) and 43.1°C

AD 3. HELIPORTS**ORAQ AD 3.1 HELIPORT LOCATION INDICATOR AND NAME**

ORAQ – Al Qaim Landing Zone

ORAQ AD 3.2 HELIPORT GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N34°15'58.57" E041°09'44.05" The geographic center of the airfield
2	Elevation and Reference Temperature	797FT (242.9 M) and 43.1°C
3	Magnetic variation/Annual change	4°E as at APR 2004, annual change not determined
4	Remarks	Heliport operator: United States Marine Corps Ph: DSN 302 3635 171

ORAQ AD 3.3 OPERATIONAL HOURS

1	Aerodrome Administration	H24
2	Customs and Immigration	Not Available
3	Health and Sanitation	Not Available
4	AIS Briefing Office	TBD
5	ATS Reporting Office	TBD
6	Met Office	H24
7	Air Traffic Services	H24
8	Fueling	H24
10	Security	H24
12	Remarks	Nil

ORAQ AD 3.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	TBD
2	Fuel and oil types	TBD
3	Fueling facilities and capacity	TBD
4	De-icing facilities	TBD
5	Hanger space for visiting aircraft	TBD
6	Repair facilities for visiting aircraft	TBD
7	Remarks	Nil

ORAQ AD 3.5 HELICOPTER LANDING AREA

1	Coordinates of touchdown and lift-off point (TLOF) threshold of final approach and take-off (FATO)	TBD
2	TLOF and/or FATO area elevation	TBD
3	TLOF and FATO area dimensions, surface, strength, marking	TBD

4	True and MAG BRG of FATO	TBD
5	Declared distance available	TBD
6	Approach and FATO lighting	TBD
7	Remarks	TBD

ORAQ AD 3.6 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
TWR	Old School Tower	255.80 MHz 139.55 MHz	H24	VHF by request only

ORAQ AD 3.7 LOCAL TRAFFIC REGULATIONS

ORAQ 3.7.1 Overflight of buildings, fueling spots, fuel tanks and parked aircraft prohibited.

ORAQ AD 3.8 OBSTACLES

ORAQ 3.8.1 Tower 200FT AGL at N34⁰16'07.24" E041⁰09'17.22" marked with red flashing beacon.

ORRW AD 3.1 HELIPORT LOCATION INDICATOR AND NAME

ORRW – Korean Village Landing Zone

ORRW AD 3.2 HELIPORT GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N33°01'05.02" E039°56'15.62" The geographic center of the airfield
2	Elevation and Reference Temperature	2500FT (762 M) and 43.1°C
3	Magnetic variation/Annual change	4°E as at APR 2004, annual change not determined
4	Remarks	Helicopter operator: United States Marine Corps Ph: DSN 302-3636-119

ORRW AD 3.3 OPERATIONAL HOURS

1	Aerodrome Administration	H24
2	Customs and Immigration	Not Available
3	Health and Sanitation	Not Available
4	AIS Briefing Office	TBD
5	ATS Reporting Office	TBD
6	Met Office	H24
7	Air Traffic Services	H24
8	Fueling	H24
10	Security	H24
12	Remarks	Nil

ORRW AD 3.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	TBD
2	Fuel and oil types	TBD
3	Fueling facilities and capacity	TBD
4	De-icing facilities	TBD
5	Hanger space for visiting aircraft	TBD
6	Repair facilities for visiting aircraft	TBD
7	Remarks	Nil

ORRW AD 3.5 HELICOPTER LANDING AREA

1	Coordinates of touchdown and lift-off point (TLOF) threshold of final approach and take-off (FATO)	TBD
2	TLOF and/or FATO area elevation	TBD
3	TLOF and FATO area dimensions, surface, strength, marking	TBD
4	True and MAG BRG of	TBD

	FATO	
5	Declared distance available	TBD
6	Approach and FATO lighting	TBD
7	Remarks	Nil

ORRW AD 3.6 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
TWR	KAY-VEE Tower	339.35 MHz 141.3 MHz	H24	Nil

ORRW AD 3.7 LOCAL TRAFFIC REGULATIONS

ORRW 3.7.1 Overflight of buildings, fueling spots, fuel tanks and parked aircraft prohibited

ORRW AD 3.8 OBSTACLES

ORRW 3.8.1 Tower 200FT AGL at N33⁰01'11.60" E039⁰55'44.31" marked with red flashing beacon.

ORRW 3.8.2 Tower 200FT AGL located at N33⁰01'05.02" E039⁰56'15.60" marked with intermittent hazard light.

ORWH AD 3.1 HELIPORT LOCATION INDICATOR AND NAME

ORWH – Washington Army Heliport

ORWH AD 3.2 HELIPORT GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome Reference Point coordinates and site	N33°18.27' E44°24.21' The geographic center of the airfield
2	Elevation and Reference Temperature	124FT (38 M)
3	Magnetic variation/Annual change	4°E as at APR 2004, annual change not determined
4	Remarks	Heliport operator United States Army Ph: DSN 302-530-9312

ORWH AD 3.3 OPERATIONAL HOURS

1	Aerodrome Administration	TBD
2	Customs and Immigration	Not Available
3	Health and Sanitation	Not Available
4	AIS Briefing Office	TBD
5	ATS Reporting Office	TBD
6	Met Office	TBD
7	Air Traffic Services	0400Z-1500Z
8	Fueling	0400Z-1500Z
10	Security	H24
12	Remarks	Nil

ORWH AD 3.4 HANDLING SERVICES AND FACILITIES

1	Cargo handling facilities	TBD
2	Fuel and oil types	TBD
3	Fueling facilities and capacity	TBD
4	De-icing facilities	Nil
5	Hanger space for visiting aircraft	Nil
6	Repair facilities for visiting aircraft	Nil
7	Remarks	Prior permission required PPR required for LDG and fuel Ph: DSN 302-530-9312

ORWH AD 3.5 HELICOPTER LANDING AREA

1	Coordinates of touchdown and lift-off point (TLOF) threshold of final approach and take-off (FATO)	To be determined
2	TLOF and/or FATO area elevation	To be determined
3	TLOF and FATO area dimensions, surface,	657FT BY 327FT, concrete

	strength, marking	
4	True and MAG BRG of FATO	To be determined
5	Declared distance available	To be determined
6	Approach and FATO lighting	H lighting center of pad
7	Remarks	LDG direction 33/15

ORWH AD 3.6 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service designation	Callsign	FREQ	Hours of operation	Remarks
TWR	Washington Tower	125.100 MHz 330.750 MHz	0400 – 1800Z DAILY	Primary Secondary

ORWH AD 3.7 LOCAL TRAFFIC REGULATIONS

ORWH 3.7.1 Over flight of hanger and helo ramp at south end of heliport prohibited.